

Table of Contents

Executive Summary	S-1
Foreword	F-1
F.1 Introduction	F-1
F.1.1 Changes Since DEIS.....	F-2
F.1.2 Combined FEIS/ROD	F-3
F.1.3 Information Provided in this Foreword	F-3
F.2 Identification of Project Sponsor and Summary of Design Refinements and New Information	F-3
F.2.1 Identification of Project Sponsor	F-3
F.2.2 Design Refinements	F-4
F.2.2.1 Surface Alignment in the Meadowlands, New Jersey	F-4
F.2.2.2 New Hudson River Tunnel and Associated Construction Activities in New Jersey	F-5
F.2.2.3 Construction in the Hudson River.....	F-7
F.2.2.4 Construction in New York	F-9
F.2.2.5 Change to Project Construction Schedule	F-11
F.2.3 New Information Available.....	F-11
F.2.3.1 Changes to Affected Environment in Project Study Area.....	F-11
F.2.3.2 Amtrak’s North River Tunnel Interim Reliability Improvements Program ...	F-13
F.2.3.3 Potential Alternative Approaches for Rehabilitation of the North River Tunnel.....	F-13
F.2.3.4 New Information Affecting Analysis of Noise and Vibration	F-14
F.2.3.5 Base Flood Elevation Mapping	F-14
F.2.3.6 Revised Methodology for Evaluating Impacts for Project Components in New York City.....	F-15
F.3 Summary of Revisions in this FEIS	F-15
Chapter 1: Purpose and Need.....	1-1
1.1 Introduction	1-1
1.1.1 Roles and Responsibilities.....	1-2
1.1.2 Project Sponsor and Joint Lead Agency.....	1-4
1.1.3 Overview of Project Purpose and Need.....	1-4
1.2 Project Background	1-5
1.2.1 Access to the Region’s Core (ARC) Project	1-6
1.2.2 Gateway Program	1-7
1.2.3 NEC FUTURE	1-7
1.2.4 Project’s Relationship to Proposed Capacity Enhancement	1-8



1.3	Project Purpose.....	1-9
1.4	Project Need	1-9
1.4.1	Need to Rehabilitate the North River Tunnel	1-9
1.4.2	Need to Maintain Existing Passenger Rail Service	1-11
1.4.3	Summary	1-12
1.5	Goals and Objectives	1-13
Chapter 2: Project Alternatives and Description of the Preferred Alternative		2-1
2.1	Introduction	2-1
2.2	Project Setting: Rail Operations in the North River Tunnel and PSNY Complex	2-2
2.2.1	North River Tunnel	2-2
2.2.2	PSNY Operations	2-4
2.3	Alternatives Development and Process Used to Identify the Preferred Alternative	2-5
2.3.1	Development and Evaluation of Preliminary Alternatives	2-5
2.3.2	Refined Screening: Evaluation of Alignment Options	2-7
2.3.2.1	Build Alternative Alignment	2-7
2.3.2.2	Alignment Options for Tunnel Between New Jersey Portal and Manhattan Bulkhead	2-10
2.3.3	Additional Alternatives Considered After Completion of the DEIS	2-12
2.3.3.1	Alternative Construction Methods	2-12
2.3.3.2	Alternative Approaches for Rehabilitation of the North River Tunnel	2-13
2.4	No Action Alternative	2-16
2.5	Preferred Alternative	2-18
2.5.1	Surface Alignment in New Jersey	2-19
2.5.1.1	Alignment	2-19
2.5.1.2	Access Roads	2-20
2.5.1.3	Track	2-20
2.5.1.4	Drainage	2-20
2.5.1.5	Utilities	2-21
2.5.2	Hudson River Tunnel	2-21
2.5.2.1	Alignment	2-21
2.5.2.2	Tunnel Design	2-23
2.5.2.3	Track	2-23
2.5.2.4	Tunnel Drainage	2-23
2.5.2.5	Utilities	2-24
2.5.2.6	Tunnel Ventilation	2-24
2.5.2.7	Ancillary Facilities	2-25
2.5.3	Connection to PSNY Approach Tracks	2-29
2.5.4	Railroad Systems and Features	2-29
2.5.4.1	Power	2-29
2.5.4.2	Signals	2-30
2.5.4.3	Communication Systems	2-30
2.5.4.4	Safety and Security / Emergency Access	2-30

2.5.4.5	Resiliency / Flood Protection	2-31
2.5.5	Right-of-Way Requirements.....	2-33
2.5.5.1	New Jersey Surface Alignment.....	2-33
2.5.5.2	Hudson River Tunnel	2-33
2.5.5.3	Temporary Use of Lot 12 on Block 675	2-34
2.5.6	Rehabilitated North River Tunnel.....	2-35
2.5.6.1	Tunnel Design	2-35
2.5.6.2	Track	2-36
2.5.6.3	Drainage.....	2-37
2.5.6.4	Utilities.....	2-37
2.5.6.5	Tunnel Ventilation	2-37
2.5.6.6	Power	2-37
2.5.6.7	Signals and Communication Systems	2-37
2.5.6.8	Safety and Security / Emergency Access	2-37
2.5.6.9	Resiliency / Flood Protection	2-37
2.5.7	Rail Operations	2-38
2.5.7.1	Interim Operations with New Tunnel Complete and North River Tunnel Being Rehabilitated.....	2-39
2.5.7.2	Operations with Both Tunnels Complete	2-39
2.5.8	Estimated Project Cost	2-39
2.5.9	Schedule for Project Completion	2-40
2.6	Preferred Alternative Would Not Preclude Future Capacity Expansion Projects	2-40
Chapter 3: Construction Methods and Activities		3-1
3.1	Introduction	3-1
3.2	Overview of Construction Methods.....	3-2
3.2.1	Mining or Tunneling Techniques.....	3-4
3.2.1.1	Tunnel Boring Machines	3-5
3.2.1.2	Sequential Excavation Method Mining	3-6
3.2.1.3	Open Excavation	3-7
3.2.2	Ground Improvement Techniques	3-7
3.2.2.1	Jet Grouting	3-7
3.2.2.2	Deep Soil Mixing.....	3-7
3.2.2.3	Ground Freezing.....	3-8
3.2.3	Description of Surface Structure Elements	3-8
3.2.4	Other Anticipated Construction Measures	3-9
3.3	Description of Site-Specific Construction Activities	3-10
3.3.1	New Jersey Surface Alignment.....	3-11
3.3.1.1	Construction of Surface Track Support Systems	3-11
3.3.1.2	Drainage	3-12
3.3.1.3	Trackwork and Railroad Systems.....	3-13
3.3.1.4	Utility Relocation	3-13
3.3.1.5	Excavated Material and Disposal	3-13
3.3.1.6	Construction Staging Areas.....	3-13
3.3.1.7	Truck Routes and Access Roads	3-14



3.3.1.8	Schedule	3-14
3.3.2	Palisades Segment of the Hudson River Tunnel	3-15
3.3.2.1	Tunnel Excavation.....	3-15
3.3.2.2	Cross Passages	3-16
3.3.2.3	Tunnel Ventilation During Construction	3-16
3.3.2.4	Excavated Material and Disposal.....	3-17
3.3.2.5	Trackwork and Railroad Systems	3-17
3.3.2.6	Construction Staging Areas	3-18
3.3.2.7	Truck Routes	3-18
3.3.2.8	Schedule	3-19
3.3.3	Hoboken Shaft, Staging, and Fan Plant Site.....	3-20
3.3.3.1	Shaft Construction.....	3-21
3.3.3.2	Excavated Material and Disposal.....	3-21
3.3.3.3	Staging Site	3-22
3.3.3.4	Truck Routes	3-23
3.3.3.5	Fan Plant Construction	3-25
3.3.3.6	Schedule	3-25
3.3.4	Hudson River Tunnel Segment Beneath Hoboken and the Hudson River	3-25
3.3.4.1	Ground Improvement and Underpinning	3-26
3.3.4.2	Tunnel Excavation.....	3-27
3.3.4.3	Cross Passages	3-27
3.3.4.4	Tunnel Ventilation During Construction	3-28
3.3.4.5	Obstructions	3-28
3.3.4.6	Excavated Material and Disposal.....	3-28
3.3.4.7	Trackwork and Railroad Systems	3-29
3.3.4.8	Construction Staging Area and Truck Routes	3-29
3.3.4.9	Schedule	3-29
3.3.5	River Tunnel In-Water Work.....	3-30
3.3.5.1	Installation of Cofferdam	3-31
3.3.5.2	Soil Improvement	3-31
3.3.5.3	Excavated Material and Disposal.....	3-32
3.3.5.4	Removal of Cofferdam	3-32
3.3.5.5	Staging	3-32
3.3.5.6	Protection of Navigation	3-33
3.3.5.7	Schedule	3-33
3.3.6	Manhattan Waterfront Area	3-33
3.3.6.1	Ground Improvement Beneath Hudson River Park and Twelfth Avenue ...	3-34
3.3.6.2	SEM Tunnel Excavation Beneath Twelfth Avenue	3-37
3.3.6.3	Tunneling Through the Manhattan Bulkhead.....	3-37
3.3.6.4	Removal of Below-Ground Tunneling Obstructions.....	3-38
3.3.6.5	Excavated Material and Disposal.....	3-38
3.3.6.6	Construction Staging Area and Truck Routes	3-39
3.3.6.7	Schedule	3-39

3.3.7	Twelfth Avenue Shaft, Staging, and Fan Plant Site	3-39
3.3.7.1	Shaft Construction	3-39
3.3.7.2	Excavated Material and Disposal	3-40
3.3.7.3	Staging Site	3-40
3.3.7.4	Fan Plant Construction On Lot 1	3-41
3.3.7.5	Truck Routes	3-41
3.3.7.6	Schedule	3-42
3.3.7.7	Potential Build-Out of Parking Garage On Adjacent Property (Lot 12)	3-43
3.3.8	Tunnel from West 30th Street to PSNY	3-43
3.3.8.1	West 30th Street Excavation	3-43
3.3.8.2	Construction in the Hudson Yards Right-of-Way Preservation Project Segment.....	3-44
3.3.8.3	Tenth Avenue Cut-and-Cover Construction	3-45
3.3.8.4	New Connections to PSNY Approach Tracks at A Yard	3-45
3.3.8.5	Excavated Material and Disposal	3-46
3.3.8.6	Fan Plant At Tenth Avenue / 450 West 33rd Street	3-46
3.3.8.7	Trackwork, Railroad Systems, and MEP Finishing	3-46
3.3.8.8	Schedule	3-46
3.3.9	Coordination With Other Construction Projects	3-46
3.3.10	Rehabilitation of North River Tunnel	3-47
3.3.10.1	Staging.....	3-47
3.3.10.2	Provision of Redundant Fire-Life Safety Infrastructure and Decommissioning..	3-49
3.3.10.3	Rehabilitation Work.....	3-49
3.3.10.4	Recommissioning	3-50
3.3.10.5	Truck Routes	3-51
3.3.10.6	Schedule	3-51
3.4	Schedule	3-51
3.4.1	Overall Construction Schedule	3-52
3.4.2	Summary of Construction Activities by Site	3-52
Chapter 4: Analysis Framework		4-1
4.1	Introduction	4-1
4.2	Hudson Tunnel Project for Analysis	4-2
4.2.1	Alternatives for Analysis.....	4-2
4.2.2	Project Setting.....	4-3
4.2.3	Project Site.....	4-3
4.3	Approach for Analysis.....	4-5
4.3.1	Conditions Analyzed	4-5
4.3.2	Study Areas.....	4-6
4.3.3	Affected Environment in the Future	4-6
4.3.3.1	Transportation Projects	4-6
4.3.3.2	Development Projects.....	4-9
4.3.4	Analysis Methodology	4-11
4.4	Format of this EIS	4-11



Chapter 5A: Traffic and Pedestrians	5A-1
5A.1 Introduction	5A-1
5A.2 Analysis Methodology	5A-2
5A.2.1 Regulatory Context.....	5A-2
5A.2.2 Analysis Techniques	5A-2
5A.2.2.1 Traffic	5A-3
5A.2.2.2 Pedestrians	5A-7
5A.2.2.3 Safety Assessment	5A-8
5A.2.3 Study Areas	5A-8
5A.2.3.1 New Jersey	5A-8
5A.2.3.2 New York.....	5A-11
5A.3 Affected Environment: Existing Conditions.....	5A-15
5A.3.1 New Jersey.....	5A-15
5A.3.1.1 Tonnelle Avenue Staging Area	5A-15
5A.3.1.2 Hoboken Staging Area	5A-19
5A.3.2 Hudson River.....	5A-22
5A.3.3 New York	5A-22
5A.3.3.1 Traffic	5A-22
5A.3.3.2 Pedestrians	5A-24
5A.3.3.3 Safety Assessment	5A-24
5A.4 Affected Environment: Future Conditions	5A-25
5A.4.1 New Jersey.....	5A-27
5A.4.1.1 Tonnelle Avenue Staging Area Study Area	5A-28
5A.4.1.2 Hoboken Staging Area	5A-32
5A.4.2 Hudson River.....	5A-35
5A.4.3 New York	5A-35
5A.4.3.1 Traffic	5A-35
5A.4.3.2 Pedestrians	5A-39
5A.4.3.3 Safety Assessment	5A-41
5A.5 Impacts of No Action Alternative	5A-41
5A.6 Construction Impacts of the Preferred Alternative	5A-41
5A.6.1 Overview.....	5A-41
5A.6.2 New Jersey.....	5A-42
5A.6.2.1 Tonnelle Avenue Staging Area	5A-45
5A.6.2.2 Hoboken Staging Area	5A-57
5A.6.2.3 Pedestrians	5A-71
5A.6.3 Hudson River.....	5A-72
5A.6.4 New York	5A-72
5A.6.4.1 Traffic	5A-72
5A.6.4.2 Pedestrians	5A-79
5A.6.4.3 Safety Assessment	5A-81
5A.7 Permanent Impacts of the Preferred Alternative.....	5A-82

5A.8	Summary of Impacts Including Identified Mitigation	5A-82
5A.8.1	New Jersey	5A-82
5A.8.1.1	Tonnelle Avenue Staging Area	5A-82
5A.8.1.2	Hoboken Staging Area	5A-87
5A.8.2	New York.....	5A-95
5A.9	Measures to Avoid, Minimize, and Mitigate Impacts	5A-98
5A.9.1	General Traffic Mitigation Measures	5A-98
5A.9.2	Tonnelle Avenue Staging Area Study Area	5A-99
5A.9.3	Hoboken Staging Area Study Area	5A-99
5A.9.4	New York.....	5A-100
Chapter 5B:	Transportation Services	5B-1
5B.1	Introduction	5B-1
5B.2	Analysis Methodology	5B-2
5B.2.1	Regulatory Context	5B-3
5B.2.2	Analysis Techniques	5B-3
5B.2.3	Study Areas.....	5B-3
5B.3	Affected Environment: Existing Conditions.....	5B-3
5B.3.1	Intercity and Commuter Passenger Rail Service	5B-3
5B.3.1.2	Amtrak and NJ TRANSIT Operations via the Northeast Corridor	5B-3
5B.3.1.1	PSNY Complex.....	5B-5
5B.3.2	Hudson-Bergen Light Rail.....	5B-6
5B.3.3	New York City Subway Service	5B-6
5B.3.4	Bus Service	5B-6
5B.3.5	PATH Service.....	5B-7
5B.3.6	Freight Railroad Services.....	5B-7
5B.3.7	Hudson River Maritime Traffic	5B-8
5B.3.8	West 30th Street Heliport.....	5B-9
5B.4	Affected Environment: Future Conditions.....	5B-10
5B.4.1	Intercity and Commuter Passenger Rail Service	5B-10
5B.4.1.1	Amtrak and NJ TRANSIT Operations via the Northeast Corridor	5B-10
5B.4.1.2	Changes at PSNY.....	5B-13
5B.4.2	Hudson-Bergen Light Rail.....	5B-14
5B.4.3	New York City Subway Service	5B-14
5B.4.4	Bus Service	5B-14
5B.4.5	PATH Service.....	5B-15
5B.4.6	Freight Railroad Services.....	5B-15
5B.4.7	Hudson River Maritime Traffic	5B-15
5B.4.8	West 30th Street Heliport.....	5B-15
5B.5	Impacts of No Action Alternative	5B-15



5B.5.1	Intercity and Commuter Passenger Rail Service	5B-15
5B.5.2	Hudson-Bergen Light Rail	5B-16
5B.5.3	New York City Subway Service	5B-17
5B.5.4	Bus Service	5B-17
5B.5.5	PATH Service	5B-17
5B.5.6	Freight Railroad Services	5B-17
5B.5.7	Hudson River Maritime Traffic	5B-17
5B.5.8	West 30th Street Heliport	5B-17
5B.6	Construction Impacts of the Preferred Alternative	5B-17
5B.6.1	Overview	5B-17
5B.6.2	Intercity and Commuter Passenger Rail Service	5B-17
5B.6.2.1	Allied Interlocking (New Jersey)	5B-18
5B.6.2.2	NEC At Tonnelles Avenue (West Portal of North River Tunnel)	5B-18
5B.6.2.3	PSNY Complex (New York)	5B-19
5B.6.3	Hudson-Bergen Light Rail	5B-20
5B.6.4	New York City Subway Service	5B-21
5B.6.5	Bus Service	5B-21
5B.6.6	PATH Service	5B-22
5B.6.7	Freight Railroad Services	5B-22
5B.6.8	Hudson River Maritime Traffic	5B-22
5B.6.9	West 30th Street Heliport	5B-23
5B.7	Permanent Impacts of the Preferred Alternative	5B-24
5B.7.1	Overview	5B-24
5B.7.2	Intercity and Commuter Passenger Rail Service	5B-24
5B.7.3	Hudson-Bergen Light Rail	5B-25
5B.7.4	New York City Subway Service	5B-25
5B.7.5	Bus Service	5B-26
5B.7.6	PATH Service	5B-26
5B.7.7	Freight Railroad Services	5B-26
5B.7.8	Hudson River Maritime Traffic	5B-26
5B.7.9	West 30th Street Heliport	5B-27
5B.8	Measures to Avoid, Minimize, and Mitigate Impacts	5B-27
Chapter 6A: Land Use, Zoning, and Public Policy	6A-1	
6A.1	Introduction	6A-1
6A.2	Analysis Methodology	6A-2
6A.2.1	Regulatory Context	6A-2
6A.2.2	Analysis Techniques	6A-3
6A.2.3	Study Areas	6A-3
6A.3	Affected Environment: Existing Conditions	6A-4
6A.3.1	New Jersey	6A-4
6A.3.1.1	Land Use	6A-4

6A.3.1.2	Zoning	6A-8
6A.3.1.3	Public Policy	6A-11
6A.3.2	Hudson River	6A-14
6A.3.3	New York.....	6A-14
6A.3.3.1	Land Use	6A-14
6A.3.3.2	Zoning.....	6A-17
6A.3.3.3	Public Policy	6A-19
6A.4	Affected Environment: Future Conditions	6A-21
6A.4.1	New Jersey	6A-21
6A.4.1.1	Land Use	6A-21
6A.4.1.2	Zoning and Public Policy	6A-22
6A.4.2	Hudson River	6A-22
6A.4.3	New York.....	6A-22
6A.4.3.1	Land Use	6A-22
6A.4.3.2	Zoning.....	6A-25
6A.4.3.3	Public Policy	6A-25
6A.5	Impacts of No Action Alternative	6A-25
6A.6	Construction Impacts of the Preferred Alternative.....	6A-26
6A.6.1	Overview	6A-26
6A.6.2	New Jersey	6A-26
6A.6.2.1	Land Use	6A-26
6A.6.2.2	Zoning.....	6A-30
6A.6.2.3	Public Policy	6A-30
6A.6.3	Hudson River	6A-31
6A.6.4	New York.....	6A-31
6A.6.4.1	Land Use	6A-31
6A.6.4.2	Zoning.....	6A-33
6A.6.4.3	Public Policy	6A-33
6A.7	Permanent Impacts of the Preferred Alternative	6A-34
6A.7.1	Overview	6A-34
6A.7.2	New Jersey	6A-34
6A.7.2.1	Land Use	6A-34
6A.7.2.2	Zoning.....	6A-36
6A.7.2.3	Public Policy	6A-36
6A.7.3	Hudson River	6A-36
6A.7.4	New York.....	6A-36
6A.7.4.1	Land Use	6A-36
6A.7.4.2	Zoning.....	6A-38
6A.7.4.3	Public Policy	6A-38
6A.8	Measures to Avoid, Minimize, and Mitigate Impacts	6A-39



6A.8.1	General Construction Practices.....	6A-39
6A.8.2	New Jersey.....	6A-40
6A.8.3	New York.....	6A-42
Chapter 6B: Property Acquisition.....		6B-1
6B.1	Introduction.....	6B-1
6B.2	Regulatory Context.....	6B-1
6B.3	Property Acquisition Required.....	6B-2
6B.3.1	New Jersey.....	6B-2
6B.3.1.1	Subsurface Easements.....	6B-2
6B.3.1.2	Surface Acquisitions.....	6B-2
6B.3.2	New York.....	6B-5
6B.3.2.1	Subsurface Easements.....	6B-5
6B.3.2.2	Surface Acquisitions.....	6B-5
6B.4	Measures to Avoid, Minimize, and Mitigate Impacts.....	6B-6
Chapter 7: Socioeconomic Conditions.....		7-1
7.1	Introduction.....	7-1
7.2	Analysis Methodology.....	7-2
7.2.1	Regulatory Context.....	7-2
7.2.2	Analysis Techniques.....	7-2
7.2.3	Study Areas.....	7-3
7.3	Affected Environment: Existing Conditions.....	7-3
7.3.1	New Jersey.....	7-3
7.3.1.1	Overall Socioeconomic Conditions.....	7-3
7.3.1.2	Local Conditions in the Study Area.....	7-6
7.3.2	New York.....	7-8
7.3.2.1	Overall Socioeconomic Conditions.....	7-8
7.3.2.2	Local Conditions in the Study Area.....	7-10
7.4	Affected Environment: Future Conditions.....	7-10
7.5	Impacts of No Action Alternative.....	7-10
7.6	Construction Impacts of the Preferred Alternative.....	7-11
7.6.1	Overview.....	7-11
7.6.2	Economic and Fiscal Benefits of Construction Expenditures.....	7-12
7.6.2.1	New Jersey.....	7-14
7.6.2.2	New York.....	7-15
7.6.3	Construction Effects on Local Conditions in the Study Area.....	7-16
7.6.3.1	New Jersey.....	7-16
7.6.3.2	New York.....	7-19
7.7	Permanent Impacts of the Preferred Alternative.....	7-20
7.7.1	Overview.....	7-20
7.7.2	New Jersey.....	7-21
7.7.3	New York.....	7-21

7.8	Measures to Avoid, Minimize, and Mitigate Impacts	7-22
Chapter 8:	Open Space and Recreational Resources	8-1
8.1	Introduction	8-1
8.2	Analysis Methodology	8-2
8.2.1	Regulatory Context	8-2
8.2.2	Analysis Techniques	8-3
8.2.3	Study Areas	8-3
8.3	Affected Environment: Existing Conditions	8-4
8.3.1	New Jersey	8-4
8.3.1.1	Study Area West of the Palisades	8-4
8.3.1.2	Study Area on the Palisades	8-4
8.3.1.3	Study Area East of the Palisades	8-5
8.3.2	Hudson River	8-6
8.3.3	New York	8-7
8.3.3.1	Hudson River Park	8-7
8.3.3.2	High Line	8-9
8.3.3.3	Open Spaces at Hudson Yards	8-10
8.4	Affected Environment: Future Conditions	8-10
8.4.1	New Jersey	8-10
8.4.2	Hudson River	8-10
8.4.3	New York	8-10
8.5	Impacts of No Action Alternative	8-12
8.6	Construction Impacts of the Preferred Alternative	8-12
8.6.1	Overview	8-12
8.6.2	New Jersey	8-12
8.6.3	Hudson River	8-15
8.6.4	New York	8-16
8.6.4.1	Hudson River Park	8-16
8.6.4.2	High Line	8-20
8.6.4.3	Open Spaces at Hudson Yards	8-21
8.7	Permanent Impacts of the Preferred Alternative	8-22
8.7.1	Overview	8-22
8.7.2	New Jersey	8-22
8.7.2.1	Effects on Open Space	8-22
8.7.2.2	Green Acres Program Approvals	8-22
8.7.3	Hudson River	8-23
8.7.4	New York	8-23
8.7.4.1	Effects on Open Space	8-23
8.7.4.2	Shadows on Open Spaces	8-23
8.7.4.3	Approvals	8-25
8.8	Measures to Avoid, Minimize, and Mitigate Impacts	8-25



Chapter 9: Historic and Archaeological Resources	9-1
9.1 Introduction	9-1
9.2 Analysis Methodology	9-2
9.2.1 Regulatory Context	9-2
9.2.2 Analysis Methodology	9-3
9.2.2.1 Consultation	9-3
9.2.2.2 Definition of the Area of Potential Effects	9-6
9.2.2.3 Identification of Historic Properties in the APE	9-7
9.2.2.4 Evaluation of Potential Effects on Historic Properties	9-9
9.3 Affected Environment: Existing Conditions	9-9
9.3.1 New Jersey	9-9
9.3.1.1 Historic Architectural Resources	9-9
9.3.1.2 Archaeological Resources	9-12
9.3.2 Hudson River	9-15
9.3.2.1 Historic Architectural Resources	9-15
9.3.2.2 Archaeological Resources	9-15
9.3.3 New York	9-16
9.3.3.1 Historic Architectural Resources	9-16
9.3.3.2 Archaeological Resources	9-20
9.4 Affected Environment: Future Conditions	9-22
9.5 Impacts of No Action Alternative	9-23
9.6 Construction Impacts of the Preferred Alternative	9-23
9.6.1 New Jersey	9-24
9.6.1.1 Historic Architectural Resources	9-24
9.6.1.2 Archaeological Resources	9-26
9.6.2 Hudson River	9-29
9.6.2.1 Historic Architectural Resources	9-29
9.6.2.2 Archaeological Resources	9-30
9.6.3 New York	9-30
9.6.3.1 Historic Architectural Resources	9-30
9.6.3.2 Archaeological Resources	9-33
9.7 Permanent Impacts of the Preferred Alternative	9-36
9.7.1 New Jersey	9-36
9.7.1.1 Historic Architectural Resources	9-36
9.7.1.2 Archaeological Resources	9-37
9.7.2 Hudson River	9-37
9.7.3 New York	9-37
9.7.3.1 Historic Architectural Resources	9-37
9.7.3.2 Archaeological Resources	9-38
9.8 Measures to Avoid, Minimize, and Mitigate Impacts	9-38

9.8.1	Historic Architectural Resources	9-38
9.8.2	Archaeological Resources	9-40
9.8.2.1	New Jersey	9-40
9.8.2.2	New York	9-41
Chapter 10:	Visual and Aesthetic Resources	10-1
10.1	Introduction	10-1
10.2	Analysis Methodology	10-1
10.2.1	Regulatory Context	10-2
10.2.2	Analysis Techniques	10-2
10.2.3	Study Areas	10-3
10.3	Affected Environment: Existing Conditions	10-4
10.3.1	New Jersey	10-4
10.3.1.1	County Road to Tonnelle Avenue	10-4
10.3.1.2	Tonnelle Avenue Area	10-5
10.3.1.3	Weehawken and Hoboken	10-6
10.3.2	Hudson River	10-7
10.3.3	New York	10-7
10.3.3.1	Waterfront Area	10-7
10.3.3.2	Tenth Avenue Area	10-9
10.4	Affected Environment: Future Conditions	10-9
10.5	Impacts of No Action Alternative	10-10
10.6	Construction Impacts of the Preferred Alternative	10-10
10.6.1	Overview	10-10
10.6.2	New Jersey	10-11
10.6.2.1	County Road to Tonnelle Avenue	10-11
10.6.2.2	Tonnelle Avenue Area	10-11
10.6.2.3	Weehawken and Hoboken	10-11
10.6.3	Hudson River	10-12
10.6.4	New York	10-12
10.7	Permanent Impacts of the Preferred Alternative	10-13
10.7.1	Overview	10-13
10.7.2	New Jersey	10-14
10.7.2.1	County Road to Tonnelle Avenue	10-14
10.7.2.2	Tonnelle Avenue Area	10-14
10.7.2.3	Weehawken and Hoboken	10-15
10.7.3	Hudson River	10-16
10.7.4	New York	10-16
10.7.4.1	Waterfront Area	10-16
10.7.4.2	Tenth Avenue Area	10-18
10.8	Measures to Avoid, Minimize, and Mitigate Impacts	10-18
Chapter 11:	Natural Resources	11-1
11.1	Introduction	11-1
11.2	Analysis Methodology	11-2



11.2.1	Regulatory Context.....	11-2
11.2.1.1	Federal	11-2
11.2.1.2	New Jersey	11-4
11.2.1.3	New York.....	11-5
11.2.2	Analysis Techniques	11-6
11.2.3	Study Areas	11-7
11.3	Affected Environment: Existing Conditions	11-7
11.3.1	New Jersey.....	11-7
11.3.1.1	Floodplains.....	11-7
11.3.1.2	Wetlands	11-8
11.3.1.3	Groundwater	11-9
11.3.1.4	Surface and Navigable Waters	11-10
11.3.1.5	Terrestrial Resources.....	11-13
11.3.1.6	Threatened, Endangered, or Special Concern Species	11-16
11.3.2	Hudson River.....	11-20
11.3.2.1	Aquatic Resources.....	11-20
11.3.2.2	Essential Fish Habitat (EFH).....	11-29
11.3.2.3	Wildlife.....	11-30
11.3.2.4	Threatened, Endangered, or Special Concern Species	11-31
11.3.2.5	Significant Coastal Fish and Wildlife Habitat	11-33
11.3.3	New York.....	11-35
11.3.3.1	Floodplains.....	11-35
11.3.3.2	Wetlands	11-35
11.3.3.3	Groundwater	11-36
11.3.3.4	Terrestrial Resources.....	11-36
11.3.3.5	Threatened, Endangered, or Special Concern Species	11-38
11.4	Affected Environment: Future Conditions	11-38
11.4.1	Overview.....	11-38
11.4.2	New Jersey.....	11-39
11.4.3	Hudson River.....	11-39
11.4.4	New York	11-40
11.5	Impacts of No Action Alternative	11-41
11.6	Construction Impacts of the Preferred Alternative	11-41
11.6.1	Overview.....	11-41
11.6.2	New Jersey.....	11-41
11.6.2.1	Floodplains.....	11-41
11.6.2.2	Wetlands	11-41
11.6.2.3	Groundwater	11-42
11.6.2.4	Surface and Navigable Waters	11-44
11.6.2.5	Terrestrial Resources.....	11-46
11.6.2.6	Threatened, Endangered, or Special Concern Species	11-47
11.6.3	Hudson River.....	11-49
11.6.3.1	Aquatic Resources	11-49

11.6.3.2	Essential Fish Habitat	11-53
11.6.3.3	Wildlife	11-53
11.6.3.4	Threatened, Endangered or Special Concern Species	11-53
11.6.3.5	Significant Coastal Fish and Wildlife Habitat	11-55
11.6.4	New York.....	11-56
11.6.4.1	Floodplains	11-56
11.6.4.2	Wetlands.....	11-56
11.6.4.3	Groundwater	11-56
11.6.4.4	Surface and Navigable Waters	11-57
11.6.4.5	Terrestrial Resources	11-57
11.7	Permanent Impacts of the Preferred Alternative	11-58
11.7.1	Overview	11-58
11.7.2	New Jersey	11-58
11.7.2.1	Floodplains	11-59
11.7.2.2	Wetlands.....	11-59
11.7.2.3	Groundwater	11-61
11.7.2.4	Surface and Navigable Waters.....	11-61
11.7.2.5	Terrestrial Resources	11-62
11.7.2.6	Threatened, Endangered, or Special Concern Species	11-63
11.7.3	Hudson River	11-64
11.7.3.1	Aquatic Resources.....	11-64
11.7.3.2	Essential Fish Habitat.....	11-65
11.7.3.3	Wildlife	11-65
11.7.3.4	Threatened, Endangered, or Special Concern Species	11-65
11.7.3.5	Significant Coastal Fish and Wildlife Habitat	11-66
11.7.4	New York.....	11-67
11.7.4.1	Floodplains	11-67
11.7.4.2	Wetlands.....	11-68
11.7.4.3	Groundwater	11-68
11.7.4.4	Terrestrial Resources	11-68
11.8	Summary of Impacts and Associated Mitigation and Minimization Measures	11-69
11.9	Measures to Avoid, Minimize, and Mitigate Impacts	11-75
11.9.1	New Jersey	11-77
11.9.2	Hudson River	11-77
11.9.3	New York.....	11-77
11.10	References	11-77
Chapter 12A: Noise	12A-1	
12A.1	Introduction	12A-1
12A.2	Analysis Methodology.....	12A-2
12A.2.1	Noise Fundamentals and Definitions	12A-3
12A.2.1.1	“A”-Weighted Sound Level (dBA)	12A-3
12A.2.1.2	Effects of Distance on Noise	12A-4
12A.2.1.3	Noise Descriptors Used in Impact Assessment	12A-5



12A.2.2	Standards and Criteria	12A-5
12A.2.2.1	Operational Noise Impact Criteria	12A-5
12A.2.2.2	Construction Noise Impact Criteria	12A-6
12A.2.3	Methodology for Evaluating Noise Impacts	12A-8
12A.2.3.1	Construction Impacts	12A-8
12A.2.3.2	Operational Impacts	12A-8
12A.2.3.3	Selection of Receptor Locations	12A-9
12A.2.3.4	Methodology and Equipment Used for Noise Survey	12A-9
12A.3	Affected Environment: Existing Conditions	12A-10
12A.3.1	New Jersey	12A-10
12A.3.1.1	Noise Receptor Locations	12A-10
12A.3.1.2	Measured Noise Levels	12A-11
12A.3.2	Hudson River	12A-12
12A.3.3	New York	12A-13
12A.3.3.1	Noise Receptor Locations	12A-13
12A.3.3.2	Measured Noise Levels	12A-14
12A.4	Affected Environment: Future Conditions	12A-15
12A.5	Impacts of No Action Alternative	12A-15
12A.6	Construction Impacts of the Preferred Alternative	12A-15
12A.6.1	Overview	12A-15
12A.6.2	New Jersey	12A-16
12A.6.2.1	Surface Track Construction	12A-16
12A.6.2.2	Construction of New Tunnel and Related Elements at the Tonnelles Avenue Staging Area	12A-17
12A.6.2.3	Hoboken Staging Area	12A-20
12A.6.2.4	North River Tunnel Rehabilitation	12A-24
12A.6.3	New York	12A-26
12A.6.3.1	Trucking Activities	12A-26
12A.6.3.2	Noise at the Construction Sites	12A-26
12A.7	Permanent Impacts of the Preferred Alternative	12A-30
12A.7.1	Overview	12A-30
12A.7.2	New Jersey	12A-31
12A.7.2.1	Surface Alignment	12A-31
12A.7.2.2	Hoboken Fan Plant	12A-32
12A.7.2.3	Other Locations	12A-33
12A.7.3	New York	12A-34
12A.8	Conclusions	12A-35
12A.9	Measures to Avoid, Minimize, and Mitigate Impacts	12A-37
12A.9.1	General Construction Practices	12A-37
12A.9.2	Construction for Surface Alignments	12A-38
12A.9.3	Construction at Tonnelles Avenue Staging Area	12A-38
12A.9.4	Construction at Hoboken Staging Area	12A-40

12A.9.5	Construction in New York	12A-41
12A.9.6	Operation of the Preferred Alternative	12A-41
Chapter 12B: Vibration	12B-1
12B.1	Introduction	12B-1
12B.2	Analysis Methodology	12B-2
12B.2.1	Vibration Fundamentals and Definitions	12B-2
12B.2.1.1	Effect of Propagation Path.....	12B-3
12B.2.1.2	Human Response to Vibration Levels	12B-3
12B.2.2	Standards and Criteria	12B-4
12B.2.2.1	Operational Vibration and Ground-Borne Noise Standards and Criteria.....	12B-4
12B.2.2.2	Construction Vibration and Ground-Borne Noise Standards and Criteria.....	12B-6
12B.2.3	Methodology for Evaluating Vibration and Ground-Borne Noise	12B-7
12B.2.3.1	Construction Impacts	12B-7
12B.2.3.2	Operational Impacts.....	12B-8
12B.2.3.3	Selection of Receptor Locations	12B-8
12B.3	Affected Environment: Existing Conditions.....	12B-8
12B.3.1	New Jersey	12B-8
12B.3.2	Hudson River	12B-9
12B.3.3	New York.....	12B-9
12B.4	Affected Environment: Future Conditions.....	12B-9
12B.5	Impacts of No Action Alternative	12B-9
12B.6	Construction Impacts of the Preferred Alternative.....	12B-10
12B.6.1	Overview	12B-10
12B.6.2	New Jersey	12B-10
12B.6.2.1	Surface Alignment Construction	12B-10
12B.6.2.2	Construction of New Tunnel and Related Elements at the Tonelle Avenue Staging Area	12B-11
12B.6.2.3	Hoboken Staging Area	12B-11
12B.6.2.4	Tunnel Boring Machine Operation along the Tunnel Alignment	12B-12
12B.6.2.5	North River Tunnel Rehabilitation	12B-13
12B.6.3	New York.....	12B-13
12B.6.3.1	Manhattan Waterfront Area.....	12B-13
12B.6.3.2	Twelfth Avenue Shaft and Fan Plant	12B-14
12B.7	Permanent Impacts of the Preferred Alternative	12B-15
12B.7.1	Overview	12B-15
12B.7.2	New Jersey	12B-16
12B.7.3	New York.....	12B-17
12B.8	Conclusions	12B-18
12B.9	Measures to Avoid, Minimize, and Mitigate Impacts	12B-18
12B.9.1	Community Outreach	12B-18
12B.9.2	Blasting Controls	12B-18



12B.9.3	Pile Installation	12B-19
12B.9.4	Vibration Monitoring Program.....	12B-19
12B.9.5	Construction Protection Plans	12B-19
12B.9.6	Operation of the Preferred Alternative	12B-20
Chapter 13: Air Quality		13-1
13.1	Introduction	13-1
13.2	Analysis Methodology	13-2
13.2.1	Regulatory Context.....	13-2
13.2.1.1	National and State Air Quality Standards	13-2
13.2.1.2	NAAQS Attainment Status and State Implementation Plans.....	13-4
13.2.1.3	Pollutants for Analysis.....	13-5
13.2.1.4	Respirable Particulate Matter—PM ₁₀ and PM _{2.5}	13-7
13.2.1.5	Impact Criteria.....	13-7
13.2.1.6	Conformity With State Implementation Plans	13-8
13.2.1.7	Air Quality, Climate Change, and Ozone	13-10
13.2.2	Analysis Techniques	13-10
13.2.2.1	On-Site Construction Source Assessment.....	13-11
13.2.2.2	On-Road Construction Source Assessment	13-12
13.2.2.3	Combined Impact Assessment	13-14
13.2.2.4	Construction Mesoscale Analysis	13-14
13.2.3	Study Areas	13-14
13.3	Affected Environment: Existing Conditions.....	13-15
13.3.1	New Jersey.....	13-15
13.3.2	New York	13-15
13.4	Affected Environment: Future Conditions	13-16
13.5	Impacts of No Action Alternative	13-16
13.6	Construction Impacts of the Preferred Alternative	13-17
13.6.1	Overview.....	13-17
13.6.2	New Jersey.....	13-17
13.6.2.1	On-Site Construction Source Assessment.....	13-17
13.6.2.2	On-Road Construction Source Assessment	13-18
13.6.2.3	Combined Impact Assessment	13-19
13.6.2.4	Other Construction Periods.....	13-19
13.6.3	Hudson River.....	13-20
13.6.4	New York	13-21
13.6.4.1	On-Site Construction Source Assessment.....	13-21
13.6.4.2	On-Road Construction Source Assessment	13-22
13.6.4.3	Combined Impact Assessment	13-23
13.7	Permanent Impacts of the Preferred Alternative.....	13-25
13.8	Conformity with State Implementation Plan	13-27
13.9	Measures to Avoid, Minimize, or Mitigate Impacts	13-29

Chapter 14: Greenhouse Gas Emissions and Resilience	14-1
14.1 Introduction	14-1
14.2 Greenhouse Gas Emissions	14-2
14.2.1 Regulatory Context	14-2
14.2.2 Methodology for Projecting GHG Emissions	14-3
14.2.2.1 Introduction	14-3
14.2.2.2 Application of FTA Programmatic Assessment for GHG Emissions	14-4
14.2.2.3 Grid Power Emissions	14-5
14.2.2.4 Mobile Source Emissions	14-5
14.2.2.5 Construction Materials Emissions	14-6
14.2.2.6 Tree Removal	14-6
14.2.3 Affected Environment: Existing and Future Conditions	14-7
14.2.4 Impacts of No Action Alternative	14-7
14.2.5 Construction Impacts of the Preferred Alternative	14-8
14.2.5.1 GHG Emissions from Construction	14-8
14.2.5.2 Measures to Avoid, Minimize, and Mitigate GHG Emissions from Construction	14-8
14.2.6 Permanent Impacts of the Preferred Alternative	14-10
14.2.6.1 Operational GHG Emissions	14-10
14.2.6.2 Measures to Avoid, Minimize, and Mitigate GHG Emissions from Operations	14-10
14.3 Resilience to Climate Change	14-10
14.3.1 Regulatory Context	14-11
14.3.2 Methodology for Evaluating Resilience	14-11
14.3.3 Affected Environment: Existing and Future Conditions	14-12
14.3.3.1 Overview	14-12
14.3.3.2 New Jersey	14-14
14.3.3.3 Hudson River	14-15
14.3.3.4 New York	14-15
14.3.3.5 Other Associated Transportation-Related Resilience Projects	14-16
14.3.4 Impacts of No Action Alternative	14-16
14.3.5 Construction Impacts of the Preferred Alternative	14-17
14.3.5.1 Overview	14-17
14.3.5.2 New Jersey	14-18
14.3.5.3 Hudson River	14-18
14.3.5.4 New York	14-18
14.3.5.5 Measures to Avoid, Minimize, and Mitigate Effect of Climate Change During Construction	14-18
14.3.6 Permanent Impacts of the Preferred Alternative	14-19
14.3.6.1 Overview	14-19
14.3.6.2 New Jersey	14-22
14.3.6.3 Hudson River	14-23
14.3.6.4 New York	14-23
14.3.6.5 Measures to Avoid, Minimize, and Mitigate Impacts for Resilience of Operations	14-23



Chapter 15: Geology and Soils	15-1
15.1 Introduction	15-1
15.2 Analysis Methodology	15-2
15.2.1 Analysis Techniques	15-2
15.2.2 Study Area	15-2
15.3 Affected Environment: Existing Conditions	15-3
15.3.1 New Jersey	15-3
15.3.1.1 Bedrock Geology	15-3
15.3.1.2 Surficial Geology	15-4
15.3.2 Hudson River	15-5
15.3.2.1 Bedrock Geology	15-5
15.3.2.2 Surficial Geology	15-5
15.3.3 New York	15-6
15.3.3.1 Bedrock Geology	15-6
15.3.3.2 Surficial Geology	15-6
15.4 Affected Environment: Future Conditions	15-7
15.5 Impacts of No Action Alternative	15-7
15.6 Construction Impacts of the Preferred Alternative	15-7
15.6.1 Overview	15-7
15.6.2 New Jersey	15-8
15.6.3 Hudson River	15-10
15.6.4 New York	15-11
15.7 Permanent Impacts of the Preferred Alternative	15-12
15.8 Measures to Avoid, Minimize, and Mitigate Impacts	15-12
15.8.1 New Jersey	15-13
15.8.2 Hudson River	15-15
15.8.3 New York	15-15
Chapter 16: Contaminated Materials	16-1
16.1 Introduction	16-1
16.2 Analysis Methodology	16-2
16.2.1 Regulatory Context	16-2
16.2.2 Analysis Techniques	16-4
16.2.3 Study Area	16-5
16.3 Affected Environment: Existing Conditions	16-5
16.3.1 New Jersey	16-6
16.3.1.1 County Road to Tonnelle Avenue	16-6
16.3.1.2 Tonnelle Avenue Area	16-7
16.3.1.3 East of the Palisades	16-7
16.3.2 Hudson River	16-8
16.3.3 New York	16-8
16.4 Affected Environment: Future Conditions	16-10

16.5	Impacts of No Action Alternative	16-10
16.6	Construction Impacts of the Preferred Alternative.....	16-10
16.7	Permanent Impacts of the Preferred Alternative	16-11
16.8	Measures to Avoid, Minimize, and Mitigate Impacts	16-12
16.8.1	Project-Wide Measures.....	16-12
16.8.1.1	Tunnel Spoils and Other Excavated Materials	16-14
16.8.1.2	Dust Control.....	16-15
16.8.2	New Jersey	16-16
16.8.3	Hudson River	16-17
16.8.4	New York.....	16-17
Chapter 17: Utilities and Energy.....		17-1
17.1	Introduction	17-1
17.2	Analysis Methodology.....	17-2
17.2.1	Regulatory Context	17-2
17.2.2	Analysis Techniques	17-2
17.2.3	Study Area	17-2
17.3	Affected Environment: Existing Conditions.....	17-3
17.3.1	Power for Railroad Operations.....	17-3
17.3.2	New Jersey	17-4
17.3.3	Hudson River	17-5
17.3.4	New York.....	17-5
17.4	Affected Environment: Future Conditions.....	17-7
17.5	Impacts of No Action Alternative	17-7
17.6	Construction Impacts of the Preferred Alternative.....	17-8
17.6.1	Overview	17-8
17.6.2	New Jersey	17-9
17.6.3	Hudson River	17-11
17.6.4	New York.....	17-11
17.7	Permanent Impacts of the Preferred Alternative	17-13
17.7.1	Overview	17-13
17.7.2	New Jersey	17-13
17.7.3	Hudson River	17-14
17.7.4	New York.....	17-14
17.8	Measures to Avoid, Minimize, and Mitigate Impacts	17-14
17.8.1	Utilities.....	17-14
17.8.2	Energy.....	17-15
Chapter 18: Safety and Security.....		18-1
18.1	Introduction	18-1
18.2	Analysis Methodology.....	18-1



18.1.1	Regulatory Context.....	18-2
18.1.2	Analysis Techniques	18-3
18.1.3	Study Area.....	18-3
18.3	Affected Environment: Existing Conditions.....	18-3
18.4	Affected Environment: Future Conditions	18-4
18.5	Impacts of No Action Alternative.....	18-4
18.6	Construction Impacts of the Preferred Alternative	18-5
18.7	Permanent Impacts of the Preferred Alternative.....	18-6
18.8	Measures to Avoid, Minimize, and Mitigate Impacts.....	18-9
Chapter 19: Public Health and Electromagnetic Fields.....		19-1
19.1	Introduction	19-1
19.2	Public Health	19-2
19.2.1	Analysis Methodology	19-2
19.2.1.1	Regulatory Context	19-2
19.2.1.2	Analysis Techniques	19-2
19.2.1.3	Study Area	19-2
19.2.2	Affected Environment: Existing and Future Conditions.....	19-3
19.2.3	Impacts of No Action Alternative	19-3
19.2.4	Construction Impacts of the Preferred Alternative	19-3
19.2.4.1	Air Quality.....	19-4
19.2.4.2	Water Quality	19-4
19.2.4.3	Contaminated Materials	19-5
19.2.4.4	Noise	19-6
19.2.5	Permanent Impacts of the Preferred Alternative	19-13
19.3	Electromagnetic Fields (EMFs).....	19-13
19.3.1	Analysis Methodology	19-13
19.3.1.1	Regulatory Context	19-13
19.3.1.2	Analysis Techniques	19-14
19.3.1.3	Study Area	19-14
19.3.2	Affected Environment: Existing and Future Conditions.....	19-14
19.3.3	Impacts of No Action Alternative	19-14
19.3.4	Construction Impacts of the Preferred Alternative	19-14
19.3.5	Permanent Impacts of the Preferred Alternative	19-14
19.4	Measures to Avoid, Minimize, and Mitigate Impacts.....	19-15
Chapter 20: Indirect and Cumulative Effects.....		20-1
20.1	Introduction	20-1
20.2	Analysis Methodology	20-2
20.2.1	Regulatory Context.....	20-2
20.2.2	Analysis Techniques	20-3
20.2.3	Study Areas	20-3
20.3	Affected Environment: Existing and Future Conditions	20-3

20.4	Indirect and Cumulative Impacts of No Action Alternative	20-3
20.5	Indirect Impacts of the Preferred Alternative	20-4
20.5.1	Overview	20-4
20.5.2	Indirect Construction Impacts of the Preferred Alternative	20-4
20.5.3	Indirect Permanent Impacts of the Preferred Alternative	20-5
20.6	Cumulative Impacts of the Preferred Alternative	20-5
20.6.1	Overview	20-5
20.6.2	Rail System Improvements Near PSNY	20-6
20.6.3	Other Transportation System Improvements	20-8
20.6.4	Development and Infrastructure Projects	20-9
20.6.4.1	New Jersey	20-9
20.6.4.2	New York	20-10
20.7	Measures to Avoid, Minimize, and Mitigate Impacts	20-12
20.8	Project's Relationship to Future Proposed Capacity Enhancement Projects	20-13
20.8.1	Introduction	20-13
20.8.2	Plans to Increase Rail Service Capacity on the NEC Between Newark and PSNY	20-14
20.8.2.1	NEC Future	20-14
20.8.2.2	Gateway Program	20-14
20.8.3	Indirect and Cumulative Effects of Future Train Operations	20-16
Chapter 21: Coastal Zone Consistency		21-1
21.1	Introduction	21-1
21.2	Analysis Methodology	21-1
21.2.1	Regulatory Context	21-2
21.2.1.1	Federal	21-2
21.2.1.2	State – New Jersey	21-2
21.2.1.3	State – New York	21-2
21.2.1.4	City – New York	21-3
21.2.2	Analysis Techniques	21-3
21.2.3	Study Area	21-3
21.3	New Jersey Coastal Zone Consistency Assessment	21-4
21.3.1	New Jersey Coastal Zone Management (CZM) Rules	21-4
21.4	New York Coastal Zone Consistency Assessment	21-29
21.4.1	Overview	21-29
21.4.2	New York City Waterfront Revitalization Program Policies	21-29
Chapter 22: Environmental Justice		22-1
22.1	Introduction	22-1
22.2	Analysis Methodology	22-2
22.2.1	Regulatory Context	22-2
22.2.2	Analysis Techniques	22-3
22.2.2.1	Delineation of Study Area	22-3
22.2.2.2	Identification of Environmental Justice Populations	22-4



22.2.2.3	Identification of Potential Adverse Effects and Potential Disproportionate Impacts	22-5
22.2.2.4	Outreach to Environmental Justice Populations	22-5
22.3	Identification of Environmental Justice Populations.....	22-6
22.3.1	New Jersey.....	22-6
22.3.2	New York	22-7
22.4	Impacts of No Action Alternative.....	22-8
22.5	Benefits and Impacts of the Preferred Alternative and Measures to Avoid, Minimize, and Mitigate Impacts	22-9
22.5.1	New Jersey.....	22-10
22.5.1.1	Overall Project Impacts	22-10
22.5.1.2	Project Impacts On Environmental Justice Communities	22-22
22.5.2	New York	22-22
22.5.2.1	Overall Project Impacts	22-22
22.5.2.2	Project Impact On Environmental Justice Communities	22-31
22.6	Determination of Disproportionately High and Adverse Effects on Environmental Justice Populations	22-32
22.6.1	Overview.....	22-32
22.6.2	New Jersey.....	22-32
22.6.3	New York	22-32
22.7	Environmental Justice Conclusion	22-32
22.7.1	Further Mitigation Measures or Alternatives that Would Avoid or Reduce the Disproportionately High and Adverse Effect Are Not Practicable	22-33
22.7.2	A Substantial Need for the Action Exists and Lesser-Impact Alternatives Are Not Available	22-34
22.8	Public Participation.....	22-35
Chapter 23: Commitment of Resources	23-1	
23.1	Introduction	23-1
23.2	Irreversible and Irretrievable Commitment of Resources	23-1
23.3	Relationship Between Short-Term Uses of the Environment and the Maintenance and Enhancement of Long-Term Productivity	23-1
23.3.1	Short-Term Uses	23-2
23.3.2	Long-Term Productivity	23-2
23.3.3	Short-Term Uses Versus Long-Term Productivity	23-2
Chapter 24: Final Section 4(f) Evaluation	24-1	
24.1	Introduction	24-1
24.2	Regulatory Context	24-1
24.2.1	Section 4(f) Use.....	24-3
24.2.1.1	De Minimis Impacts.....	24-3
24.2.1.2	Exceptions from Section 4(f).....	24-4
24.2.1.3	Exemptions from Section 4(f).....	24-4

24.2.2	Avoidance Alternatives	24-4
24.2.3	Least Overall Harm Alternative	24-4
24.3	Need, Purpose, Goals, and Objectives	24-4
24.4	Alternatives	24-5
24.4.1	No Action Alternative	24-5
24.4.2	Preferred Alternative	24-6
24.5	Identification and Use of Section 4(f) Properties	24-6
24.5.1	Wildlife or Waterfowl Refuges	24-6
24.5.2	Parklands and Recreational Resources	24-6
24.5.2.1	Paterson Plank Road Park	24-9
24.5.2.2	19th Street Basketball Courts	24-10
24.5.2.3	1600 Park	24-10
24.5.2.4	Harborside/Hoboken Cove Park	24-12
24.5.2.5	Hudson River Waterfront Walkway	24-14
24.5.2.6	The High Line	24-15
24.5.2.7	Hudson River Park	24-18
24.5.3	Historic Resources	24-18
24.5.3.1	Archaeological Resources	24-18
24.5.3.2	Historic Architectural Resources	24-19
24.6	Hudson River Bulkhead	24-24
24.6.1	Description of the Section 4(f) Property	24-24
24.6.2	Use of the Section 4(f) Property	24-24
24.6.3	Alternatives to Avoid the Use of the Section 4(f) Property	24-25
24.6.3.1	No Action Alternative	24-28
24.6.3.2	Deep Tunnel Alternative	24-28
24.6.3.3	Bridge Alternative	24-29
24.6.3.4	Northern Alignment Alternative	24-29
24.6.4	Least Overall Harm Alternative	24-30
24.6.5	Measures to Minimize Harm	24-30
24.7	Hudson River Park	24-32
24.7.1	Description of the Section 4(f) Property	24-32
24.7.1.1	Overview	24-32
24.7.1.2	Park Area Near the Project Alignment	24-33
24.7.2	Impacts to and Use of the Section 4(f) Property	24-33
24.7.2.1	Temporary Construction Activities in Hudson River Park	24-34
24.7.2.2	Temporary Construction Activities Near Hudson River Park	24-36
24.7.2.3	Permanent Tunnel Alignment Beneath Hudson River Park	24-38
24.7.2.4	Permanent Project Structure Near Hudson River Park	24-38
24.7.2.5	Conclusions	24-39
24.7.3	Alternatives to Avoid the Use of the Section 4(f) Property	24-39
24.7.4	Least Overall Harm Alternative	24-40
24.7.5	Measures to Minimize Harm	24-40
24.8	Coordination	24-40



24.8.1	Coordination with Officials with Jurisdiction over the Section 4(f) Properties	24-40
24.8.2	Public Involvement	24-41
Chapter 25: Process, Agency Coordination, and Public Involvement.....		25-1
25.1	Introduction	25-1
25.2	Regulatory Process.....	25-2
25.2.1	National Environmental Policy Act (NEPA)	25-2
25.2.2	Section 106 Consultation	25-4
25.2.3	Section 4(f) Consultation	25-4
25.2.4	Environmental Justice Outreach	25-4
25.2.5	Other Permits and Approvals	25-5
25.3	Coordination	25-5
25.3.1	Lead, Cooperating, and Participating Agencies	25-5
25.3.2	Section 106 Consultation	25-10
25.3.3	Environmental Justice Outreach	25-12
25.4	Public Involvement	25-12
25.4.1	Public Scoping Meetings	25-15
25.4.2	Public Information Open Houses.....	25-15
25.4.3	Targeted Outreach	25-16
25.4.4	Public Review and Comment on DEIS	25-16
25.5	Project Contacts	25-18
Chapter 26: List of Preparers		26-1
26.1	Introduction	26-1
26.2	Federal Railroad Administration (Lead Federal Agency).....	26-1
26.3	Consultant, Booz Allen Hamilton (Program Consultant for FRA)	26-1
26.4	NJ TRANSIT (Joint Lead Agency)	26-2
26.5	Port Authority of New York and New Jersey (Joint Lead Agency)	26-2
26.6	NEPA Consultant, AKRF, Inc. (Overall Preparation of the FEIS).....	26-2
26.6.1	Subconsultant, Dewberry	26-3
26.6.2	Subconsultant, Fitzgerald & Halliday, Inc.....	26-3
26.6.3	Subconsultant, RGA, Inc.	26-3
26.6.4	Subconsultant, Simco Engineering, P.C.	26-3
Chapter 27: Distribution of EIS		27-1
27.1	Introduction	27-1
27.2	DEIS Distribution	27-1
27.2.1	DEIS Distribution List	27-1
27.2.1.1	Project Partners	27-1
27.2.1.2	Federal Agencies	27-1
27.2.1.3	State Agencies and Entities	27-1
27.2.1.4	Local Agencies	27-2

27.2.1.5	Stakeholders and General Public	27-2
27.2.2	DEIS Document Availability Locations	27-2
27.3	FEIS Distribution	27-3
Chapter 28:	Comments and Responses	28-1
28.1	Introduction	28-1
28.1.1	Contents of this Chapter	28-1
28.1.2	Roles and Responsibilities	28-2
28.1.2.1	Responsible Parties	28-2
28.1.2.2	Project Sponsor and Joint Lead Agency	28-4
28.2	Comment Period	28-5
28.2.1	DEIS Availability	28-5
28.2.2	Public Hearings	28-7
28.2.3	Public Comments	28-8
28.3	List of Commenters	28-8
28.3.1	Elected Officials or their Representatives	28-8
28.3.1.1	Federal	28-8
28.3.1.2	State	28-9
28.3.1.3	County and Local	28-9
28.3.2	Agencies and Governmental Organizations	28-10
28.3.2.1	Federal	28-10
28.3.2.2	State: New Jersey	28-10
28.3.2.3	State: New York	28-10
28.3.2.4	State: Other	28-11
28.3.2.5	County and Local: New Jersey	28-11
28.3.2.6	County and Local: New York	28-11
28.3.3	Organizations and Businesses	28-11
28.3.4	Individuals	28-14
28.4	Response to Comments	28-18
28.4.1	General (Comments 1-11)	28-18
28.4.1.1	General Support for the Hudson Tunnel Project and/or the Gateway Program	28-19
28.4.1.2	General Opposition	28-22
28.4.2	Process and Public Outreach (Comments 12-22)	28-24
28.4.3	Purpose and Need (Comments 23-25)	28-30
28.4.4	Project Cost and Funding (Comments 26-29)	28-33
28.4.5	Alternatives to the Proposed Project (Comments 30-53)	28-34
28.4.5.1	Alternative Evaluation: General	28-34
28.4.5.2	Tunnel Alignment Options	28-35
28.4.5.3	Capacity Enhancements	28-44
28.4.5.4	Enhancements to Service in the Tunnel	28-57
28.4.5.5	Enhancements: New Station in New Jersey	28-63
28.4.6	Preferred Alternative: Project Definition (Comments 54-68)	28-65
28.4.6.1	New Jersey	28-69



28.4.6.2	New York.....	28-74
28.4.7	Construction Methods (Comments 69-88)	28-76
28.4.7.1	General	28-76
28.4.7.2	Weehawken and Hoboken.....	28-76
28.4.7.3	New York.....	28-92
28.4.8	Analysis Framework (Comment 89).....	28-95
28.4.9	Traffic and Pedestrians (Comments 90-102)	28-95
28.4.9.1	New Jersey	28-95
28.4.9.2	New York.....	28-104
28.4.10	Transportation Services (Comments 103-111)	28-106
28.4.10.1	New Jersey	28-106
28.4.10.2	Hudson River	28-108
28.4.10.3	New York.....	28-110
28.4.11	Land Use, Zoning, and Public Policy (Comments 112-129)	28-111
28.4.11.1	New Jersey	28-111
28.4.11.2	New York.....	28-118
28.4.12	Socioeconomic Conditions (Comments 130-138).....	28-130
28.4.13	Open Space and Recreational Resources (Comments 139-154).....	28-136
28.4.13.1	New Jersey	28-136
28.4.13.2	New York.....	28-139
28.4.14	Historic Resources (Comments 155-167)	28-149
28.4.14.1	New Jersey	28-149
28.4.14.2	New York.....	28-151
28.4.15	Visual and Aesthetic Resources (Comments 168-173)	28-155
28.4.15.1	New Jersey	28-155
28.4.15.2	New York.....	28-157
28.4.16	Natural Resources (Comments 174-183)	28-159
28.4.16.1	New Jersey	28-162
28.4.16.2	Hudson River	28-163
28.4.17	Noise (Comments 184-192)	28-165
28.4.17.1	New Jersey	28-165
28.4.17.2	New York.....	28-170
28.4.18	Vibration (Comments 193-195)	28-175
28.4.19	Air Quality (Comments 196-204).....	28-178
28.4.19.1	New Jersey	28-181
28.4.19.2	New York.....	28-184
28.4.20	Greenhouse Gas Emissions and Resilience (Comments 205-214).....	28-186
28.4.20.1	New Jersey	28-190
28.4.21	Geology and Soils (Comments 215-221)	28-191
28.4.21.1	New Jersey	28-191
28.4.21.2	Hudson River	28-194
28.4.22	Contaminated Materials (Comments 222-224)	28-195
28.4.22.1	New Jersey	28-195

28.4.22.2	New York	28-199
28.4.23	Utilities and Energy (Comment 225)	28-199
28.4.24	Safety and Security (Comments 226-227).....	28-200
28.4.25	Indirect and Cumulative Effects (Comments 228-229).....	28-201
28.4.26	Public Health (Comment 230).....	28-202
28.4.27	Environmental Justice (Comments 231-233).....	28-202
28.4.28	Draft Section 4(f) Evaluation (Comments 234-235).....	28-206
Glossary		G-1
Programmatic Agreement (also part of Appendix 9).....		PA-1

List of Appendices

Appendix 1 Purpose and Need

1-1 Project Sponsor Letter

Appendix 2 Project Alternatives and Description of the Preferred Alternative

2-1 Alternatives Development Report

Appendix 3 Construction Methods and Activities

3-1 Options for Spoils Removal and Materials Deliveries at the Hoboken Staging Area

Appendix 4 Analysis Framework

4-1 CEQR Technical Area Guide

Appendix 5 Transportation

5-1 Traffic and Pedestrian Volumes

5-2 Intersection Level of Service Summary Tables

Appendix 6 Land Use, Zoning, Public Policy, and Property Acquisition

6-1 Potential Property Acquisition

Appendix 8 Open Space and Recreational Resources

8-1 Detailed Shadows Analysis

Appendix 9 Historic and Archaeological Resources

9-1 Programmatic Agreement

9-2 Historic and Archaeological Resources: Agency Correspondence

9-3 Area of Potential Effects Memorandum

Appendix 11 Natural Resources

11-1 Natural Resources: Agency Correspondence

11-2 Wetland Delineation Report

11-3 Essential Fish Habitat

11-4 Conceptual Compensatory Mitigation Plan

11-5 Information in Support of Section 404(b)(1) Analysis

Appendix 12 Noise and Vibration

12-1 Construction Assumptions Used in Noise Analysis

12-2 ARC FEIS Chapter 5.2 Construction-Related Impact to Land Use, Zoning, and Public Policy

12-3 ARC FEIS Appendix 5.7 Noise and Vibration

12-4 TBM Vibration Table (Excerpt from ARC FEIS Chapter 5.7)

Appendix 13 Air Quality

13-1 Construction Assumptions Used in Air Quality Analysis

13-2 Air Quality Conformity Exemption



Appendix 15	Geology and Soils
15-1	ARC FEIS Chapter 4.11 Soils and Geology
15-2	ARC FEIS Appendix 4.11 Soils and Geology
Appendix 19	Public Health and Electromagnetic Fields
19-1	ARC FEIS Chapter 4.16 Electric and Magnetic Fields
Appendix 21	Coastal Zone Consistency
21-1	Coastal Zone Consistency: Agency Correspondence
21-2	Coastal Assessment Forms Submitted for Concurrence in 2017
Appendix 24	Final Section 4(f) Evaluation
24-1	Section 4(f) Correspondence
Appendix 25	Process, Agency Coordination, and Public Involvement
25-1	Hudson Tunnel Project Public/Agency Coordination Plan
Appendix 28	Comments and Responses
28-1	Final Record of Comments

List of Tables

S-1	Summary of Effects of the Preferred Alternative and Measures to Avoid, Minimize, or Mitigate Impacts	S-17
S-2	Major Permits and Approvals Required for the Hudson Tunnel Project	S-32
S-3	Lead Agencies and Invited Cooperating and Participating Agencies	S-34
S-4	Project DEIS Viewing Locations	S-36
2-1	Screening Evaluation of Preliminary Alternatives	2-7
3-1	Track Support for Surface Alignment.....	3-11
4-1	New York Development Projects Described in the DEIS that are Now Complete	4-10
5A-1	Traffic Analysis Locations, Tonnelle Avenue Staging Area, New Jersey	5A-9
5A-2	Safety Assessment Study Locations, Tonnelle Avenue Staging Area, New Jersey	5A-10
5A-3	Traffic Analysis Locations, Hoboken Staging Area, New Jersey	5A-10
5A-4	Safety Assessment Study Locations, Hoboken Staging Area, New Jersey	5A-11
5A-5	Traffic Analysis Locations, New York.....	5A-12
5A-6	Pedestrian Analysis Locations, New York	5A-13
5A-7	Safety Assessment Study Locations, New York.....	5A-14
5A-8	Summary of 2016 Existing Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey, Commuter Peak Hours.....	5A-16
5A-9	Summary of 2016 Existing Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey, New Tunnel Construction Peak Hours	5A-17
5A-10	Summary of 2016 Existing Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey, North River Tunnel Rehabilitation Construction Peak Hours	5A-18
5A-11	Tonnelle Avenue Staging Area Crash Summary, 2017-2019.....	5A-19
5A-12	Summary of 2016 Existing Traffic Analysis Results, Hoboken Staging Area, New Jersey, Commuter Peak Hours	5A-20
5A-13	Summary of 2016 Existing Traffic Analysis Results, Hoboken Staging Area, New Jersey, Construction Peak Hours	5A-20
5A-14	Summary of 2016 Existing Traffic Analysis Results, Secondary Study Area, New Jersey, Construction Peak Hours	5A-21
5A-15	Hoboken Staging Area Crash Summary, 2017-2019	5A-22
5A-16	Summary of 2016 Existing Traffic Analysis Results, New York Study Area, Commuter Peak Hours	5A-23
5A-17	Summary of 2016 Existing Traffic Analysis Results, New York Study Area, Construction Peak Hours	5A-24
5A-18	Summary of 2016 Existing Pedestrian Analysis Results, New York Study Area	5A-25
5A-19	New York Study Area Crash Summary, 2014-2016	5A-26
5A-20	Summary of 2024 Future No Action Condition Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey, Commuter Peak Hours	5A-29



5A-21	Summary of 2024 No Action Condition Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey, Construction Peak Hours	5A-30
5A-22	Summary of 2032 No Action Condition Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey, Commuter Peak Hours.....	5A-31
5A-23	Summary of 2032 No Action Alternative Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey, Construction Peak Hours	5A-32
5A-24	Summary of 2025 No Action Condition Traffic Analysis Results, Hoboken Staging Area, New Jersey, Commuter Peak Hours.....	5A-33
5A-25	Summary of 2025 No Action Condition Traffic Analysis Results, Hoboken Staging Area, New Jersey, Construction Peak Hours	5A-34
5A-26	Summary of 2025 No Action Condition Traffic Analysis Results, Hoboken Secondary Study Area, New Jersey, Construction Peak Hours.....	5A-35
5A-27	Western Rail Yard Project Construction Mitigation Incorporated into the Analysis ..	5A-37
5A-28	Summary of 2024 No Action Condition Traffic Analysis Results, New York Study Area, Commuter Peak Hours	5A-38
5A-29	Summary of 2024 No Action Condition Traffic Analysis Results, New York Study Area, Construction Peak Hours	5A-39
5A-30	Summary of 2024 No Action Alternative Pedestrian Conditions, New York Study Area	5A-40
5A-31	Summary of 2024 Preferred Alternative Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey: New Tunnel Construction, Commuter Peak Hours	5A-46
5A-32	Summary of 2024 Preferred Alternative Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey: New Tunnel Construction, Construction Peak Hours	5A-47
5A-33	Summary of 2024 Adverse Traffic Impacts, Tonnelle Avenue Staging Area, New Jersey: New Tunnel Construction	5A-48
5A-34	Summary of 2032 Preferred Alternative Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey: North River Tunnel Rehabilitation, Commuter Peak Hours.....	5A-49
5A-35	Summary of 2032 Preferred Alternative Traffic Analysis Results, Tonnelle Avenue Staging Area, New Jersey: North River Tunnel Rehabilitation, Construction Peak Hours	5A-50
5A-36	Summary of 2032 Adverse Traffic Impacts, Tonnelle Avenue Staging Area, New Jersey: North River Tunnel Rehabilitation	5A-51
5A-37	Identified Mitigation Measures During Construction of the Preferred Alternative, Tonnelle Avenue Staging Area, New Jersey, Not Including New Intersection at Site Driveway	5A-53
5A-38	Identified Mitigation Measures During Construction of the Preferred Alternative, with Signalized 1801 Tonnel Avenue, Tonnelle Avenue Staging Area, New Jersey.....	5A-56
5A-39	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 1: Hoboken Staging Area, New Jersey Commuter Peak Hours	5A-58
5A-40	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 1: Hoboken Staging Area, New Jersey Construction Peak Hours (Workers Parking at the Staging Area)	5A-59

5A-41	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 1: Hoboken Staging Area, New Jersey, Construction Peak Hours (Workers Parking Off-Site).....	5A-60
5A-42	Summary of 2025 Adverse Traffic Impacts, Hoboken Staging Area, New Jersey, Haul Route Option 1.....	5A-61
5A-43	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 2: Hoboken Staging Area, New Jersey Commuter Peak Hours	5A-62
5A-44	Summary of 2025 Preferred Alternative Traffic Analysis Results Haul Option 2: Hoboken Staging Area, New Jersey Construction Peak Hours (Workers Parking at the Staging Areas).....	5A-63
5A-45	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 2: Hoboken Staging Area, New Jersey, Construction Peak Hours (Workers Parking Off-Site).....	5A-64
5A-46	Summary of 2025 Adverse Traffic Impacts, Hoboken Staging Area, New Jersey, Haul Route Option 2	5A-64
5A-47	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 3: Hoboken Staging Area, New Jersey Commuter Peak Hours	5A-65
5A-48	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 3: Hoboken Staging Area, New Jersey Construction Peak Hours (Workers Parking at the Staging Area).....	5A-66
5A-49	Summary of 2025 Preferred Alternative Traffic Analysis Results, Haul Route Option 3: Hoboken Staging Area, New Jersey Commuter Peak Hours (Workers Parking Off-Site).....	5A-67
5A-50	Summary of 2025 Adverse Traffic Impacts, Hoboken Staging Area, New Jersey, Haul Route Option 3.....	5A-68
5A-51	Identified Mitigation Measures During Construction of the Preferred Alternative, Hoboken Staging Area, New Jersey.....	5A-69
5A-52	Identified Mitigation Measures During Construction of the Preferred Alternative with Off-site Worker Parking, Hoboken Staging Area, New Jersey.....	5A-70
5A-53	Summary of 2024 Preferred Alternative Traffic Analysis Results, New York Study Area, Commuter Peak Hours.....	5A-75
5A-54	Summary of 2024 Preferred Alternative Traffic Analysis Results, New York Study Area, Construction Peak Hours	5A-76
5A-55	Summary of 2024 Preferred Alternative Traffic Analysis Results, New York Study Area.....	5A-76
5A-56	Identified Mitigation Measures During Construction of the Preferred Alternative, New York Study Area.....	5A-78
5A-57	Summary of 2024 Preferred Alternative Pedestrian Analysis Results, New York Study Area.....	5A-81
5A-58	Tonnel Avenue Staging Area, New Tunnel Construction (2024), Traffic Mitigation Overview—Mitigation Not Including New Signal	5A-84
5A-59	Tonnel Avenue Staging Area, New Tunnel Construction (2024), Traffic Mitigation Overview—Mitigation Including New Traffic Signal at Site Driveway.....	5A-85



5A-60	Tonnelle Avenue Staging Area, Rehabilitation of the North River Tunnel (2032), Traffic Mitigation Overview, Mitigation Not Including New Signal	5A-86
5A-61	Tonnelle Avenue Staging Area, Rehabilitation of the North River Tunnel (2032), Traffic Mitigation Overview, Mitigation Including New Traffic Signal at Site Driveway.....	5A-87
5A-62	Hoboken Staging Area, Traffic Mitigation Overview, Analysis Year 2025 (New Tunnel Construction): Haul Route Option 1	5A-89
5A-63	Hoboken Staging Area, Traffic Mitigation Overview, Analysis Year 2025 (New Tunnel Construction): Haul Route Option 2	5A-90
5A-64	Hoboken Staging Area, Traffic Mitigation Overview, Analysis Year 2025 (New Tunnel Construction): Haul Route Option 3	5A-91
5A-65	Hoboken Staging Area, Traffic Mitigation Overview, Analysis Year 2025 (New Tunnel Construction): Haul Route Option 1 and Off-Site Worker Parking	5A-92
5A-66	Hoboken Staging Area, Traffic Mitigation Overview, Analysis Year 2025 (New Tunnel Construction): Haul Route Option 2 and Off-Site Worker Parking	5A-93
5A-67	Hoboken Staging Area, Traffic Mitigation Overview, Analysis Year 2025 (New Tunnel Construction): Haul Route Option 3 and Off-Site Worker Parking	5A-94
5A-68	New York Study Area, Traffic Mitigation Overview, Analysis Year 2024	5A-96
5A-69	New York Study Area, Pedestrian Mitigation Overview	5A-98
5B-1	Daily Weekday Ferry Trips in the Hudson River near the Project Site	5B-9
6A-1	Properties and Land Uses on the Project Site, County Road to Tonnelle Avenue.....	6A-5
6A-2	Existing Zoning in the New Jersey Study Area	6A-9
6A-3	Existing Zoning Districts in the New York Study Area.....	6A-17
6A-4	Special Zoning Districts in the Study Area	6A-18
6A-5	Potential Future Projects in New York Study Area.....	6A-23
6B-1	Surface Property Acquisitions for the Preferred Alternative, New Jersey	6B-4
7-1	2015-2019 Total Population, New Jersey Study Area	7-4
7-2	2015-2019 Household Income Characteristics	7-5
7-3	Estimated Employees and Businesses in New Jersey Study Area and Hudson County.....	7-6
7-4	2015-2019 Total Population, New York Study Area.....	7-8
7-5	2015-2019 Household Income Characteristics	7-8
7-6	Estimated Employees and Businesses in New York Study Area and Manhattan	7-9
7-7	Economic and Fiscal Benefits Associated with Construction of the Preferred Alternative	7-14
8-1	Parks and Recreational Facilities in New Jersey Study Area	8-5
8-2	Parks and Recreational Facilities in New York Study Area.....	8-7
9-1	Historic Architectural Resources in the APE – New Jersey	9-10
9-2	Known Historic Architectural Resources in the APE – New York	9-17
9-3	Historic Architectural Resources in the APE and Effects Assessment – New Jersey.....	9-24

9-4	Areas of Archaeological Sensitivity in the APE for Direct Effects and Effects Assessment – New Jersey.....	9-27
9-5	Historic Architectural Resources in the APE and Effects Assessment – New York	9-30
9-6	Areas of Archaeological Sensitivity in the APE for Direct Effects and Effects Assessment – New York.....	9-34
11-1	NJDEP Water Quality Standards and Data for Penhorn Creek Sampling Station PHC6	11-12
11-2	Migratory Birds of Concern Listed in USFWS IPaC Resource List	11-17
11-3	NYSDEC and NJDEP Surface Water Quality Standards	11-22
11-4	NYCDEP Water Quality Data for Lower Hudson River Sampling Stations N3B, N4, and N5 (2000-2019, All Months)	11-24
11-5	NJHDG Water Quality Data for Sampling Stations 32 and 33 (2003-2019, All Months).....	11-25
11-6	Finfish Species with the Potential to Occur in the Lower Hudson River.....	11-28
11-7	Essential Fish Habitat Designated Species by Designated Life Stage in the Vicinity of the Project Site	11-30
11-8	New York State Breeding Bird Atlas 2000-2005 for Block 5751D	11-37
11-9	Summary of Temporary Impacts to Wetlands and Associated Open Waters	11-42
11-10	Summary of Permanent Impacts to Wetlands and Associated Open Waters	11-60
11-11	Summary of Potential Impacts to Natural Resources and Proposed Mitigation and Impact Minimization Measures	11-70
12A-1	Common Noise Levels	12A-4
12A-2	FTA’s Land Use Category and Metrics for Transit Noise Impact Criteria	12A-6
12A-3	FTA Detailed Noise Analysis Construction Noise Impact Criteria (in dBA)	12A-7
12A-4	Noise Receptor Locations in New Jersey	12A-11
12A-5	Existing Noise Levels in New Jersey (in dBA)	12A-13
12A-6	Noise Receptor Locations in New York	12A-14
12A-7	Existing Noise Levels in New York (in dBA)	12A-15
12A-8	Worst-Case Construction Noise Levels Near Surface Alignment (in dBA).....	12A-17
12A-9	Worst-Case Construction Noise Levels Near Tonnelle Avenue Staging Area During New Tunnel Construction (in dBA).....	12A-19
12A-10	Worst-Case Construction Noise Levels near Hoboken Staging Area (in dBA)	12A-23
12A-11	Worst-Case Construction Noise Levels During North River Tunnel Rehabilitation (in dBA)	12A-25
12A-12	Worst-Case Construction Noise Levels near Manhattan Construction Sites (in dBA)	12A-27
12A-13	New Jersey Preferred Alternative Noise Levels (in dBA)	12A-33
12A-14	New York Preferred Alternative Noise Levels (in dBA).....	12A-34
12A-15	Summary of Construction Noise Impacts Based on FTA Impact Criteria	12A-37
12B-1	Typical Levels of Ground-Borne Vibration	12B-4
12B-2	Ground-Borne Vibration and Ground-Borne Noise Impact Criteria for General Assessment.....	12B-5



12B-3	Ground-Borne Vibration and Ground-Borne Noise Impact Criteria for Special Buildings	12B-6
12B-4	Vibration Source Levels for Construction Equipment.....	12B-7
12B-5	Construction Vibration Damage Criteria	12B-7
12B-6	Vibration Receptor Locations in New Jersey	12B-8
12B-7	Vibration Receptor Locations in New York.....	12B-9
12B-8	New Jersey Operational Vibration and Ground-Borne Noise Analysis Results	12B-16
12B-9	New York Operational Vibration and Ground-Borne Noise Analysis Results	12B-17
13-1	National Ambient Air Quality Standards (NAAQS).....	13-3
13-2	NAAQS Attainment Status in the Project Area.....	13-5
13-3	Analysis Periods for Dispersion Modeling	13-13
13-4	Representative Monitored Ambient Air Quality Data - New Jersey	13-15
13-5	Representative Monitored Ambient Air Quality Data - New York.....	13-15
13-6	Pollutant Concentrations from On-Site Construction Sources ($\mu\text{g}/\text{m}^3$), Tonelle Avenue Staging Area.....	13-18
13-7	Pollutant Concentrations from On-Site Construction Sources ($\mu\text{g}/\text{m}^3$), Hoboken Staging Area	13-18
13-8	Pollutant Concentrations from On-Road Construction Sources ($\mu\text{g}/\text{m}^3$), Intersection of 19th Street and Park Avenue, Weehawken.....	13-19
13-9	Maximum Combined Concentrations from On-Site and On-Road Construction Sources ($\mu\text{g}/\text{m}^3$), Tonelle Avenue Staging Area	13-20
13-10	Maximum Combined Concentrations from On-Site and On-Road Construction Sources ($\mu\text{g}/\text{m}^3$), Hoboken Staging Area.....	13-20
13-11	Pollutant Concentrations from On-Site Construction Sources ($\mu\text{g}/\text{m}^3$), Twelfth Avenue Staging Area.....	13-22
13-12	Pollutant Concentrations from On-Road Construction Sources ($\mu\text{g}/\text{m}^3$), Intersection of West 33rd Street and Eleventh Avenue	13-23
13-13	Maximum Combined Concentrations from On-Site and On-Road Construction Sources ($\mu\text{g}/\text{m}^3$), Twelfth Avenue Staging Area	13-24
13-14	Emissions from Construction Activities (ton/yr).....	13-28
13-15	Emissions from Construction Activities with SEM Mining (ton/yr).....	13-29
14-1	Global Warming Potential (GWP) for Major GHGS.....	14-3
14-2	GHG Emissions from Construction (metric tons CO_2e)	14-8
14-3	Projected Precipitation Increases, High Scenario	14-14
14-4	Projected Potential 1-Percent Annual Probability Flood Elevations, New Jersey Sites (feet NAVD88)	14-15
14-5	Projected Potential 1-Percent Annual Probability Flood Elevations, New York Sites (feet NAVD88)	14-16
14-6	DFE for the Preferred Alternative (feet NAVD88)	14-19
17-1	Sources of As-Built Utility Information	17-3
17-2	Existing Utilities Serving the Project Area, New Jersey	17-5

17-3	Existing Utilities Serving the Project Area, New York	17-6
22-1	Environmental Justice Study Area Block Groups	22-4
22-2	Study Area Minority and Low-Income Characteristics	22-7
22-3	Summary of Effects of the Preferred Alternative in New Jersey and Measures to Avoid, Minimize, or Mitigate Impacts	22-12
22-4	Summary of Effects of the Preferred Alternative in New York and Measures to Avoid, Minimize, or Mitigate Impacts	22-24
22-5	Public Involvement Meetings	22-36
24-1	Section 4(f) Properties—Parklands and Recreational Resources	24-8
24-2	Section 4(f) Properties—Historic Resources	24-20
24-3	Section 4(f) Screening Evaluation of Alternatives Developed During NEPA Process	24-27
25-1	Major Permits and Approvals Required for the Hudson Tunnel Project	25-6
25-2	Lead Agencies and Invited Cooperating and Participating Agencies	25-8
25-3	Agency Meetings Held to Date	25-10
25-4	Public Involvement Meetings	25-14
25-5	Media Outlets for Meeting Advertisements	25-15
25-6	DEIS Viewing Locations	25-17
27-1	FEIS Viewing Locations	27-3
28-1	DEIS Viewing Locations	28-6
28-2	Media Outlets for Public Hearing Notices	28-7

List of Figures

		<i>Following page</i>
S-1	Project Location	S-1
S-2	Tunnel Alignment Options.....	S-6
S-3	Preferred Alternative	S-9
F-1	Design Refinements in the FEIS: New Jersey	F-4
F-2	Design Refinements in the FEIS: New York	F-4
1-1	Project Location	1-4
1-2	Amtrak Northeast Corridor and Connecting Rail Network	1-5
1-3	NJ TRANSIT Commuter Network	1-5
2-1	PSNY Rail Complex.....	2-4
2-2	Tunnel Alignment Options.....	2-10
2-3	Preferred Alternative	2-18
2-4	New Jersey Surface Alignment.....	2-19
2-5	New Tunnel Alignment (Plan and Profile): New Jersey	2-21
2-6	New Tunnel Alignment (Plan and Profile): Hudson River and New York	2-21
2-7	New Tunnel Alignment (Plan and Profile): New York	2-22
2-8	Typical Tunnel Cross Section: New Tunnel	2-23
2-9	Hudson River Tunnel Ventilation Design	2-24
2-10	Hoboken Fan Plant, View North (Conceptual Artist Rendering).....	2-26
2-11	Twelfth Avenue Fan Plant Potential Massing and Siting Scenarios	2-28
2-12	Tenth Avenue Fan Plant Potential Louvers Locations.....	2-28
2-13a	Existing Track Layout at PSNY	2-29
2-13b	Proposed Track Layout at PSNY	2-29
2-14	North River Tunnel: Existing and Proposed Cross Section	2-35
3-1	Overview of Construction Methods	3-4
3-2a	Construction of the Preferred Alternative: New Jersey	3-4
3-2b	Construction of the Preferred Alternative: New York	3-4
3-3	Examples of Tunnel Boring Machines (TBMs)	3-5
3-4	Typical Sequential Excavation Method (SEM) Mining Sequence.....	3-6
3-5	Types of Surface Alignments	3-11
3-6	Tonnelle Avenue Staging Area: Truck Routes and Access Roads	3-14
3-7	Hoboken Staging Area: Truck Routes	3-20
3-8	Low Cover Area: Ground Improvement Process (Deep Soil Mixing) and Typical Cross-Section	3-31



3-9	Potential Construction Zone for Vertical Ground Freezing in Hudson River Park	3-34
3-10	Potential Construction Zone for Sequential Excavation Method Tunneling in Hudson River Park.....	3-35
3-11	Tunneling Through Manhattan Bulkhead	3-37
3-12	Underpinning of Sewer in Twelfth Avenue	3-38
3-13	Twelfth Avenue Staging Area: Truck Routes	3-40
3-14	North River Tunnel Rehabilitation: Staging Area Option with Platform over North River Tunnel Tracks	3-48
3-15	North River Tunnel Rehabilitation: Staging Area Option with Platforms over North River Tunnel Tracks and Hudson River Tunnel Tracks	3-48
3-16	Overall Project Construction Schedule Assumed in the EIS – By Major Activity	3-52
3-17	Duration of Major Construction Activities Assumed in the EIS – By Staging Site.....	3-53
4-1	Project Site Overview	4-3
4-2	Project Site in New Jersey	4-3
4-3	Project Site in New York.....	4-3
4-4	Tax Lots on Twelfth Avenue Staging Site	4-4
4-5	Key Future Transportation Improvements.....	4-6
5A-1	Traffic Analysis Intersections in New Jersey: Tonnelles Avenue Staging Site and Truck Routes	5A-9
5A-2	Traffic Analysis Intersections in New Jersey: Hoboken Staging Site and Haul Route Option 1	5A-9
5A-3	Traffic Analysis Intersections in New Jersey: Hoboken Staging Site and Haul Route Option 2.....	5A-9
5A-4a	Traffic Analysis Intersections in New Jersey: Hoboken Staging Site and Haul Route Option 3.....	5A-9
5A-4b	Haul Route Option 3: New Intersection at 19th Street.....	5A-9
5A-5	Potential Off-Site Worker Parking Locations.....	5A-9
5A-6	Traffic Analysis Intersections in New York: Twelfth Avenue Staging Site and Truck Routes.....	5A-11
5A-7	Pedestrian Analysis Locations in New York: Twelfth Avenue Staging Site	5A-12
5B-1	Hudson-Bergen Light Rail Route in the Study Area.....	5B-6
5B-2a	Bus Routes in New Jersey	5B-7
5B-2b	Bus Routes in New York	5B-7
6A-1	New Jersey Land Use Study Area	6A-4
6A-2	New York Land Use Study Area.....	6A-4
6A-3	Land Use in Western Portion of New Jersey Study Area.....	6A-4
6A-4	Land Use in Eastern Portion of New Jersey Study Area.....	6A-4
6A-5	Zoning in Western Portion of New Jersey Study Area	6A-8
6A-6	Zoning in Eastern Portion of New Jersey Study Area	6A-8

6A-7	Land Use in New York Study Area	6A-15
6A-8	Zoning in New York Study Area	6A-17
6A-9	Potential Future Developments in New York Study Area	6A-22
7-1	Socioeconomic Conditions Study Area	7-3
7-2	Construction Effects to Businesses in the Meadowlands: Key Map	7-16
7-3	Construction Activity and Property Acquisition at 801 Penhorn Avenue, Secaucus	7-16
7-4	Construction Activity and Property Acquisition at 401 Penhorn Avenue, Secaucus	7-16
7-5	Construction Activity and Property Acquisition at 301 Penhorn Avenue, Secaucus	7-16
7-6	Construction Activity and Property Acquisition at 201 Penhorn Avenue, Secaucus	7-16
7-7	Construction Activity and Property Acquisition at 2806 Secaucus Road, North Bergen.....	7-16
7-8	Construction Activity and Property Acquisition at 2820 16th Street, North Bergen	7-16
8-1	Open Spaces in New Jersey Study Area	8-4
8-2	Open Spaces in New York Study Area	8-4
8-3	Hudson River Park Features Near Proposed Construction Zones	8-16
8-4	Shadows – Tier 1 and 2 Assessments.....	8-24
8-5	Northwest Location – December 21.....	8-24
8-6	Northwest Location – March 21 / September 21	8-24
8-7	Northwest Location – May 6 / August 6	8-24
8-8	West 29th Street Location – December 21	8-24
8-9	West 29th Street Location – March 21 / September 21.....	8-24
9-1	New Jersey: Area of Potential Effects.....	9-6
9-2	New York: Area of Potential Effects.....	9-6
9-3	New Jersey: Area of Potential Effects and Location of Historic Architectural Resources	9-10
9-4	North River Tunnel: Typical Existing Cross Section	9-11
9-5	New Jersey Historic Architectural Resources: North (Hudson) River Tunnel (NJ Resource No.1).....	9-11
9-6	New Jersey Historic Architectural Resources: Pennsylvania Railroad New York to Philadelphia Historic District (NJ Resource No. 2)	9-11
9-7	New Jersey Historic Architectural Resources: New Jersey Midland Railway/New York, Susquehanna and Western Railroad Historic District (NJ Resource No. 3)	9-11
9-8	New Jersey Historic Architectural Resources: Erie Railroad Main Line Historic District (NJ Resource No. 4)	9-11
9-9	New Jersey Historic Architectural Resources: Jersey City Waterworks Historic District (NJ Resource No. 5)	9-12
9-10	New Jersey Historic Architectural Resources: Substation No. 3, Pennsylvania Railroad (NJ Resource No. 6).....	9-12
9-11	New Jersey Historic Architectural Resources: Charles X. Harris House and Studio (NJ Resource No. 7)	9-12
9-12	New Jersey Historic Architectural Resources: Residence at 320-324 Mountain Road (NJ Resource No. 8)	9-12



9-13	New Jersey: Area of Potential Effects for Direct Effects and Areas of Archaeological Sensitivity	9-15
9-14	New York: Area of Potential Effects and Location of Historic Architectural Resources	9-16
9-15	New Jersey and New York Known Historic Architectural Resource: North River Tunnel (NJ and NY Resource No. 1).....	9-16
9-16	New York Known Historic Architectural Resources: Hudson River Bulkhead (NY Resource No. 2)	9-16
9-17	New York Known Historic Architectural Resources: High Line (NY Resource No. 3).....	9-17
9-18	New York Known Historic Architectural Resources: Master Printers Building (NY Resource No. 4).....	9-18
9-19	New York Known Historic Architectural Resources Demolished: Charles P. Rodgers & Co. Building (NY Resource No. 5 – Now Demolished)	9-19
9-20	New York Known Historic Architectural Resources: W & J Sloane Warehouse and Garage (NY Resource No. 6)	9-19
9-21	New York Known Historic Architectural Resources: Starrett-Lehigh Building (NY Resource No. 7)	9-19
9-22	New York Known Historic Architectural Resources: West Chelsea Historic District (NY Resource No. 8)	9-20
9-23	New York Known Historic Architectural Resources: West Chelsea Historic District (NY Resource No. 8)	9-20
9-24	New York Known Historic Architectural Resources: West Chelsea Historic District (NY Resource No. 8)	9-20
9-25	New York: Area of Potential Effects for Direct Effects and Areas of Archaeological Sensitivity	9-21
9-26	North River Tunnel: Existing Condition	9-23
9-27	North River Tunnel: Existing Condition	9-23
10-1a	New Jersey Area of Visual Effect and Photo Key Plan	10-4
10-1b	New York Area of Visual Effect and Photo Key Plan	10-4
10-2	Views of County Road to Tonnelle Avenue Area	10-4
10-3	Views along Tonnelle Avenue	10-4
10-4	Views along Paterson Plank Road	10-4
10-5	Views of Hoboken Fan Plant Site	10-4
10-6a	Views of the Shades Neighborhood, Weehawken	10-4
10-6b	Views of the Shades Neighborhood, Weehawken	10-4
10-7	View of Hoboken Fan Plant Site from Firefighters' Memorial Park	10-4
10-8	Views of Hudson River Park.....	10-4
10-9	Views of Twelfth Avenue Fan Plant Site	10-4
10-10	Twelfth Avenue Fan Plant Site	10-4
10-11	Views of New Development on Block 675	10-4
10-12	Views of Hudson Yards Development.....	10-4

10-13	Views from the High Line	10-4
10-14	View of Tenth Avenue between West 31st and West 33rd Streets	10-4
10-15	Illustrative View of Hoboken Fan Plant	10-15
11-1	Flood Hazard Areas, Preliminary FIRM: New Jersey Study Area	11-7
11-2	Wetlands Mapped by the National Wetlands Inventory	11-8
11-3	Wetlands Mapped by the New Jersey Department of Environmental Protection	11-8
11-4a	Delineated Wetlands	11-9
11-4b	Delineated Wetlands	11-9
11-4c	Delineated Wetlands	11-9
11-5	Thickness of Unconsolidated Sediments and Groundwater Wells	11-10
11-6	Penhorn Creek Drainage	11-10
11-7	Flood Hazard Areas, Preliminary FIRM: New York Study Area	11-35
11-8	NYSDEC Littoral Zone Tidal Wetlands	11-35
12A-1	FTA Noise Impact Criteria for Transit Projects	12A-6
12A-2	New Jersey Noise Receptor Locations	12A-10
12A-3	New York Noise Receptor Locations	12A-14
12B-1	New Jersey Vibration Receptor Locations	12B-8
12B-2	New York Vibration Receptor Locations	12B-9
15-1	Bedrock Geology in the Study Area	15-3
15-2	Geologic Hazards within the Study Area	15-3
22-1	Environmental Justice Communities in the Study Area	22-4
24-1	Section 4(f) Park Resources in New Jersey	24-7
24-2	Section 4(f) Park Resources in New York	24-7
24-3	Hudson River Park Walkway and Route 9A Bikeway near West 29th Street	24-19
24-4	Section 4(f) Historic Resources in New Jersey	24-19
24-5	Section 4(f) Historic Resources in New York	24-33
24-6	Hudson River Park Features near Proposed Construction Zones	24-35
24-7	Potential Construction Zone for Vertical Ground Freezing in Hudson River Park	24-36
24-8	Potential Construction Zone for Sequential Excavation Method Tunneling in Hudson River Park	24-37