# POST MORTEM INVESTIGATION OF THE KANSAS TEST TRACK



NOVEMBER 1979 FINAL REPORT

Document is available to the public through the National Technical Information Service, Springfield, Virginia 22161.

**Prepared** for

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL RAILROAD ADMINISTRATION Office of Research and Development Washington, D.C. 20590



## NOTICES

This document is disseminated under the sponsorship of the Department of Transportation in the interest of information exchange. The United States Government assumes no liability for its contents or use thereof.

The United States Government does not endorse products or manufacturers. Trade or manufacturers' names appear herein solely because they are considered essential to the object of this report.

**Technical Report Documentation Page** 

1. Report No.	2. Government Accession	No. 3.	Recipient's Catalog	No.
FR4 /ORD_ 79 /09 TT			,	
A Title and Subtitle			Report Date	·····
	י היניס	5.	February, 197	79 <sup>-</sup>
KANSAS TEST TRACK, VOLUME I	IIIE I	6.	Performing Organizat	ion Code
7. Author(s)		8.	Performing Organizat	ion Report No.
S. S. Cooper H. C. Gr A. J. Bush III M. A. Vi	eer III M. M. .spi	. Carlson	· · · · · · · · · · · · · · · · · · ·	
9. Performing Organization Name and Address	s	10.	Work Unit No. (TRA	15)
U. S. Army Engineer Waterwa	ys Experiment Sta	ation 11	Contract or Grant N	·····
Geotechnical Laboratory	Naa 20180		DOT AR-3002	5
P. U. BOX 031, Vicksburg, M	1188• 29100	13.	Type of Report and	Period Covered
12. Sponsoring Agency Name and Address	· · · · · · · · · · · · · · · · · · ·		Final Report	
U. S. Department of Transpo	rtation		6/1/75_10/1/	76
Office of Rail Safety Recea	rch	14	Sponsoring Agency (	I Y
Washington, D. C. 20590			RRD-32	
15. Supplementary Notes				
	۰ ۲			ĸ
		· · · · · · · · · · · · · · · · · · ·		
which were founded on a des ture failure in service, ar approximately six months of	(KTT) was compris signed embankment nd KTT operations f traffic.	sed of nine di . The KTT sub were terminat	grade experies ed in June 19	nced prema- 75 after
which were founded on a des ture failure in service, an approximately six months of A postmortem investigation conclusions, and recommendation of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was comprising signed embankment and KTT operations traffic. Ation of the KTT with ion are presented ations are present ocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigate conclusions, and recommenda of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was comprising signed embankment, nd KTT operations f traffic. Ation of the KTT we ion are presented ations are presented ations are present pocument the equipt ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and is	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigation conclusions, and recommendation of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was comprising signed embankment and KTT operations traffic. Ation of the KTT we ion are presented ations are presented ations are present pocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigat conclusions, and recommenda of five appendixes which do tained in KTT structures, w tion testing.	(KTT) was comprising signed embankment and KTT operations traffic. Ation of the KTT with the are presented ations are present ocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigate conclusions, and recommenda of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was comprising signed embankment, and KTT operations for traffic. Ation of the KTT we ion are presented ations are presented ations are present ocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigation conclusions, and recommendation of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was comprising signed embankment and KTT operations traffic. Ation of the KTT we ion are presented ations are presented ations are presented provide the equipted of the second second second provide the second second second second second second second second second second second second second second second second second second second seco	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigat Results of this investigatic conclusions, and recommendat of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was comprising signed embankment and KTT operations traffic. ation of the KTT w ion are presented ations are present ocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigat conclusions, and recommenda of five appendixes which do tained in KTT structures, w tion testing.	(KTT) was comprising signed embankment and KTT operations traffic. ation of the KTT with ion are presented ations are present ocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigate conclusions, and recommenda of five appendixes which do tained in KTT structures, w tion testing.	(KTT) was comprising signed embankment, and KTT operations for traffic. Ation of the KTT we ion are presented ations are presented ations are present pocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a dest ture failure in service, an approximately six months of A postmortem investigation conclusions, and recommendation of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was compris signed embankment nd KTT operations traffic. ation of the KTT w ion are presented ations are present ocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
which were founded on a des ture failure in service, an approximately six months of A postmortem investigate conclusions, and recommenda of five appendixes which do tained in KTT structures, we tion testing.	(KTT) was comprising signed embankment and KTT operations traffic. ation of the KTT with ion are presented ations are present ocument the equip ribroseismic, pend	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre	t in 1975 and s. Summary d I. Volume II dure used, an nching, and i	nced prema- 75 after 1976. ata, analyses is comprised d data ob- nstrumenta-
<ul> <li>Ine Kansas Test Frack</li> <li>which were founded on a desture failure in service, an approximately six months of A postmortem investigate conclusions, and recommendate of five appendixes which do tained in KTT structures, which the testing.</li> <li>17. Key Words</li> <li>Kansas Test Track, Structure Vibroseismic Testing, Pene</li> </ul>	(KTT) was comprising signed embankment and KTT operations traffic. ation of the KTT with the are presented ations are presented ations are present ocument the equip ribroseismic, pend ribroseismic, pend 18.	<ul> <li>The KTT sub were terminat</li> <li>was carried ou in two volume ted in Volume ment and proce etrometer, tre</li> <li>Distribution Statement</li> <li>Report is avai through the Na</li> </ul>	lierent track grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and is hoching, and is lable to the tional Techni	U. S. public cal Informa-
<ul> <li>Ine Kansas Test Track</li> <li>which were founded on a desture failure in service, an approximately six months of A postmortem investigate conclusions, and recommendate of five appendixes which do tained in KTT structures, which do tained in KTT structures, which testing.</li> <li>17. Key Words</li> <li>Kansas Test Track, Structure Vibroseismic Testing, Trenching, Instructure Testing</li> </ul>	(KTT) was comprising signed embankment and KTT operations for traffic. Traffic. Traffic. The second second to are presented ations are presented ations are presented ations are presented to are presented ations at a presented ation at a presented ation at a presented at a presented	sed of nine di The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre Distribution Statement Report is avai through the Na tion Service,	lierent track grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and i nching, and i lable to the tional Techni Springfield,	U. S. public cal Informa- va. 22161.
<ul> <li>Ine Kansas Test Track which were founded on a desture failure in service, an approximately six months of A postmortem investigate conclusions, and recommendate of five appendixes which do tained in KTT structures, which the tained in KTT structures, which testing.</li> <li>17. Key Words Kansas Test Track, Structure Vibroseismic Testing, Pener Testing, Trenching, Instructure Testing</li> <li>18. Security Classif (of this error)</li> </ul>	(KTT) was comprising signed embankment and KTT operations traffic. Ation of the KTT with ion are presented ations are present boument the equip ribroseismic, pend ribroseismic, pend re Testing, trometer mentation	sed of nine di . The KTT sub were terminat was carried ou in two volume ted in Volume ment and proce etrometer, tre Distribution Statement Report is avai through the Na tion Service,	lierent track grade experies ed in June 19 t in 1975 and s. Summary d I. Volume II dure used, an nching, and is lable to the tional Techni Springfield,	U. S. public cal Informa- Va. 22161.

#### PREFACE

This study was authorized by the Department of Transportation (DOT) Federal Railroad Administration (FRA) under Interagency Agreement AR 30025, dated 12 December 1972, and Amendments 3-8 thereto. The work was performed by personnel of the U. S. Army Engineer Waterways Experiment Station (WES), P. O. Box 631, Vicksburg, Mississippi 39180. Dr. R. M. McCafferty of the Office of Rail Safety Research, FRA, monitored the project.

Mr. A. J. Bush III, Pavement Evaluation Branch, Geotechnical Laboratory (GL), carried out the field and laboratory trenching study. Mr. H. C. Greer, Instrumentation Services Division, was responsible for the instrumentation investigation, and Mr. M. A. Vispi, Explorations Branch, GL, accomplished the penetrometer testing. Mr. M. M. Carlson conducted the vibroseismic testing. Mr. S. S. Cooper, Geodynamics Branch (GDB), Earthquake Engineering and Vibrations Division (EE&VD), directed the investigation and prepared this report under the supervision of Mr. R. F. Ballard, Chief, GDB, and Messrs. P. F. Hadala and F. G. McLean, Chief and former Chief, respectively, of EE&VD. The work was performed under the general supervision of Mr. J. P. Sale, Chief, GL.

COL G. H. Hilt, CE, and COL J. L. Cannon, CE, were Directors of the WES during this study. Mr. F. R. Brown was Technical Director.

iii

# METRIC CONVERSION FACTORS

	Approximate Co	versions to Metri	c Measures		3		Approximate Conversions from Metric Measures			
Symbol	When You Know	Multiply by	Te Find Symbol			Symbol	When You Know	Multiply by	To Find	Symbol
			•	•			<del></del>	LENGTH		
		LENGTH			<u>≡</u> *		1			
	· · · · ·		•	·		mm	millimeters	0.04	inches	in
			4 1.	·		CM	contimeters	0.4	inches	in
' in	inches	*2.5	Centimeters CM			m	maters	3.3	test	п.
tt	feet	30	centimeters cm		· <u> </u>	m 1	moters	1.1	yanus	yu mi
٧đ	yards	0.9	meters m	·	<u></u>	KIN .	K1 (Ometers	0.0	miles	
mi	miles .	1.6	kilameters .km	·	E E					
		ADEA			<b></b>			AREA	~	
		ANCA				•				-
				•	Ē	cm <sup>r</sup> .	siquare centimeters	0.16	square inches	is <sup>2</sup>
in"	square inches	6.5	square centimeters cm*		<u> </u>	m <sup>4</sup>	square meters	1.2	square yards	yd <sup>2</sup>
tt"	square feet	0.09	square moters m <sup>4</sup>		=	km <sup>2</sup> .	square kilometers	0.4	square miles	mi <sup>2</sup>
yď	square yards	0,8	square meters m <sup>4</sup>			ha	hectares (10,000 m <sup>2</sup>	2.5	acres	
mif	aquare miles	2.6	square kilomoters km*				• • •			
	80108	0.4	hectares he		<u> </u>		·			
ヒ				a	- · ·		1	MASS (weight)		• •
٩ .		MASS (weight)	· · · · · · · · · · · · · · · · · · ·				· · · ·		•	
<b>A</b> 7	040265		013/016			9 1	grams	0.035	ounces	GI
ih.	nounds	0.45	kiloorama ka			kg	kilograms	2.2	pounds	i b
	abort tons	0.45	toppen i t	·		t	tonnes (1000 kg)	1.1	short tons	
	(2000 lb)			•	<u> </u>					
		VOLUME						VOLUME		
								TOLOME	•	
tsp	teaspoons	5	mittiliters ml	· . —	<u>a</u>	mt	milliliters	0.03	fluid ounces	floz
Theo	tablespoons	15	milliliters ml		•	1	. liters	2.1	pints	pt .
floz	fluid ounces	30	milliliters ml	<u>۔</u> ۳	<u> </u>	ł	liters	1.06	quarts	qt
c	- cups	0.24	liters I			١.	liters	0.25	gallons	gel
pt .	pints	0.47	liters I			ີ	cubic meters	35	cubic feet	ft"
qt	quarts	0.95	liters I			mJ	Cubic meters	1.3	cubic yards	۳d۳
gal	gellons	3.8	liters I							
ft <sup>3</sup>	cubic feet	0.03	cubic meters m <sup>3</sup>							
۶ď	cubic yards	0.76	cubic meters m <sup>3</sup>	N	<u> </u>		IEM	PERATURE (exect)		
	TEMI	PERATURE (exact)				°c	Celsius	9/5 (then	Fabrenheit	• •F
						•	temperature	add 32)	temperature	
•	Fahrenheit	5/9 (after	Celsius °C		<u> </u>					
	tomporature	subtracting	temperature		<b>H</b>	· .	_ · ·		•F	
	-	34)			"		°F 32	98-6	212	
						· -	40 0 40	80 IZO	160 200	
*1 in # 2.5	4 (exactly). Fur other exact con	versions and more detaile	d tables, see NBS Misc. Publ. 286,	iz -1						
Units of Wei	ghts and Measures, Price \$2.25,	SD Catalog No. C13.10:28	B6	*		· -	40 -20 0	20 140 1	•C •C	,
				<u>0</u>	<u> </u>		-u .	¥1		

# TABLE OF CONTENTS

t

Ξ.

•

. 7

~ ,

	+ +	•	Page
INTRODUCTION			1
APPENDIX A: STRUCTURES TESTINGS			A-1
General Dynamic Testing Static Load-Deflection Tests Plate Bearing Tests	· · ·		A-1 A-1 A-3 A-4
APPENDIX B: VIBROSEISMIC STUDY	٣		B-1
General Test Plan Field Testing Computation of Poisson's Ratio and Elastic Moduli	•		B-1 B-1 B-2 B-4
APPENDIX C: DUTCH CONE PENETROMETER TESTS			C-l
General Test Plan Field Testing			C-1 C-1 C-1
APPENDIX D: TRENCHING, SAMPLING, AND SOIL TESTING			D-1
General Test Plan Field Testing Laboratory Testing	. '	·	D-1 D-1 D-1 D-3
APPENDIX E: INSTRUMENTATION			E-1
General Transducers Dynamic Recording Equipment Field Calibrations and Measurements Field Observations Posttest Laboratory Calibration of Soil Pressure Cells Soil Moisture and Temperature Sensors	:		E-1 E-1 E-2 E-2 E-4 E-5 E-5
PCA Carlson Pressure Cells	,		E-6
LIST OF TABLES		5 <sup>0</sup>	

Table <u>No.</u>	L		Title				
A1.	STATIC LOAD POSTMORTEM)	VERSUS VERTICAL TEST NO. 1	DEFLECTION	TEST	RESULTS	(KTŢ	А-б
A-2	STATIC LOAD POSTMORTEM)	VERSUS VERTICAL TEST NO. 2	DEFLECTION	TEST	RESULTS	(KTT	A-7

v

.

Table No.	Title	Page
A-3	STATIC LOAD VERSUS VERTICAL DEFLECTION TEST RESULTS (KTT POSTMORTEM) TEST NO. 3	A-8
A-4	STATIC LOAD VERSUS SURFACE STRAIN TEST RESULTS (KTT POSTMORTEM) TEST NO. 1	A-9
A-5	STATIC LOAD VERSUS SURFACE STRAIN TEST RESULTS (KTT POSTMORTEM) TEST NO. 2	A-10
A-6	STATIC LOAD VERSUS SURFACE STRAIN TEST RESULTS (KTT POSTMORTEM) TEST NO. 3	A-11
A-7	30-INDIAM. PLATE BEARING TEST RESULTS (KTT POSTMORTEM) ON KTT SUBGRADE	A-12
B-1	RESULTS OF VIBROSEISMIC SURVEY	в-б
D <b>-</b> 1	LOCATIONS OF EACH TEST TRENCH	D-5
D <b>-</b> 2	PLATE BEARING TEST RESULTS	D-6
D <b>-</b> 3	KANSAS TEST TRACK TEST PIT 1	·D <b>-</b> 7
D-4	KANSAS TEST TRACK SECTION 2A	D-10
D <b>-</b> 5	KANSAS TEST TRACK SECTION 2B	D-12
D-6	KANSAS TEST TRACK SECTION 3A	D-14
D <b>-</b> 7	KANSAS TEST TRACK SECTION 3B	D-16
D <b>-</b> 8	KANSAS TEST TRACK SECTION 4	D-18
D <b>-</b> 9	KANSAS TEST TRACK SECTION 5	D-20
D-10	KANSAS TEST TRACK SECTION 7	D-22
D-11	KANSAS TEST TRACK SECTION 8	D-24
D-12	KANSAS TEST TRACK SECTION 9	D-26
D <b>-</b> 13	LABORATORY TEST RESULTS ON BALLAST SAMPLES	D-28
D-14	LABORATORY CLASSIFICATION TESTS ON SUBGRADE SAMPLES	D-29
E-1	FINAL EXTENSOMETER INDICATIONS	E-7
E-2	FINAL INDICATIONS, MOISTURE AND TEMPERATURE FROM MC300A METER	E-8
E-3	INSULATION TO GROUND, TEST SECTION 2, 20 MAY 1976	E-9
E-4	INSULATION TO GROUND, TEST SECTION 7, 18 MAY 1976	E-10
E-5	INSULATION TO GROUND, TEST SECTION 9, 19 MAY 1976	. E-11
E-6	CONDITION OF EXTENSOMETER LVDT ASSEMBLY	E-12
E-7	IN SITU CALIBRATION VALUES FOR EXTENSOMETERS, 20 MAY 1976	E-13

Table

.

No.	Title	Page
E-8	POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 2203	E-14
E-9	POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 7201	E-15
E-10	POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 7202	E-16
E-11	POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 7203	E-17
E-12	POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 9201	E-18
E-13	POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 9202	E-19
E-14	CALIBRATION HISTORY OF MAIN INSTRUMENTATION ARRAY SLOPE INDICATOR COMPANY PRESSURE CELLS	E-20

# LIST OF FIGURES

Figure No.	Title	
1	GRAPHICAL SUMMARY OF WES TEST PLAN	
A-1	TIME TABLE DEVELOPED FOR WES PHASE I FIELD OPERATIONS	A-13
A-2	GAGE CONFIGURATION FOR STATIC AND DYNAMIC STRUCTURE TESTS	A-14
A-3	DETAILS OF DIAL GAGE INSTALLATIONS	A-15
A-4	STRAIN GAGE INSTRUMENTATION, BEAM 16, NORTH RAIL, TRACK SECTION $4$	A-16
<u>-</u> 1–5	LOADING CONFIGURATION FOR LOAD-DEFLECTION TESTS	A-17
А-б	PLOTS OF LOAD VERSUS SURFACE STRAIN FROM LOAD-DEFLECTION TEST 1	A-18
A-7	PLOTS OF LOAD VERSUS SURFACE STRAIN FROM LOAD-DEFLECTION TEST 2	A-19
8–A	PLOTS OF LOAD VERSUS SURFACE STRAIN FROM LOAD-DEFLECTION TEST 3	A-20
A-9	LOCATION OF 30-INDIAM PLATE BEARING TEST ON SUBGRADE	A-21
A-10	PLATE BEARING TEST RESULTS, LOCATION 1	A-22
A-11	PLATE BEARING RESULTS, LOCATION 2	A-23
A-12	PLATE BEARING TEST RESULTS, LOCATION 3	A-24
B-1	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 1, STA 8534+75	B-11
B-2	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 2, STA 8531+62.5	B <b>-11</b>

Figure No.	Title	: Page
B-3	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 2, STA 8535+15	B-12
в-4	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 3, STA 8540+19	B-12
B-5	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 3, STA 8542+50	· B <b>-</b> 13
в-6	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 4, STA 8547+79	-B-13
В-7	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 5, STA 8558+30	в-14
в-8	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 7, STA 8576+42	B-14
B <b>-</b> 9	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 8, STA 8586+00	B-15
B-10	POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 9, STA 8595+33	· B-15
B11	TYPICAL VIBROSEISMIC TEST CONFIGURATION	B-16
B-12	TYPICAL VELOCITY DETERMINATIONS FROM VIBRATION TEST, POSTTRAFFIC, TRACK SECTION 3, STA 8540+09	B-17
B-13	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 1, STA 8524+75	B-17
B-14	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 2, STA 8531+62.5	B <b>-</b> 18
B-15	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 2, STA 8535+15	B <b>-</b> 18
в–16	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 3, STA 8540+09	B-19
B-17	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 3, STA 8542+05	B-19
B-18	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 4, STA 8547+79	B <b>-</b> 20
_ B-19	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 5, STA 8558+30	B <b>-</b> 20
B-20	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 7, STA 8576+42	B-21
B-21	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 8, STA 8587+00	B-21
,		

2 1

Figure No.	Title	Page
B-22	POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 9, STA 8595+33	B-22
B∸23	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 1, STA 8524+75	в <b>-</b> 23
B-24	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 2, STA 8531+62.5	B-23
B-25	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 2, STA 8535+15	B-24
в-26	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 3, STA 8540+19	B-25
B-27	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 3, STA 8542+50	B-25
. В-28	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 4, STA 8547+79	в-26
B-29	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 5, STA 8558+30	в-26
B-30	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 7, STA 8576+42	B-27
B-31	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 8, STA 8587+00	B-27
B-32	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 9, STA 8595+33	B-28
B-33	POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTIONS 1 THROUGH 9	в <b>-</b> 28
C-1	ACTION OF FRICTION JACKET CONE	C-4
C-2	PORTABLE DUTCH CONE PENETROMETER	C-5
C-3	MODIFIED DUTCH CONE PENETROMETER AT TEST LOCATION IN TRACK SECTION 3	с-б
<b>C-</b> 4	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 1, STA 8521+01	C-7
C-5	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 1, STA 8523+00	<b>C-</b> 8
c-6	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 1, STA 8525+00	C-9
C-7	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 1, STA 8527+00	C-10
C-8	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 2, STA 8529+00	C-11

ix

Title	Page
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 2, STA 8531+00	C-12
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 2, STA 8533+00	C-13
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DETPH IN THE SUBGRADE, TRACK SECTION 2, STA 8534+96	C-14
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8538+00	C-15
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8540+00	C-16
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8542+30.3	C-17
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8544+00	C-18
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8546+45 AND 8546+50	C-19
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8547+95 AND 8548+00	C-20
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8549+95 AND 8550+00	C-21
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8551+55 AND 8551+60, NORTH BEAM	C-22
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8551+55 AND 8551+60, SOUTH BEAM	C-23
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8553+95 AND 8554+00	C-24
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8555+95 AND 8556+00	C-25
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8557+95 AND 8558+00	c-26
DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8558+27.5 AND 8558+30	C-27
	Title DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 2, STA 8531+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DETPH IN THE SUBGRADE, TRACK SECTION 2, STA 8534+96 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DETTH IN THE SUBGRADE, TRACK SECTION 3, STA 8534+96 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8538+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8540+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8540+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8544+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8546+45 AND 8546+50 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8547+95 AND 8546+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8547+95 AND 8546+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8547+95 AND 8550+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8551+55 AND 8551+60, NORTH BEAM DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8551+55 AND 8551+60, SOUTH BEAM DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8551+55 AND 8551+60, SOUTH BEAM DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8551+95 AND 8551+60 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8557+95 AND 8558+00 DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8557+95 AND 8558+00 DUTCH CONE PENETROMETER DRIVE POINT R

TR.2 ...

No.	Title	Page
C-25	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8559+95 AND 8560+00	C-28
C-26	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8561+95 AND 8562+00	Ċ-29
C-27	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8570+95 AND 8571+00	C-30
C-28	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8573+00 AND 8573+05	C-31
C-29	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8574+50 AND 8574+55	C-32
C-30	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8576+10 AND 8576+15, NORTH BEAM	C-33
C-31	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8576+10 AND 8576+15, SOUTH BEAM	C-34
C-32	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8578+00 AND 8578+05	C-35
C-33	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8581+30	C-36
C-34	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8583+00	C-37
C-35	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8585+00	C-38
C-36	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8586+80	C-39
C-37	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8588+00.5	C-40
C-38	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8591+01	C-41
C-39	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8593+00	C-42
C-140	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8594+82.7	C-43

Figure No.	Title	Page
C-41	DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8596+31	 C-44
D-1	PROFILES AND CROSS SECTION OF TEST SECTION 1	D-30
D-2	PROFILES AND CROSS SECTION OF TEST SECTIONS 2A AND 3A	D-31
D-3	PROFILES AND CROSS SECTION OF TEST SECTION 2B	D-32
D-4	PROFILES AND CROSS SECTION OF TEST SECTION 3B	D <b>-</b> 32
<sup>-</sup> D-5	PROFILES AND CROSS SECTION OF TEST SECTION 4	D-33
D-6	PROFILES AND CROSS SECTION OF TEST SECTION 5	D-34
D-7	PROFILES AND CROSS SECTION OF TEST SECTION 7	D <b>-</b> 35
D-8	PROFILES AND CROSS SECTION OF TEST SECTION 8	D <b>-</b> 36
. D <b>-</b> 9	PROFILES AND CROSS SECTION OF TEST SECTION 9	D-36
D-10	TYPICAL PLATE BEARING TEST SETUP	D <b>-</b> 37
D-11	TYPICAL PLATE BEARING LOAD-DEFLECTION PLOT	D-38
D-12	TYPICAL LOCATIONS OF BALLAST AND UNDISTURBED SOIL SAMPLES ON TIE SECTIONS	D <b>-</b> 39
D-13	TYPICAL LOCATIONS OF BALLAST AND UNDISTURBED SOIL SAMPLES ON BEAM SECTIONS	Ď≕40
D-14	LOCATIONS OF FIELD TESTS AND SAMPLES ON TRACK SECTION 5	D-41
D-15	SUBGRADE SURFACE OF TEST PIT 1	D-42
D-16	SOUTH WALL OF TEST PIT 2A, (NOTE BALLAST SUBGRADE INTERFACE)	D-43
D-17	CROSS SECTION OF SUBGRADE SURFACE, (NOTE BEAM EDGES ARE RESTING ON SHOULDER SUBGRADE INPICATING 3-1/2- TO 4-IN. RELATIVE DEFORMATION UNDER TRACK STRUCTURE)	44
D-18	TYPICAL LOCATIONS OF FIELD TESTS ON TIE SECTIONS	D-45
D <b>-</b> 19	TYPICAL LOCATIONS OF FIELD TESTS ON BEAM SECTIONS	D-46
D-20	CALIFORNIA BEARING RATIO (CBR)	D-47
D-21	LABORATORY COMPACTION TEST RESULTS (MODIFIED AASHO EFFORT), TRACK SECTION 1	D-48
D-22	LABORATORY COMPACTION TEST RESULTS (MODIFIED AASHO EFFORT), TRACK SECTION 4	D-49
D-23	LABORATORY COMPACTION TEST RESULTS (MODIFIED AASHO EFFORT), TRACK SECTION 9	D-50
D-24	UNCONSOLIDATED, UNDRAINED (Q) TRIAXIAL TEST RESULTS FROM TEST PITS 1 AND 4	D <b>-</b> 51

.

.

Figure No.	Title	Page
D-25	UNCONSOLIDATED, UNDRAINED (Q) TRIAXIAL TEST RESULTS FROM TEST PIT 9	D-52
D-26	UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 1 AND 2A	D-53
D-27	UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 2B AND 3A	D-54
D-28	UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 3B AND $^{\mathrm{h}}$	D-55
D-29	UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 5 AND $\gamma$	D <b>-</b> 56
D-30	unconfined compression test results from test pits 8 and 9	D <b>-</b> 57
E-1	CALIBRATION NETWORK FOR SCHAEVITZ LVDT	E-21
É–2	INSTRUMENTATION LAYOUT	E-22
E-3	INSTRUMENT INSTALLATION DETAILS	E-23
, E-4	TEST SECTION 1, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY	E-24
E-5	TEST SECTION 2, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY	E-25
Е-б	TEST SECTION 3, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY	e-26
E-7	TEST SECTION 7, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY	Е <b>-</b> 27
E-8	TEST SECTION 8, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY	E-28
E-9	TEST SECTION 9, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY	<sup>-</sup> Е–29
E-10	TEST SECTION 2, MAIN INSTRUMENTATION ARRAY	E-30
E-11	TEST SECTION 2, EXCAVATED EXTENSOMETER	E-31
E-12	TEST SECTION 2, 2402 TERMINAL BOX	E <b>-</b> 32
E-13	TEST SECTION 2, 2401 TERMINAL BOX	E-33
E-14	TEST SECTION 2, EXCAVATION 2201	E-34
E-15	TEST SECTION 7, MAIN INSTRUMENTATION ARRAY	E-35
E-16	ANCHOR PRONG-SOIL COMPLING FOR GAGES 7401-1 AND 7402-1, TEST SECTION 7	Е-36
E-17	ANCHOR PRONG-SOIL COMPLING FOR GAGE 7-01-1, TEST SECTION 7	E <b>-</b> 37

Figure No.	Title	Page
E-18	TEST SECTION 7, 7401 TERMINAL BOX	E-38
E-19	TEST SECTION 7, 7402 TERMINAL BOX	E-39
E-20	TEST SECTION 7, EXCAVATION OF 7401 AND 7402	E-40
E-21	TEST SECTION 9, PRESSURE CELLS 9201 AND 9202	E-41
E-22	TEST SECTION 9, EXTENSOMETER EXCAVATION	E-42
E-23	EXTENSOMETER TERMINAL BOX EXCAVATION SHOWING TILT AND WATER SEEPAGE, TEST SECTION 9	E-43
E-24	TEST SECTION 6, FAILURE OF EXTENSOMETER 6402	E-44
E-25	TEST SECTION 8, FAILURE OF EXTENSOMETER 8402	E-45
E-26	CALIBRATION NETWORK FOR SLOPE INDICATOR COMPANY SOIL PRESSURE CELL	Е-46
E-27	POST EXCAVATION CALIBRATION, SOIL PRESSURE CELL 9201	E-47
E-28	POST EXCAVATION CALIBRATION, SOIL PRESSURE CELL 2203	E-48
́Е-29	POST EXCAVATION CALIBRATION, SOIL PRESSURE CELL 7201	E-49
E-30	POST EXCAVATION CALIBRATION, SOIL PRESSURE CELL 7202	E-50
E-31	POST EXCAVATION CALIBRATION, SOIL PRESSURE CELL 7203	E-51
E-32	POST EXCAVATION CALIBRATION, SOIL PRESSURE CELL 9202	E-52
E-33	LETTER REPORT FROM SOILTEST, INC., TO WES CONCERNING DEFECTIVE SOIL MOISTURE CELLS	E-53
E-34	DIFFERENTIAL SETTLEMENT IN PCA PRESSURE CELL ARRAY, TEST SECTION 3	E-56
E-35	PCA PRESSURE CELL IN CLOSE PROXIMITY TO REINFORCING BAR, TEST SECTION 7	E-57
E <b>-</b> 36	WOODEN WEDGE DRIVEN AGAINST PCA PRESSURE CELL, TEST SECTION 7	E-58
E-37	LIME ENCRUSTATION ON PCA PRESSURE CELL, TEST SECTION 7	E-59
E-38	DAMAGE TO CORK LINER AROUND SIDES OF PCA PRESSURE CELL, TEST SECTION $\boldsymbol{\gamma}$	Е-60

## POSTMORTEM INVESTIGATION OF THE

KANSAS TEST TRACK, VOLUME II

## INTRODUCTION

In consideration of the quantity of data and information generated in KTT Postmortem Investigation, results are presented in two volumes. Volume I describes the postmortem test plan, summarizes results of the field and laboratory tests conducted, and presents analyses, conclusions, and recommendations derived from the test results. Volume II provides detailed descriptions of test equipment and procedures used in the investigation and also documents the original data. Volume II consists of five appendixes, A-E, which refer to the text in Volume I and document the structures, vibroseismic, Dutch cone penetrometer, trenching, and instrumentation studies, respectively. A summary of the U. S. Army Engineer Waterways Experiment Station (WES) test plan is presented in Figure 1 to assist the reader in identifying test locations with in the KTT.



FIGURE 1. GRAPHICAL SUMMARY OF WES TEST PLAN

.

10

N

#### APPENDIX A: STRUCTURES TESTING

#### General

The Kansas Test Track (KTT) Phase I Postmortem Investigations requested by the Department of Transportation (DOT) were conducted by a U. S. Army Engineer Waterways Experiment Station (WES) field party at the KTT in the period from 15 October - 17 November 1975. The sequence and timing of the various investigations conformed closely to the timetable developed by WES in joint planning with DOT and associated participants. This timetable, which was furnished to all interested parties before field operations commenced, is shown in Figure A-1. Essentially, Phase I field operations included dynamic and static testing to provide data to validate and tune MITRE Corporation analytical models, as well as posttraffic impedance studies of selected track sections. Selection of test locations within the track sections of interest was based on performance summary charts developed by WES from maintenance records furnished by the Atchinson, Topeka, and Santa Fe Railroad (AT&SF) and from an on-site reconnaissance trip performed in late September 1975.

The WES field crew, which consisted of a project engineer and two technicians in the early part of the field operations, was augmented by two WES instrumentation specialists who provided the required expertise in strain gaging and signal conditioning for dynamic testing and data acquisition. The various phases of the investigation were coordinated with AT&SF representatives at the KTT. It should be noted that the decision rendered in the early September meeting at DOT to conduct the balance of the Postmortem Investigation in the spring of 1976 was a sound one because the deterioration in weather conditions after 17 November and other considerations would certainly have prevented completion of the remaining (Phase II) work during the winter season of 1975. A discussion of the structures testing conducted in Phase I is presented in subsequent paragraphs.

## Dynamic Testing

The WES project engineer in charge of field operations arrived at

A-1.

the KTT on 15 October 1975. Watering (for the purpose of inducing a pumping condition) on the track sections selected for impedance testing had already commenced. The track was inspected and the timetable for field operations was confirmed in detail. At this time the test locations had already received approximately 4000 gal\* of water in 1000-gal increments. Installation of nine vertical (absolute) reference rods was begun on 16 October and was completed 18 October. Details of this installation are shown in Figures A-2 and A-3. During the installation process on 17 October, free water was encountered at the base of Beam 16 (Track Section 4); hence, watering at the impedance test location in Track Section 4 (sta 8546+95) was suspended. Apparently, the water applied to the impedance test location had migrated along the track structure to the structures test location at Beams 14-18 of Track Section 4; this was an undesirable condition for purposes of the planned structures tests. The impedance test location for Track Section 4 was shifted to Beam 78 (sta 8553+95). This location was believed to be of comparable characteristics to the original location and was sufficiently removed so that water migration to the structures test location would not occur. No free water was encountered at Beams 14-18 after the impedance test (watering) location was shifted.

Strain gaging of Beam 16 in accordance with MITRE specifications commenced on 17 October and was completed by 21 October. Figure A-4 shows the strain gage configuration used. During this time, differential motion Linear Variable Differential Transformers (LVDT) and absolute motion film potentiometers were also mounted in the required locations. The train to be used for dynamic loading, consisting of an engine, two loaded ballast cars, and a caboose, arrived at the KTT on the morning of 22 November. After some preliminary slow runs across the test area, it was concluded that the differential motion LVDT's were not behaving properly. Special mounts were fabricated in the field so that the relative motion LVDT's could be replaced with more

\* A table of factors for converting units of measurement is presented on page iv.

È.

sensitive carbon film potentiometers which had been prepared as alternates; excellent results were obtained with the film pots during calibration runs at very slow train speeds (verified by dial gage measurements) and during the ensuing dynamic tests at higher train speed.

Dynamic measurements of the test sections response to 17 train runs at speeds from 10-50 mps were made on 20 October. MITRE representatives were present during this phase of testing. A total of 13 data channels were recorded on tape, including measurements of relative motion (two channels), absolute motion (four channels), acceleration (one channel), particle velocity (two channels), and surface strain (four channels). Playbacks of the taped data onto oscillographs were examined in the field, and all channels, except those from the strain gages at the east of Beam 16, appeared to yield consistent results of good quality. The observed lack of response from the east end strain gages could not be explained at the time, but this phenomenon (after a more thorough examination in conjunction with the overall data picture) may have been due to rail-fastener-beam-load transfer characteristics in the dynamic test configuration since the gages in question did respond more consistently in later (static) testing. No modifications or repairs were made to the gages installed at the east end of the beam. However, another strain gage was added at this location for redundancy and verification during later testing. Oscillograph records and instrumentation details for each run were furnished to MITRE, and the taped data were digitized at WES to MITRE specifications. Delivery of the digitized tapes to MITRE was effected 19 January 1976.

# Static Load-Deflection Tests

In planning for the load-deflection tests, the method of attack had been to shift the north rail so that the 1-ton lead weights used for static loading could be stacked on the top surface of Beam 16. To shift the rail the desired amount (3 ft) at Beam 16 would have required releasing 700-1000 ft of rail from the fasteners; however, a powered nut remover which the AT&SF had intended to use for this purpose was inoperative on 7 November because replacement parts had not been

received. The time and cost-effective alternative under the circumstances was to cut and remove the north rail; accordingly, a 32-ft section of rail was cut free and lifted from Beams 15, 16, and 17 to facilitate loading and to permit installation of the necessary dial gages. The north rail was also loosened from its fasteners on Beams 12, 13, 14, 18, 19, and 20 so that the response of the beams in the test section would not be affected by load transfer to the rail.

Three load deflection tests were conducted between 10 and 12 November. Results of these tests are shown in Tables A-1-A-7 (deflection measurements made using dial gages) and Figures A-5-A-8 (strain gage data from Beam 16, north rail). The final test, i.e., the second loading on the west end of Beam 16, was omitted with the approval of Dr. James L. Milner of MITRE because highly consistent results had been obtained in the first three tests. As stated previously, strain gage response in the static tests was much more consistent than in the earlier dynamic tests. An additional longitudinal gage, which was installed on the east end of Beam 16 after the dynamic testing, yielded virtually the same response during the static tests as the longitudinal gage originally installed at that location. This suggests that the strain gages performed properly in both the static and dynamic testing, and that response in the dynamic tests was affected by uncontrolled variables, such as rail-fastener-beam-load transfer conditions, which were eliminated in the static tests.

Prior to testing, it was noted that the north rail beams in the test section were canted to the north field side of the track with a slope of about 1:30. This slope, resulting from rail traffic over the KTT, is opposite the 1:40 slope with which the beams were originally placed and indicates an appreciable rotation of the beams about their long axis. Measurements of long axis rotation during the load deflection tests were neither desired nor conducted; however, it is likely that some such rotation did occur.

#### Plate Bearing Tests

Preparations for performing plate bearing tests on the subgrade

beneath Beam 16 included removal of ballast to the depth of the bottom of the beam (18 in.), cutting the gage rods joining Beam 16 and its companion beam under the south rail, and cutting and removing Beam 16 together with 1-1/2 ft of each adjacent beam. The subgrade thus exposed consisted of a 3- to 4-in.-thick layer of ballast material embedded in moist to wet reddish brown clay. During excavation it was noted that the ballast around Beam 16 was fouled with clay to within 1 or 2 in. of its top surface. The surface of the subgrade material beneath north rail Beam 16 also exhibited a pronounced slope to the north field side of the track. No evidence of a lime stabilized layer, which had been placed as the top 6 in. of the embankment, was encountered.

A 40-ft-long flat bed trailer was next hoisted onto the track to span the gap left by removing the beam. This trailer was loaded with 1-ton lead pigs to react the force applied, by means of a hydraulic ram, to the 30-in.-diam plate used in testing the subgrade. Locations of the tests are shown in Figure A-9. The plate bearing tests were conducted in accordance with procedures contained in EM 1110-45-303, and results are shown in Figure A-10-A-12. This testing completed the Phase I KTT Postmortem field operations.

Static			Absolut	e Verti	cal Def	lection	, in.*			Relative	Vertical	Deflecti	on, in.*
Load	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial
<u>   1b    </u>	<u>No. 1</u>	<u>No. 2</u>	<u>No. 3</u>	<u>No. 4</u>	<u>No. 5</u>	<u>No6</u>	<u>No. 7</u>	<u>No. 8</u>	<u>No. 9</u>	<u>No. 10</u>	<u>No. 11</u>	<u>No. 12</u>	<u>No. 13</u>
0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0,0000	0.0000	0.0000	0.0000
4,070	·0.000	0.000	0.001	0.006	0.007	0.002	0.002	0.001	0.000	0.0000	0.0020	-0.0070	0.0000
8,140	0.000	0.001	0.002	0.013	0.014	0.005	0.003	0.001	0.000	0.0000	0.0020	-0.0070	0.0000
12,210	0.000	0.002	0.003	0.019	0.025	800.0	0.006	0.001	0.000	-0.0005	0.0070	-0.0180	-0.0001
16,280	0.000	0.002	0.004	0.026	0.033	0.010	0.007	0.001	0.000	-0.0010	0.0100	-0.0220	-0.0002
20,350	0.000	0.002	0.007	0.031	0.042	0.013	0.009	0.002	0.000	-0.0020	0.0115	-0.0290	-0.0002
24,420	0.000	0.002	0.008	0.037	0.049	0.015	0.010	0.002	0.000	-0.0025	0.0135	-0.0320	-0.0001
28,490	0.000	0.002	0.009	0.042	0.056	0.017	0.012	0.002	0.000	-0.0031	0.0143	-0.0375	0.0002
32,560	0.000	0.002	0.011	0.048	0.062	0.019	0.013	0.002	0.000	-0.0040	0.0155	-0.0400	0.0004
24,420	0.000	0.002	0.010	0.045	0.059	0.019	0.014	0.001	0.000	-0.0035	0.0153	-0.0380	0.0004
16,280	0.000	0.002	0.009	0.039	0.050	0.017	0.013	0.001	0.000	-0.0026	0.0145	-0.0320	0.0003
8,140	0.000	0.002	0.007	0.028	0:034	0.014	0.011	0.000	0.000	-0.0018	0.0115	-0.0240	0.0002
0	0.000	0.001	0.003	0.007	0.008	0.009	0.010	0.000	0.000	-0.0004	0.0041	-0.0030	0.0001

TABLE A-1. STATIC LOAD VERSUS VERTICAL DEFLECTION TEST RESULTS (KTT POSTMORTEM) TEST NO. 1 (CENTER LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4, 10 NOV 1975)

\* The dial numbers shown refer to locations depicted in Figures A-5-A-8.

Static			Absolut	e Verti	cal Def	lection	, in.*			Relative	Vertical	Deflecti	on, in.*
Load	Dial	Dial	Dial	Dial									
<u>    1b    </u>	<u>No. 1</u>	<u>No. 2</u>	<u>No. 3</u>	<u>No. 4</u>	<u>No. 5</u>	<u>No. 6</u>	<u>No. 7</u>	<u>No. 8</u>	<u>No. 9</u>	<u>No. 10</u>	<u>No. 11</u>	No. 12	<u>No. 13</u>
0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.0000	0.0000	0.0000	0.0000
4,070	0.000	0.000	0.000	0.006	0.008	0.002	0.002	0.000	0.000	0.0000	0.0020	-0.0080	0.0000
8,140	0.000	0.001	0.002	0.017	0.017	0.004	0,003	0.00.1	0.000	-0.0003	0.0060	-0.0135	-0.0005
12,210	0.000	0.002	0.003	0.023	0.019	0.006	0.005	0.002	0.000	-0.0006	0.0080	-0.0217	-0.0003
16,280	0.000	0.002	0.004	0.030	0.036	0.008	0.006	0.002	0.000	-0.0010	0.0107	-0.0256	-0.0003
20,350	0.000	0.002	0.006	0.035	0.045	0.010	0.008	0.002	0.000	-0.0014	0,0120	-0.0325	-0.0001
24,420	0.000	0.003	800.0	0.042	0.052	0.012	0.010	0.002	0.000	-0.0020	0.0127	-0.0355	0.0000
28,490	0.000	0.003	0.010	0.046	0.059	0.016	0.012	0.003	0000	-0.0030	0,0130	-0.0 <sup>1</sup> 103	0.0003
32,560	0.000	0.004	0.012	0.052	0.065	0.018	0.014	0.003	0.000	-0.0037	0.0135	-0.0420	0.0004
24,420	0.000	0.004	0.011	0.049	0.059	0.018	0.013	0.003	0.000	-0.0030	0.0133	-0.0400	0.0003
16,280	0.000	0.003	0.010	0.043	0.050	0.016	0.013	0.003	0.000	-0.0026	0.0130	-0.0360	0.0001
8,140	0.000	0.003	0.007	0.031	0.034	0.013	0.012	0.003	0.000	-0.0014	0.0100	-0.0265	0.0001
0	0:000	0.003	0,003.	0.008	0.006	0.008	0.009	0.002	0.000	-0.0003	0.0020	-0.0025	0.000
				•		-						• •	· .

c,

TABLE A-2. STATIC LOAD VERSUS VERTICAL DEFLECTION TEST RESULTS (KTT POSTMORTEM) TESTNO. 2 (CENTER LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4, 11 NOV 1975)

\* The dial numbers shown refer to locations depicted in Figures A-5-A-8.

NO. 3 (WEST END LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4, 12 NOV 1975)												
		Absolut	e Verti	cal Def	lection	., in.*			Relative	Vertical	Deflecti	on, in.*
Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial	Dial
<u>No. 1</u>	<u>No. 2</u>	<u>No. 3</u>	<u>No. 4</u>	<u>No. 5</u>	<u>No. 6</u>	<u>No. 7</u>	<u>No. 8</u>	<u>No. 9</u>	<u>No. 10</u>	<u>No. 11</u>	<u>No. 12</u>	<u>No. 13</u>
0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.0000	0.0000	0.0000	0.0000
0.000	0.000	0.001	0.003	0.009	0.002	0.002	0.000	0.000	0.0000	0.0002	-0.0157	-0.0010
0.000	0.000	0.001	0.009	0.019	0.004	0.003	0.001	0.000	-0.0002	0.0012	-0.0255	-0.0012
0.000	0.001	0.001	0.013	0.028	0.009	0.004	0.001	0.000	-0.0004	0.0017	-0.0370	-0.0012
0.000	0.001	0.002	0.019	0.038	0.012	0.006	0.002	0.001	-0.0008	0.0020	-0.0425	-0.0011
0.000	0.002	0.003	0.021	0.044	0.018	0.009	0.002	0.001	-0.0009	0.0021	-0.0482	-0.0008
0.000	0.002	0.003	0.026	0.052	0.023	0.012	0.002	0.001	-0.0011	0.0034	-0.0509	-0.0003
0.000	0.002	0.004	0.027	0.058	0.031	0.015	0.003	0.001	-0.0013	0.0035	-0.0535	0.0006
0.000	0.003	0.004	0.032	0.065	0.037	0.018	0.003	0.001	-0.0018	0.0046	-0.0546	0.0013
0.000	0.003	0.004	0.030	0.061	0.035	0.016	0.003	0.001	-0.0015	0.0040	-0.0543	0.0005
0.000	0.002	-0.004	0.026	0.053	0.028	0.013	0.003	0.001	-0.0011	0.0033	-0.0500	-0.0004
0.000	0.002	0.003	0.019	0.037	0.019	0.009	0.003	0.001	-0.0005	0.0022	-0.0360	-0.0011
0.000	0.001	0.002	0.013	0.025	0.015	0.007	0.002	0.001	0.0000	0.0002	-0.0265	-0.0001
0.000	0.001	0.001	0.006	0.008	0.010	0.003	0.002	0.000	0.0003	0.0002	-0.003	-0.0002
	Dial No. 1 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000	No. 3           Dial         Dial           No. 1         No. 2           0.000         0.000           0.000         0.000           0.000         0.000           0.000         0.000           0.000         0.000           0.000         0.001           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.003           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.002           0.000         0.001	Absolut           Dial         Dial         Dial           No. 1         No. 2         No. 3           0.000         0.000         0.000           0.000         0.000         0.000           0.000         0.000         0.001           0.000         0.000         0.001           0.000         0.001         0.001           0.000         0.001         0.002           0.000         0.002         0.003           0.000         0.002         0.004           0.000         0.002         0.004           0.000         0.002         0.004           0.000         0.002         0.004           0.000         0.002         0.003           0.000         0.002         0.004           0.000         0.002         0.003           0.000         0.002         0.003           0.000         0.001         0.002           0.000         0.001         0.002	Absolute Verti           Dial         Dial         Dial         Dial           No. 1         No. 2         No. 3         No. 4           0.000         0.000         0.000         0.000           0.000         0.000         0.000         0.000           0.000         0.000         0.001         0.003           0.000         0.001         0.009         0.009           0.000         0.001         0.001         0.009           0.000         0.001         0.001         0.013           0.000         0.001         0.002         0.019           0.000         0.002         0.003         0.026           0.000         0.002         0.004         0.027           0.000         0.002         0.004         0.032           0.000         0.002         0.004         0.026           0.000         0.002         0.004         0.026           0.000         0.002         0.003         0.019           0.000         0.002         0.003         0.019           0.000         0.001         0.002         0.013           0.000         0.001         0.002         0.013 <td>Absolute Vertical Def           Dial         Dial         Dial         Dial         Dial         Dial           No. 1         No. 2         No. 3         No. 4         No. 5           0.000         0.000         0.000         0.000         0.000           0.000         0.000         0.000         0.000         0.000           0.000         0.000         0.001         0.003         0.009           0.000         0.000         0.001         0.003         0.009           0.000         0.001         0.003         0.009         0.019           0.000         0.001         0.001         0.013         0.028           0.000         0.001         0.002         0.019         0.038           0.000         0.002         0.003         0.026         0.052           0.000         0.002         0.003         0.027         0.058           0.000         0.002         0.004         0.032         0.065           0.000         0.002         0.004         0.026         0.053           0.000         0.002         0.003         0.019         0.037           0.000         0.001         0.002         0.</td> <td>Absolute Vertical DeflectionDial Dial Dial Dial Dial Dial DialDialDialDialDialDialNo. 1No. 2No. 3No. 4No. 5No. 60.0000.0000.0000.0000.0000.0000.0000.0000.0010.0030.0090.0020.0000.0010.0010.0090.0190.0040.0000.0010.0010.0130.0280.0090.0000.0010.0020.0190.0380.0120.0000.0020.0030.0210.0440.0180.0000.0020.0030.0260.0520.0230.0000.0020.0040.0270.0580.0310.0000.0030.0040.0320.0650.0370.0000.0020.0040.0260.0530.0280.0000.0020.0030.0190.0370.0190.0000.0010.0020.0130.0250.0150.0000.0010.0020.0130.0250.015</td> <td>Absolute Vertical Deflection, in.*           Dial         Dial</td> <td>Absolute Vertical Deflection, in.*           Dial         Dial</td> <td><math display="block">\begin{array}{c ccccccccccccccccccccccccccccccccccc</math></td> <td>NO. 3 (WEST END LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4,           Absolute Vertical Deflection, in.*         Relative           Dial         Dial</td> <td>MO. 3 (WEST END LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4, 12 NOV 1           Absolute Vertical Deflection, in.*         Relative Vertical           Dial         Dial&lt;</td> <td>Absolute Vertical Deflection, in.*         Relative Vertical Deflection, in.*           Dial         Dial</td>	Absolute Vertical Def           Dial         Dial         Dial         Dial         Dial         Dial           No. 1         No. 2         No. 3         No. 4         No. 5           0.000         0.000         0.000         0.000         0.000           0.000         0.000         0.000         0.000         0.000           0.000         0.000         0.001         0.003         0.009           0.000         0.000         0.001         0.003         0.009           0.000         0.001         0.003         0.009         0.019           0.000         0.001         0.001         0.013         0.028           0.000         0.001         0.002         0.019         0.038           0.000         0.002         0.003         0.026         0.052           0.000         0.002         0.003         0.027         0.058           0.000         0.002         0.004         0.032         0.065           0.000         0.002         0.004         0.026         0.053           0.000         0.002         0.003         0.019         0.037           0.000         0.001         0.002         0.	Absolute Vertical DeflectionDial Dial Dial Dial Dial Dial DialDialDialDialDialDialNo. 1No. 2No. 3No. 4No. 5No. 60.0000.0000.0000.0000.0000.0000.0000.0000.0010.0030.0090.0020.0000.0010.0010.0090.0190.0040.0000.0010.0010.0130.0280.0090.0000.0010.0020.0190.0380.0120.0000.0020.0030.0210.0440.0180.0000.0020.0030.0260.0520.0230.0000.0020.0040.0270.0580.0310.0000.0030.0040.0320.0650.0370.0000.0020.0040.0260.0530.0280.0000.0020.0030.0190.0370.0190.0000.0010.0020.0130.0250.0150.0000.0010.0020.0130.0250.015	Absolute Vertical Deflection, in.*           Dial         Dial	Absolute Vertical Deflection, in.*           Dial         Dial	$\begin{array}{c ccccccccccccccccccccccccccccccccccc$	NO. 3 (WEST END LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4,           Absolute Vertical Deflection, in.*         Relative           Dial         Dial	MO. 3 (WEST END LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4, 12 NOV 1           Absolute Vertical Deflection, in.*         Relative Vertical           Dial         Dial<	Absolute Vertical Deflection, in.*         Relative Vertical Deflection, in.*           Dial         Dial

TABLE A-3. STATIC LOAD VERSUS VERTICAL DEFLECTION TEST RESULTS (KTT POSTMORTEM) TEST NO. 3 (WEST END LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4, 12 NOV 1975)

\* The dial numbers shown refer to locations depicted in Figures A-5-A-8.

.

TABLE A-4.	STATIC I	LOAD VERSUS	SURFACE S	TRAIN TEST	RESULTS (KTT
POSTMORTE	M) TEST N	NO. 1 (CENT	ER LOADING	, BEAM 16,	NORTH RAIL
	TRA	ACK SECTION	4, 10 NOV	1975)	

Static	Apj	parent Surf	ace Strai	n, µin./i	n. (2 Act	ive Gages	)*
Load	Gage						
<u> </u>	<u>No. 1</u>	<u>No. 2</u>	<u>No. 3</u>	<u>No. 4</u>	<u>No. 5</u>	<u>No. 6</u>	<u>No. 7</u>
<b>O</b> ,	0	0	0	0	0	0	0
4,070	-152	-120	-1	58	1	17	-6
8,140	-307	-262	3	42	-10	26	-286
12,210	-338	-311	15	40	-25	49	-313
16,280	-333	-316	23	21	-41	69	-327
20,350	-326	-325	35	-21	-63	96	-331
24,420	-331	-325	40	-58	-88	119	-337
28,490	-329	-332	40	-113	-133	133	-336
32,560	-329	-330	53	-159	-145	137	-336
24,420	-340	-345	38	-252	-124	121	-349
16,280	-341	-357	16	-339	-223	95	-380
8,140	-366	-369	-2		-234	94	-392
0	-378	-388	-39	-435	-265	98	-445

\* Divide apparent values by <u>two</u> to get actual surface strain. Gage numbers refer to locations shown in Figure A-4.

TABLE A-5. STATIC LOAD VERSUS SURFACE STRAIN TEST RESULTS (KTT POSTMORTEM) TEST NO. 2 (CENTER LOADING, BEAM 16, NORTH RAIL TRACK SECTION 4, 11 NOV 1975)

٤	Static			Appa	rent Surfa	ce Strai	n, µin./in	n. (2 Acti	ve Gages)	¥
,	Load		Gage	۳.	Gage	Gage	Gage	Gage	Gage	Gage
	<u></u>		<u>No. 1</u>	•	<u>No. 2</u>	<u>No. 3</u>	<u>No. 4</u>	<u>No. 5</u>	<u>No. 6</u>	<u>No. 7</u>
	• • • 0		. 0	٠,	0	0	0	0	0	0
	4,070	•	-165	۲	-80	0	35	<b>8</b> (c)	<b>3</b> . **	-125
. ,	8,140		-202	. <u>.</u>	-177	12	64	10	8	-149
	12,210	÷	-205		<b>-185</b> 👾 👉	21	70	7	15	-165
, •	16,280	ţ,	-203		-189	27	<b>79</b>	7	a <b>21</b> . (	-161
•	20,350		-201		-189	40	85	2	: 33 🗟	-163
	24,420		-202		-188	49	74	-11	46	-162
	28,490		-208	•	-192	50 <sup>°</sup>	62	-25	54	-173
	32,560		-214		-195	57	33	-40	52	-166
Ì,	24,420		-218		-200	45	10	-46	64	-182
	16,280	2	-218	-	-208	36	-29	-61	<b>58</b> • •	-190
γ,	8,140	• .	-217		-215	23	-65	-77	52 .	-209
•	· <b>O</b>		-190	63	-229	16	-142	-107	46	-194

\* Divide apparent values by two to get actual surface strain. Gage numbers refer to locations shown in Figure A-4.

TABLE A-6. STATIC LOAD VERSUS SURFACE STRAIN TEST RESULTS (KTT POSTMORTEM) TEST NO. 3 (WEST END LOADING, BEAM 16, NORTH RAIL, TRACK SECTION 4, 12 NOV 1975)

	· · · · · · · · · · · · · · · · · · ·					1 e	
Static	Apr	arent Surfa	ace Strain	, µin./	in. (2 Act	ive Gages)	*
Load	Gage	Gage	Gage	Gage	Gage	Gage	Gage
<u>    1b    </u>	No. 1	<u>No. 2</u>	<u>No. 3</u>	<u>No. 4</u>	<u>No. 5</u>	<u>No. 6</u>	<u>No. 7</u>
0	0	0	<b>O</b>	0	0	0	0
4,070	100	108	136	-43	-34	18	55
8,140	107	127	2	-42	-36	<b>8</b> '	100
12,210	119	155	-7:5	-37	-35	13	102
16,280	134	174	7	<b>-2</b> 5	-32	4. <b>)</b> <sub>1</sub>	112
20,350	126	177	10	-14	-28	7	107
24,420	140	193	41	7	-21	<b>-1</b>	· 80
28,490	-24	116	38 · "	17	-17	1, <b>1</b>	124
32,560	24	63	47	35	-15	-10	100
24,420	7	35	70	34	-13	9	-27
16,280	_44	10	38	30	-10	18	-59
8,140	-40	-9	30 -	23	-4	37	-70
4,070	-1	5	22	<b>19</b> "	-3	43	-87
0	-43	<b></b> _	45	28	37	31	-45

\* Divide apparent values by two to get actual surface strain. Gage numbers refer to locations shown in Figure A-4.

			Deflec	•	Elapsed	Date	
Location	Load	Dial	Dial	Dial		Time	of
No.	<u>psi</u>	<u>No. 1</u>	<u>No. 2</u>	<u>No. 3</u>	Average	min*	<u>Test</u>
1**	5	0.035	0.029	0.039	0.034	21	16 Nov
	10	0.051	0.053	0.061	0.055	15	
	15	0.060	0.081	0.087	0.079	15	• •
	20	0.098	0.119	0.124	0.1137	36	
	25	0.121	0.153	0.156	0.1433	30	
	30	0.138	0.193	0.189	0.1733	33	
	0	0.057	0.076	0.079	0.0706	27	
2**	5	0.024	0.009	0.017	0.0167	9	17 Nov
	10	0.046	0.033	0.037	0.0387	18	
	15	0.070	0.064	0.061	0.065	21	
	20	0.089	0.098	0.085	0.0906	18	к Ч
	25	0.109	0.139	0.110	0.119	21	
	30	0.130	0.193	0.143	0.155	30	
	0	0.046	0.049	0.045	0.0467	27	
3**	5	0.051	0.053	0.027	0.0437	15	17 Nov
	10	0.084	0.088	0.043	0.0717	12	
	15	0.116	0.122	0.066	0.101	21	
	20	0.145	0.156	0.083	0.128	21	
	25	0.175	0.184	0.103	0.154	18	
	30	0.210	0.219	0.127	0.185	30	
	<b>O</b> <sup>1</sup>	0.098	0.094	0.037	0.763	45	

TABLE A-7. 30-IN.-DIAM. PLATE BEARING TEST RESULTS (KTT POSTMORTEM) ON KTT SUBGRADE (NORTH RAIL, BEAM 16, TRACK SECTION 4)

\* Elapsed time between load application and dial indicator readings readings made when dial creep was less than 0.001 in. in a 3-min interval.

\*\* Test locations were as follows: Location No. 1 - West end of Beam 16 Location No. 2 - Center of Beam 16 Location No. 3 - East end of Beam 16



FIGURE A-1. TIME TABLE DEVELOPED FOR WES PHASE I FIELD OPERATIONS



SYMBOL











EAST

PROFILE VIEWED FROM NORTH FIELD SIDE

13



FIGURE A-3. DETAILS OF DIAL GAGE INSTALLATIONS



## LEGEND

SYMBOL

A-16

DESCRIPTION

NO. 1 LATERAL GAGE (2 ACTIVE, FULL BRIDGE) 4" GAGE LENGTH
NO. 2 LONG. GAGE (2 ACTIVE, FULL BRIDGE) 2" GAGE LENGTH
NO. 3 LONG. GAGE (2 ACTIVE, FULL BRIDGE) 2" GAGE LENGTH
NO. 4 LONG. GAGE (2 ACTIVE, FULL BRIDGE) 2" GAGE LENGTH
NO. 5 LATERAL GAGE (2 ACTIVE, FULL BRIDGE) 4" GAGE LENGTH
NO. 6 LONG. GAGE (2 ACTIVE, FULL BRIDGE) 2" GAGE LENGTH
NO. 7 LONG. GAGE (2 ACTIVE, FULL BRIDGE) 2" GAGE LENGTH

# PLAN VIEW BEAM 16

FIGURE A-4. STRAIN GAGE INSTRUMENTATION, BEAM 16, NORTH RAIL, TRACK SECTION 4

EAST



\* CONFIGURATION SHOWN IS FOR CENTER LOADING (TESTS NO. 1 AND 2) OF BEAM 16. DASHED ARROWS SHOW LOADING POINTS FOR WEIGHTS IN WEST END LOAD-DEFLECTION TEST (TEST NO. 3). IN EITHER CONFIGURATION, LOAD WAS CENTERED ON EXISTING FASTENER LOCATIONS AS SHOWN.

a. TYPICAL LOADING PROCEDURE





## b. DETAILS OF SUPPORT ARRANGEMENT

FIGURE A-5. LOADING CONFIGURATION FOR LOAD-DEFLECTION TESTS



FIGURE A-6. PLOTS OF LOAD VERSUS SURFACE STRAIN FROM LOAD-DEFLECTION TEST 1



FIGURE A-7. PLOTS OF LOAD VERSUS SURFACE STRAIN FROM LOAD-DEFLECTION TEST 2


FIGURE A-8. PLOTS OF LOAD VERSUS SURFACE STRAIN FROM LOAD-DEFLECTION TEST 3



FIGURE A-9. LOCATION OF 30-IN.-DIAM PLATE BEARING TEST ON SUBGRADE

and the second second

•



FIGURE A-10. PLATE BEARING TEST RESULTS, LOCATION 1 (WEST END BEAM 16)



-71 . 1 120

A-23



PLATE BEARING TEST RESULTS, LOCATION 3 (EAST END BEAM 16) FIGURE A-12.

A-24

#### APPENDIX B: VIBROSEISMIC STUDY

#### General

WES vibroseismic tests are used to determine the in situ elastic properties of foundation materials. In the KTT Postmortem Investigation, vibroseismic tests were conducted at 10 preselected locations on the KTT embankment; these locations were also used for studies of embankment strength and material properties. The vibroseismic field work was carried out, as part of the Phase II field operations, by a project engineer and technician in the period 5-15 May 1976.

### Test\_Plan

Vibroseismic tests were conducted for the following purposes:

- 1. To determine the variation of embankment elastic moduli with depth for the posttraffic (postmortem) test condition.
- For comparison with 1971 pretraffic vibroseismic test results in order to assess traffic induced changes in embankment strength.

Locations for the vibroseismic tests were selected to typify either "good" or "poor" performance, based on judgements of ATSF maintenance records for the KTT. WES judgements of performance from the ATSF maintenance records are described in Volume I of this report, but may be summarized as follows:

Track Section	Test Location (KTT Control Stations)	Performance
1	8524+75	Poor
2 (A) (B)	8531+60 8535+16 <b>*</b>	Poor Good
3 (A) (B)	8540 <b>+</b> 17 8542+49	Good Poor
4	8551+50	Poor

\* Denotes location of main (built in) KTT instrumentation array.

Track Section	Test Location (KTT Control Stations)	Performance
5.	8558 <b>+</b> 20	Poor
7	8576+41*	Poor
8	8587+10	Good
9	8595+37*	Good

\* Denotes location of main (built in) KTT instrumentation array.

## Field Testing

The vibroseismic tests at each location were carried out in two steps. First, the compression wave velocity in each subsurface layer and the depth to interfaces between layers were determined using refraction seismic techniques. A 16-1b sledge hammer provided the seismic energy source and compression wave arrivals at scaled distances from the source were recorded using a 12-channel seismograph. Seismic waves were generated by striking the sledge hammer on a thick steel disk. Compression wave arrivals were detected with vertical seismic geophones, which were spaced at 2-ft intervals along a line following the north or south rail of the KTT track structures. The track structures had, of course, been removed prior to testing. The ballast was also removed so that the geophones could be placed on the top surface of the embankment. The sledge hammer was struck at either end of the geophone spread so as to obtain both forward and reverse traverses on the subsurface materi-The wave travel times and distances to each detector were used to als. construct the time-distance plots shown in Figures B-1-B-10. The slope of the line in these plots gives the apparent compression wave velocity of the subsurface material. A change in slope of the line indicates the presence of a subsurface layer with different seismic properties from the overlying material. For a two-layer system, the depth to the interface between layers may be calculated from the following equation:

$$D_{1} = \frac{X_{1}}{2} \sqrt{\frac{V_{2} - V_{1}}{V_{2} + V_{1}}}$$
(B-1)

where

 $D_1 = depth$  from surface to first interface  $X_1 = distance$  from source to change in slope  $V_1 = compression$  wave velocity in upper layer  $V_2 = compression$  wave velocity in lower layer

Since dipping layers will cause different apparent velocities to be recorded for the same material, forward and reverse traverses are used to determine the true compression wave velocity in a layer. The true velocity is obtained using the following equation:

$$r = \frac{2V_u V_d}{V_u / V_d}$$
(B-2)

where

 $V_{T}$  = true compression wave velocity,  $LT^{-1}$  $V_{u}$  = apparent velocity updip,  $LT^{-1}$  $V_{d}$  = apparent velocity downdip,  $LT^{-1}$ 

The second phase of the vibroseismic investigation is a vibratory test, which is conducted at the same location as the refraction seismic survey. A 25-lb force output electromagnetic vibrator was used for vibration testing at the KTT, and surface waves were detected using the 12-channel seismograph equipment previously described. A typical test setup is shown in Figure B-ll. This vibrator and associated instrumentation is described in detail in WES Miscellaneous Paper (MP) 4-691, entitled <u>Determination of Soil Shear Moduli at Depths by In Situ Vibra-</u> tory Techniques, Dec 1964, and in <u>A Procedure for Determining Elastic</u> <u>Moduli of In Situ Soils by Dynamic Techniques</u>, an excerpt from the 1967 Proceedings of the International Symposium on Wave Propagation and Dynamic Properties of Earth Material.

The vibratory test consists of determining the wavelength of surface (Rayleigh) waves generated by a vibrator operating at a discrete frequency. A number of different frequencies are used to cover the frequency domain of interest, and wave velocity is computed from the following equation:

 $V = \lambda f$ 

where

 $V = wave velocity, LT^{-1}$ 

 $\lambda$  = wave length, L

 $f = frequency of vibration, T^{-1}$ 

An example plot of this type is shown in Figure B-12.

## Computation of Poisson's Ratio and Elastic Moduli

Shear wave velocity and Rayleigh wave velocity are related by Poisson's ratio. For homogenous materials, having Poisson's ratios in the range from 0.20 to 0.50, the difference between shear and Rayleigh wave velocities is less than 9 percent. For practical purposes, shear and Rayleigh waves may be taken to have the same velocity. The wave velocities measured in the vibratory test may therefore be used to compute shear moduli from

$$G = \rho V_g^2$$

where

 $G = shear modulus of soil, FL^{-1}$ 

V = shear wave velocity, LT

 $\rho$  = mass density of soil,  $\gamma w/g$ ,  $GL^{-4}T^2$ 

 $\gamma_w$  = wet unit weight of soil, FL<sup>-3</sup>

 $g = acceleration due to gravity, LT^2$ 

Assuming that shear and compression wave velocities were determined for the same material, Poisson's ratio can be determined using the velocity ratio

$$V_r = \frac{V_c}{V_s}$$

(B-5)

(B-4)

(B-3)

where

 $V_r = velocity ratio$ 

 $V_c$  = compression wave velocity, LT<sup>-1</sup>  $V_c$  = shear wave velocity, LT<sup>-1</sup>

Poisson's ratio  $\nu$  is calculated from elastic theory using the relationship

$$v = \frac{v_r^2 - 2}{2(v_r^2 - 1)}$$
(B-6)

Young's E modulus is similarly derived from the equation

$$E = 2G(1 + v)$$
 (B-7)

WES experience indicates that shear wave velocity and E and G moduli derived in this way correlate well with results of conventional exploration methods if the derived values are assigned to a depth equal to one-half the surface wave length measured in the vibratory tests. Results presented herein conform with the above practice and are summarized in Table B-1. Plots of shear wave velocity versus depth in the embankment for each test location are shown in Figures B-13-B-22. Corresponding plots of E and G moduli with depth are shown in Figures B-23-B-32. A summary plot showing the average variation in E and G moduli with depth is shown in Figure B-33. These moduli should be considered as upper bound values since they were derived from tests conducted at very low stress levels.

Wet Unit	P-Wave			Wave	<u></u>	R-Wave Velocity	Poission	Modulus	s, 10 <sup>3</sup> psi
Ym <sup>2</sup> pcf V fps	Depth <u>d, ft</u>	Frequency f, Hz	Length De $\lambda$ , ft d.	Depth d, ft	V, fps	Ratio Y	Shear <u> </u>	Young's E	
			à.	Test Sec	tion 1	•		a.	·
107	1075	0+	400 350 300 250 200 150	0.70 0.80 1.00 1.60 1.90 3.20	0.35 0.40 0.50 0.80 1.00 1.60	265 280 310 400 390 480	0.47 0.46 0.45 0.42 0.42 0.38	1.6 1.8 2.2 3.7 3.5 5.3	4.70 5.30 6.40 10.50 9.90 14.60
150	, * *		100 80 70 50	6.70 8.110 8.60 11.50	3.40 4.20 4.30 5.80	670 670 600 580	0.18 0.18 0.27 0.29	11.6 11.6 9.3 8.7	27.90 27.90 23.30 22.50
	-		n	Cest Sect	ion 2A				9 2
107	1075	0+	250 200 150	2.00 2.60 3.80	1.00 1.30 1.90	510 520 570	0.36 0.35 0.31	6.0 6.2 7.5	16.30 16.70 19.70
120			100 80 70 50 45 40	6.00 6.30 7.60 10.00 14.50 18.80	3.00 3.20 3.80 5.00 7.30 9.40	600 505 530 500 655 750	0.28 0.36 0.34 0.37 0.23 0.04	9.3 6.6 7.3 6.5 11.1 14.6	23.80 18.00 19.60 17.80 27.30 30.40

# TABLE B-1. RESULTS OF VIBROSEISMIC SURVEY

(Continued)

. .

(Sheet 1 of 5)

в-6

Wet Unit Weight Ym <sup>2</sup> pcf	P-Wave Velocity V <sub>c</sub> fps	Depth d, ft	Frequency f, Hz	Wave Length λ, ft	Depth d, ft	R-Wave Velocity V <sub>s</sub> , fps	Poission Ratio Y	Modulus Shear G	, 10 <sup>3</sup> psi Young's E
	·····		1	est Sect	ion 2B		·		
107	1090	0+	300 250 200	1.70 2.10	0.85	510 520	0.36 0.35 0.35	6.0 6.2	16.30 16.70
			150 100	4.30 5.40	2.10	640 540	0.24 0.34	10.6 7.6	26.30 20.40
· .	•	•	80 70 50	8.30 8.30 10.80	3.10 4.10 5.40	580 580 510	0.39 0.30 0.34	8.7 7.6	20°10 55°60
			<u>1</u>	est Sect	ion 3A		· · ·		• • • •
107	1150	0+	300 250	1.70 1.90	0.87 0.94	520 470	0.37 0.40	6.2 5.1	17.00 14.30
120			200 150 100 80 70	2.60 3.70 5.70 6.00 7.60	1.30 1.80 2.80 3.00 3.80	510 550 570 480 530	0.38 0.35 0.34 0.39 0.37	6.7 7.8 8.4 6.0 7.3	18.50 21.10 22.50 16.70 20.00
· · · ·	•		50 	12.80 Sest Sect	6.40 ion 3B	640	0,28	10.6	27.10
107	1150	0+	300 250	2.00 2.20	1.00 1.10	610 550	0.30 0.35	8.6 7.0	22.40 18.90

TABLE B-1 (Continued)

(Continued)

(Sheet 2 of 5)

Wet Unit Weight $\gamma_m^2$ per	P-Wave Velocity V <sub>c</sub> fps	Depth d, ft	Frequency f, Hz	Wave Length $\lambda$ , ft	Depth d, ft	R-Wave Velocity V <sub>s</sub> , fps	Poission Ratic Y	<u>Mođulu</u> Shear G	<u>3, 10<sup>3</sup> psi</u> Young's E
			<u>Test</u> S	ection 31	B (Conti	nued)	· · ·		
120		· · ·	200 150 100 80 70 50 40	2.50 3.40 5.00 5.50 7.00 12.20 12.50	1.30 1.70 2.50 2.80 3.50 6.10 6.30	500 510 500 440 490 620 500	0.38 0.38 0.38 0.41 0.39 0.26 0.38	6.5 6.7 6.5 5.0 6.2 10.0 6.5	17.90 18.50 17.90 14.10 17.20 25.80 17.90
				Test Sec	tion 4		2		
107	1040	0+	400 350 300 250	1.10 1.20 1.30 1.50	0.55 0.56 0.63 0.73	450 400 375 365	0.38 0.41 0.43 0.43	4.7 3.7 3.2 3.1	13.00 10.40 9.20 8.90
•	-		200 150	1.90 2.40	0.93	375 360 270	0.43 0.43	3.2 3.0	9.20 8.60 9.20
1.20			80 70	5.50 6.30	2.80	4)10 440	0.39 0.39	5.0 5.0	13.90 13.90

TABLE B-1 (Continued)

(Sheet 3 of 5)

в-8

Wet Unit Weight $\gamma_m^2$ pcf	P-Wave Velocity V <sub>c</sub> , fps	Depth d, ft	Frequency _f, Hz	Wave Length $\lambda$ , ft	Depth d, ft	R-Wave Velocity V <sub>s</sub> , fps	Poission Ratio Y	Modulu Shear G	s,10 <sup>3</sup> psi Young's E
			· <u>1</u>	lest Sect	ion 5				
107	1075 4750	0-5.1 5.1+	400 350 300 250 200 150 100	0.85 0.97 1.10 1.30 1.60 2.00 3.20	0.40 0.50 0.60 0.70 0.80 1.00 1.60	340 340 325 315 300 320	0.45 0.45 0.45 0.45 0.45 0.45 0.46 0.45	2.7 2.7 2.4 2.3 2.1 2.4	7.80 7.80 7.80 7.00 6.80 6.10 7.00
120		_	80 70 50 40 35	4.40 4.70 6.80 11.80 17.10	2.20 2.40 3.40 5.40 8.60	350 330 340 470 600	0.44 0.45 0.44 0.50 0.48	3.2 2.8 3.0 5.7 9.3	9.20 8.10 8.60 17.10 27.50
			Ţ	est Sect	ion 7				,
107	1100 1955	0-4.4 4.4+	400 350 300 250 200	1.10 1.50 1.80 2.00 2.50	0.60 0.80 0.90 1.00 1.30	440 525 540 500 510	0.40 0.35 0.34 0.37 0.36	4.5 6.3 6.7 5.8 5.9	12.60 17.00 18.00 15.90 16.10
120			150 100 80 70 50 10	3.40 6.00 5.90 7.40 11.60 13.50	1.70 3.00 3.00 3.70 5.80 6.80	510 600 հ75 515 580 5հ0	0.36 0.29 0.39 0.36 0.45 0.46	6.7 9.3 5.8 6.8 8.7 7.6	18.20 24.00 16.10 18.50 25.20 22.20
			35	17.00 (Continu	8.50 ed)	595	0.44	9.2	20.50

•

TABLE B-1 (Continued)

(Sheet 4 of 5)

в-9

.

Wet Unit Weight Ym <sup>2</sup> pcf	P-Wave Velocity V <sub>c</sub> , fps	Depth d, ft	Frequency f, Hz	Length $\lambda$ , ft	Depth d, ft	R-Wave Velocity V <sub>g</sub> , fps	Poission Ratio	Modulus Shear G	s, 10 <sup>3</sup> psi Young's E
	· · ·			Test Sec	tion 8				
107	1100 1740	0-2.8 2.8+	300 250 200	1.40 1.80 2.60	0.70 0.90 1.30	410 450 520	0.42 0.40 0.36	3.9 4.7 6.2	11.10 13.20 16.90
120			150 100 80 70 50 40 35	3.50 5.60 7.50 8.00 12.50 18.30 26.00	1.70 2.80 3.70 4.00 6.30 9.20 13.00	520 560 600 560 630 730 910	0.36 0.44 0.43 0.44 0.42 0.39 0.31	7.0 8.1 9.3 8.1 10.3 13.8 21.4	19.00 23.30 26.60 23.30 29.30 38.40 56.10
				Test Sec	tion 9				
107	1140 1710	0+2.4 +2.4	1400 350 300 250 200	1.00 1.40 1.60 2.10 2.50	0.50 0.60 0.80 1.00 1.30	380 400 480 520 500	0.44 0.43 0.39 0.37 0.38	3.3 3.7 5.3 6.2 5.8	8.80 10.60 14.70 17.00 16.00
120			150 100 80 70 50 40 35	3.60 5.70 7.00 8.40 13.20 22.50 28.00	1.80 2.80 3.50 4.20 6.60 11.30 14.00	540 565 560 590 660 900 995	0.36 0.44 0.44 0.43 0.41 0.31 0.24	7.5 8.3 8.1 9.0 11.3 21.0 25.6	20.40 23.90 23.30 25.70 31.90 55.00 63.50

TABLE B-1 (Concluded)

.

(Sheet 5 of 5)

.







TEST RESULTS, TRACK SECTION 2, STA 8531+62.5 (TEST LOCATION 2A, KTT EMBANKMENT)



FIGURE B-3. POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 2, STA 8535+15 (TEST LOCATION 2B, KTT EMBANKMENT)



FIGURE B-4. POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 3, STA 8540+19 (TEST LOCATION 3A, KTT EMBANKMENT)



FIGURE B-6. POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 4, STA 8547+79 (KTT EMBANKMENT)



FIGURE B-7. POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 5, STA 8558+30 (KTT EMBANKMENT)



TEST RESULTS, TRACK SECTION 7, STA 8576+42 (KTT EMBANKMENT)



FIGURE B-9. POSTTRAFFIC REFRACTION SEISMIC TEST RESULTS, TRACK SECTION 8, STA 8587+00 (KTT EMBANKMENT)



TEST RESULTS, TRACK SECTION 9, STA 8595+33 (KTT EMBANKMENT)



FIGURE B-11. TYPICAL VIBROSEISMIC TEST CONFIGURATION



FIGURE B-12. TYPICAL VELOCITY DETERMINATIONS FROM VIBRATION TEST, POSTTRAFFIC, TRACK SEC-TION 3, STA 8540+09 (TEST LOCATION 3A, KTT EMBANKMENT)



FIGURE B-13. POSTTRAFFIC SHEAR-WAVE VELOCITY RESULTS, TRACK SECTION 1, STA 8524+75 (KTT EMBANKMENT)



، ، میں بین میں



ITY RESULTS, TRACK SECTION 3, STA 8542+05 (TEST LOCATION 3B, KTT EMBANKMENT)



FIGURE B-18. POSTTRAFFIC SHEAR-WAVE VELOC-ITY RESULTS, TRACK SECTION 4, STA 8547+79 (KTT EMBANKMENT)



FIGURE B-19. POSTTRAFFIC SHEAR-WAVE VELOC-ITY RESULTS, TRACK SECTION 5, STA 8558+30 (KTT EMBANKMENT)



FIGURE B-20. POSTTRAFFIC SHEAR-WAVE VELOC-ITY RESULTS, TRACK SECTION 7, STA 8576+42 (KTT EMBANKMENT)



ITY RESULTS, TRACK SECTION 8, STA 8587+00 (KTT EMBANKMENT)





FIGURE B-23. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 1, STA 8524+75 (KTT EMBANKMENT)



FIGURE B-24. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 2, STA 8531+62.5 (TEST LOCATION 2A, KTT EMBANKMENT)



FIGURE B-25. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 2, STA 8535+15 (TEST LOCA-TION 2B, KTT EMBANKMENT)



FIGURE B-26. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 3, STA 8540+19 (TEST LOCA-TION 3A, KTT EMBANKMENT)



FIGURE B-27. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 3, STA 8542+50 (TEST LOCA-TION 3B, KTT EMBANKMENT)



FIGURE B-28. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 4, STA 8547+79 (KTT EMBANKMENT)



FIGURE B-29. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 5, STA 8558+30 (KTT EMBANKMENT) .

•

-



FIGURE B-30. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 7, STA 8576+42 (KTT EMBANKMENT)



ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 8, STA 8587+00 (KTT EMBANKMENT)

. . .

. . 2\* { } .


FIGURE B-32. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTION 9, STA 8595+33 (KTT EMBANKMENT)

в-28



FIGURE B-33. POSTTRAFFIC PLOTS OF ELASTIC MODULI VERSUS DEPTH, TRACK SECTIONS 1 THROUGH 9 (KTT EMBANKMENT)

## APPENDIX C: DUTCH CONE PENETROMETER TESTS

General

The Dutch cone penetrometer provides a measure of foundation strength in terms of penetration resistance versus depth. For purposes of the KTT Postmortem Investigation, a total of 97 subgrade soundings were made at intervals along the length of the KTT embankment. This work was accomplished in the period 5-13 May 1976.

## Test Plan

Measurements of penetration resistance in the embankment were made . for the following purposes:

- 1. To provide an index of embankment uniformity throughout its length.
- 2. To determine whether soil conditions, measured in terms of penetration resistance, would reflect the variations in strength believed to exist beneath the track structures.

In order to assess embankment uniformity, soundings were made at intervals of approximately 200 ft throughout the length of the KTT. At each test location, two or three soundings were made in a pattern selected to typify soil conditions in highly stressed, moderately stressed, and/or relatively unstressed areas of the subgrade beneath each track structure. For example, the subgrade beneath the rail seats of crossties or control joints of beam and slab structures would be subjected to higher traffic induced stresses than other areas of the foundation.

Field Testing

A standard friction jacket Dutch cone, whose penetrating action is shown in Figure C-1, was used throughout. This cone permits readings of both point and friction jacket resistances for each penetration drive

increment. Both point, and friction resistances were recorded, but only point resistance data will be presented. The skid-mounted, portable Dutch cone penetrometer used in the KTT work is shown in Figure C-2. The thrust to push the cone is provided by a hydraulic ram which is powered by a gasoline engine driven hydraulic pump. The engine, pump, and ram are skid mounted in one unit. The ram is fitted with a drivehead, which contains force measurement gages. Operation of the cone is controlled using an inner rod and outer casing system. Both the inner rods and outer casings are in 1-m lengths. The inner rods transfer force to the cone point, which after 1.5 in. of travel engages the friction sleeve. The sleeve and point move together for a further 1.5 in. of travel, at which time the drive is complete. The cone and conesleeve travel is continuous at a rate of 2 cm/sec. The outer casing is used to telescope the cone and sleeve, which are then advanced to the next test depth. This unit was designed to be used with soil anchors, which react the uplift forces generated during sounding. This configuration was not suitable for purposes of the KTT investigation, which involved relatively shallow, but numerous, penetrations. Instead, the skid unit was adapted to a platform which included two 2000-1b lead weights, intended to function as reaction masses during penetration. A forklift was used to transport the apparatus to each test location in the conventional (tie) track sections as shown in Figure C-3. A crane was used to position the penetrometer in the nonconventional track sections (the rail fastener studs projecting from the structures in Track Sections 4, 5, and 7 interfered with the forklift).

At each test location the ballast material was first removed by a tractor-mounted backhoe. The Dutch cone apparatus was next positioned over the desired location, and readings of penetration resistance were made at 6-in. intervals from the ballast-subgrade interface to 6 ft in depth. Measurements of penetration resistance were made electronically rather than by reading the force gages supplied with the penetrometer. The force required to push the cone was measured with a calibrated force transducer which was mounted in the penetrometer drivehead. Vertical displacement of the cone was measured with a linear potentiometer,

C-2-

which was attached to the drivehead and referenced to the frame of the apparatus. Both force and displacement were recorded on an X-Y plotter.

## Data Reduction

The average drive force, in pounds, required to push the cone 1.5 in. at each penetration depth was picked from the X-Y plot. This force was divided by the projected cross-sectional area of the cone, and the result, in pounds per square inch, was converted to tons per square foot. Figures C-4-C-41 present results of the penetrometer soundings in plots of penetration resistance versus depth in the embankment. Sounding locations are given in terms of both track section and KTT survey station.



CONE & JACKET BOTH ADVANCE FOR CONE BEARING PLUS LOCAL FRICTION

FIGURE C-1. ACTION OF FRICTION JACKET CONE



FIGURE C-2. PORTABLE DUTCH CONE PENETROMETER



FIGURE C-3. MODIFIED DUTCH CONE PENETROMETER AT TEST LOCATION IN TRACK SECTION 3



FIGURE C-4. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 1, STA 8521+01

€A£ O UNDER NORTH RAIL, MIDWAY BETWEEN TIES.  $\Delta$  under north rail, under tie. UNDER TIE, AT TRACK CENTERLINE. 3. DEPTH, FT 









FIGURE C-7. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 1, STA 8527+00





CONE RESISTANCE, TSF









CONE RESISTANCE, TSF O UNDER NORTH RAIL, MIDWAY BETWEEN TIES.  $\Delta$  UNDER NORTH RAIL, UNDER TIE. U UNDER TIE, AT TRACK CENTERLINE. 口の仏 DEPTH, FT Δ 5. 







FIGURE C-13. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8540+00







FIGURE C-15. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 3, STA 8544+00



FIGURE C-16. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 4, STA 8546+45 AND 8546+50





















FIGURE C-22. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUB-GRADE, TRACK SECTION 5, STA 8555+95 AND 8556+00



104.7

152.1





AND 8558+30



FIGURE C-25. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8559+95 AND 8560+00



FIGURE C-26. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 5, STA 8561+95 AND 8562+00



FIGURE C-27. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8570+95 AND 8571+00



FIGURE C-28. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8573+00 AND 8573+05









FIGURE C-31. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8576+10 AND 8576+15, SOUTH BEAM


FIGURE C-32. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 7, STA 8578+00 AND 8578+05









FIGURE C-34. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8583+00



FIGURE C-35. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8585+00





C-39



FIGURE C-37. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 8, STA 8588+00.5



FIGURE C-38. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8591+01



1

~FIGURE C-39. DUTCH CONE PENETROMETER DRIVE POINT RESISTANCE VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8593+00



VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8594+82.7



VERSUS DEPTH IN THE SUBGRADE, TRACK SECTION 9, STA 8596+31

1. 1. 1

· \*.

۰.

.

#### APPENDIX D: TRENCHING, SAMPLING, AND SOIL TESTING

#### General

During the period 19 April - 21 May 1976, a field party from the Pavement Investigations Division, Soils and Pavements Laboratory (now designated Geotechnical Laboratory) performed in situ soil tests and collected samples for the posttraffic investigation of the Kansas Test Track.

#### Test Plan

The investigation consisted of visual observations of ballast, drainage, settlement, cracking, and overall conditions of each test item. These conditions were also documented using color photographs. Test trenches, approximately 4 ft wide and 8 ft long were excavated in each track section with the exception of Track Section 6. In-place testing in each trench consisted of at least one 30-in.-diam plate bearing test on the ballast just beneath the structure (tie, slab, or beam). Water contents, densities, and California Bearing Ratio (CBR) tests were also conducted on the subgrade to a depth of 3 ft measured from the top of the subgrade. Disturbed samples were taken in each test pit for laboratory classification tests and compaction tests. Two undisturbed samples were taken in each trench. One was taken between the surface and 12 in., and the other was between 12- and 24-in. depth. Laboratory triaxial and unconfined compression tests were conducted on the undisturbed samples.

#### Field Testing

#### Location and depth control

A thorough study was made of the maintenance records kept by the Santa Fe Railroad during the traffic tests. Sites were selected in areas of high maintenance to determine causes of failure. The location of the approximate center of each trench with the tie, beam, or slab numbers is given in Table D-1.

Prior to the field testing at the KTT, all rails and fasteners had been removed. Therefore, elevations were taken on the top of each structure in the center of the north and south rails. This is not consistant with the elevations taken during traffic testing since they referenced the base of the rail. Cross sections and profiles along each rail were taken on the top of the subgrade after the ballast had been removed. These cross sections and profiles are shown in Figures D-1 to D-9. All depths of soil tests were referenced to the top of the subgrade during this testing and in this report.

#### Plate bearing tests

Thirty-inch-diameter plate bearing tests were conducted in each track section with the exception of Track Section 6. These tests were conducted in accordance with ASTM Dl196-64. Tests were conducted on the ballast beneath the tie, beam, or slab structure. The track structure was removed and ballast cleared to the level of the bottom of the structure and wide enough for the plate (Figure D-10). Sand was used to obtain a level seat for the plate. A typical load-deflection plot is shown in Figure D-11. Plate bearing test results are given in Table D-2.

#### Pit excavation

After completion of plate bearing tests, samples of ballast were taken. The locations of these samples for each type track section is shown on Figures D-12 through D-14. The upper portion of ballast was then removed with a back hoe. The final cover was excavated by hand so that the subgrade surface would not be disturbed. Cross sections of the subgrade surface and profiles along the rails were taken at each pit location on the ballast-subgrade interface. These measurements are shown in Figures D-1 through D-9. Note the undulations beneath the ties on Tie Sections 1, 2A, 2B, 3B, and 8. This was not evident on Track Section 9. Also, a profile was taken on the shoulder of most track sections. Note the effects of loading by comparing the shoulder profile with the rail profile. Figures D-15 and D-16

Ð-2

illustrate the undulations on Track Sections 1 and 2A. Figure D-17 illustrates the deformation in the tie area on Track Section 2B. California Bearing Ratio tests

California Bearing Ratio (CBR) tests were conducted in accordance with MIL-STD-621A, Method 101. CBR is a measure of the soil resistance to penetration of a 3-sq-in. piston expressed as a percent of a standard. The standard is 1000 psi at 0.1-in. penetration of 1,500 psi at 0.2-in. penetration. CBR tests were used to determine the relative soil strengths throughout the KTT. Tests were taken under ties, between ties, and under the north and south rails on the sections. In beam and slab sections they were conducted under joints, under the north and south rails, and between the rails. Locations are shown in Figures D-14, D-18, and D-19. A typical test setup is shown in Figure D-20. CBR data for each test pit is shown in Tables D-3 through D-12. Moisture and density tests

At each CBR test location, moisture content and dry density tests were conducted. Original plans included use of a nuclear moisture density testing apparatus. This method was abandoned because of the influence of the walls of the test trench on the readings. Density tests were conducted using drive cylinders of known volume. Moisture content was determined by sampling and oven drying overnight. Results of moisture and density tests are also shown in Table D-3 through D-12. 13

 $\mathcal{S}$ 

### Laboratory Testing

#### Ballast

Laboratory tests on ballast consisted of sieve analysis on all camples collected in Track Sections 1, 4, and 9. If there were enough fines (passing the 200 sieve) in these samples, Atterberg limits were conducted. After this testing was accomplished and the data analyzed, sieve analyses were conducted on selected samples from all other track sections. A total of 56 sieve analyses were conducted on ballast samples from the KTT. Atterberg limits tests were performed on fines obtained from these samples. Two samples were tested from the adjacent

D-3

main line of the AT&SF Railroad. Results of these tests are shown in Table D-13.

## Subgrade

Two undisturbed and two disturbed samples were taken from each test pit. Locations of these samples are shown in Figures D-12 through D-14. Laboratory tests on the disturbed samples consisted of Atterberg limits and sieve analyses. These tests were conducted for classification purposes. The results are given in Table D-14. Compaction tests were also conducted on the disturbed samples from Track Sections 1, 4, and 9. Samples were molded using the modified American Association of State Highway Officials (AASHO) effort. CBR's were conducted on the samples as molded. They were then remolded and soaked for 96 hours. CBR's were conducted on the soaked specimens. Results of these tests are shown in Figures D-21 to D-23. Note the almost total loss of strength under the soaked conditions.

Laboratory tests on undisturbed samples consisted of unconsolidated, undrained (Q) triaxial tests on samples from Track Sections 1, 4, and 9. Q test results are an average of at least three tests at confining pressures of 0.3, 0.5, and 0.8 tsf. Results of these tests are shown in Figures D-24 and D-25. Unconfined compression tests were conducted on all undisturbed samples. A minimum of two tests were run on each of the two samples taken from each pit. Results of these tests are presented in Figures D-26 through D-30.

**D-**4

Track Section	Test Pit No.	Station of the Approximate Center Line	Tie, Beam or Slab No.
l	:1 .	8524+75	208,209,210
2 .	2A	8531+60	115,116,117
2	2B	8535+16	276,277,278
3	3A	8540+17	160,161,162
3	3B	8542+49	275,276,277
<u>)</u>	<u>4</u>	8551+50	53,54
5	5	8558+20	120,121
7	7	8576+41	62,63
8	8	8587+10	261,262,263
9	9	8595+37	10,11,12
x.	, <u>.</u>		

.

2

TABLE D-1. LOCATIONS OF EACH TEST TRENCH

	TABLE	D <b>-</b> 2.	PLATE	BEARING	TEST	RESULTS
--	-------	---------------	-------	---------	------	---------

	······································	 1 <sub>7</sub> *	
Section	Location	psi	• • •
l	Sta 8524+75 (south rail)	380	, ,
2A	Sta 8531+62 (south rail)	303	
2B	Sta 8535+16 (north rail)	317	
3A	Sta 8542+49 (south rail)	229	
3B	Sta 8540+20 (north rail)	294	• •
4	Sta 8551+50 (north rail)	217	
5	Sta 8558+20 (centér)	88	
5	Sta 8558+10 (center)	232	· :
5	Sta 8562+05 (center)	317	
7	Sta 8576+41 (south rail)	338	
8	Sta 8587+08 (north rail)	261	
9	Sta 8595+33 (north rail)	203	-

\* k = slope of average pressures versus deflection curve during loading.

	Depth				CBR Da	ta	
Material	or Elev	Location		CBR	WC	DW	Remarks
Lime Stab Lean Cl	Surface	Under Tie 210	AVG	3.3 33.0 30.0 22.1	29.9 30.9 39.1 33.3	89.3* 85.4* 82.5* 85.7	N - lime stab layer not present M - lime stab layer approx 2" thick S - lime stab layer approx 2" thick
Hvy Cl	6"		AVG	7.7 6.8 5.0 6.5	29.8 27.1 29.0 28.6	92.2 93.4 93.4 93.0	N M S
	12"		AVG	7.3 7.9 6.7 7.3	27.1 27.6 28.1 27.6	92.1 91.5 89.1 90.9	N M S
	24"		AVG	10.0 6.8 12.0 9.6	26.5 26.1 26.0 26.2	93.0 93.6 92.1 92.9	N. M. S
Hvy Cl	36"	Under Tie 210	AVG	10.0 13.0 12.0 11.7	26.5 25.6 28.0 26.7	91.7 90.9 88.9 90.5	N M S
Lime Stab Lean Cl	Surface	Between Ties 209-210	AVG	7.0 39.0 48.0 31.3	29.0 28.5 36.1 31.2	90.9* 86.2* 84.3* 87.1	N - lime stab layer not present M - lime stab layer approx 3" thick S - lime stab layer approx 3" thick
Hvy Cl	6"	Between Ties 209-210	AVG	6.6 4.5 4.0 5.0			*
				(C)	ontinue	a)	

×. .

....

## TABLE D-3. KANSAS TEST TRACK TEST PIT 1

,

D-7

(Sheet 1 of 3)

•

Che	Depth	. <u> </u>	CBR Data				
Material	or Elev	Location		CBR	WC	DW	Remarks
Hvy Cl	12"	Between Ties 209-210	AVG	6.5 6.8 5 <b>.2</b> 6.2	27.6 28.6 27.9 28.0	91.2 89.0 89.4 89.9	N M S
SF .	24"		AVG	8.1 6.8 9.0 8.0	25.4 30.5 23.1 26.3	93.8 83.0 94.2 90.3	N . M S
Hvy Cl	36"	Between Ties 209-210	AVG	11.0 11.0 11.0 11.0	27.6 24.9 28.4 27.0	90.8 92.6 87.7 90.4	N M S
Lime Stab Lean Cl	Surface	Under Tie 209	AVG	1.8 31.0 12.0 14.9	34.5 34.5 42.5 37.2	88.1* 85.9* 81.1* 85.0	N - lime stab layer not present M - lime stab layer approx 2" thick S - lime stab layer approx 1" thick
Hvy Cl	6"		AVG	3.9 4.2 5.0 4.4	28.3 27.4 29.7 28.5	89.0 94.6 89.2 90.9	N M S
	12"		AVG	7.0 7.5 8.8 7.8	26.7 26.1 26.3 26.4	92.7 93.1 93.3 93.0	N M S
Hvy Cl	24"	Under Tie 209	۵VG	11.0 6.3 11.0	27.2 26.2 25.8 26.4	88.1 91.4 89.3 89.6	N M S

TABLE D-3 (Continued)

(Continued)

(Sheet 2 of 3)

• .

D-8

.

λ. .

:

	Depth		CBR Data						2	
<u>Material</u>	or Elev	Location		CBR	WC	DW	·			Remarks
Hvy Cl	36"	Under Tie 209	AVG	10.0 12.0 10.0 10.7	28.4 26.6 27.1 27.4	89.1 90.4 89.1 89.5	n M S			
Lime Stab Lean Cl	Surface	Between Ties 208-209	AVG	11.0 48.0 43.0 34.0	33.4 42.7 30.9 35.7	86.0* 80.6* 89.9* 85.5	N - M - S -	lime lime lime	stab st <b>a</b> b stab	layer approx 1" thi layer approx 3" thi layer approx 3" thi
Hvy Cl	6"		AVG	7.0 6.1 4.5 5.9	31.3 28.0 28.9 29.4	87.0 90.2 89.2 88.8	n M S			
	12"		AVG	7.2 7.1 6.0 6.8	27.2 27.7 28.5 27.8	90.9 90.8 90.7 90.8	N M S			
	24 <b>"</b>	-	AVG	15.0 6.8 11.0 10.9	27.6 25.4 23.8 25.6	89.0 94.3 94.3 92.5	N M S			
HvyCl	36"	Between Ties 208-209	AVG	11.0 11.0 12.0 11.3	25.8 25.4 26.3 25.8	91.4 93.3 90.7 91.8	N M S			
	• • • • •		AVG	11.3	25.8	91.8		:		· · · ·

TABLE D-3 (Concluded)

\* Computed from moisture cans with nuclear density.

(Sheet 3 of 3)

D-9

antes antes

Material	Depth or Elev	Location
Lime Stab Lean Cl	Surface	Between Ties 117 <del>-</del> 116
Lime Stab Lean Cl	Surface	Under Tie 116
Hvy Cl	6"	
	12"	
	24 <b>"</b>	
Hvy Cl	36"	Under Tie 116

D-10

	CBI	R Data			<del></del>		
	CBR	WC	DW			Remarks	
AVG	3.8 9.0 6.6 6.5	27.6 26.4 26.0 26.7	91.2 89.7 90.8 90.6	n M S	T A S		
AVG	3.0 9.3 7.6 6.6	29.8 27.8 24.7 27.4	89.7 87.2 94.0 90.3	n M S	1 1 3		
AVG	9.1 10.0 8.2 9.1	24.4 26.9 29.5 26.9	94.9 92.2 89.4 92.2	n M S	F 1 3		
AVG	9.3 14.0 9.4 10.9	28.6 30.6 27.2 28.8	87.7 87.3 91.7 88.9	n M S	Г 1 5		
AVG	13.0 13.0 14.0 13.3	23.0 22.3 21.9 22.4	95.0 94.4 97.3 95.6	n M S	r 1 5		
AVG	11.0 16.0 13.0 13.3	21.6 24.3 24.3 23.4	94.9 92.7 93.2 93.6	n M S	r - 1 1		

.

. . .

# TABLE D-4. KANSAS TEST TRACK SECTION 2A

(Continued)

.

	Depth	·· <u>···································</u>		CBR I	Data		······································
Material	or Elev	Location		CBR	WC	DW	Remarks
Lime Stab Lean Cl	Surface	Between Ties 116-115	AVG	3.1 3 9.3 2 6.6 2 6.3 2	31.3 28.1 28.4 29.3	89.7 85.1* 90.2 88.3	N M - void in cylinder S
Hvy Cl	6"		AVG	12.0 2 9.3 2 10.0 2 10.4 2	24.4 27.1 25.6 25.7	94.7 89.9 92.5 92.4	n M S
ран (1997) 1977 — Полона (1997) 1977 — Полона (1997)	12"		AVG	9.1 2 10.0 2 9.0 2 9.4 2	28.3 30.2 27.6 28.7	89.0 87.4 90.8 89.1	n M S
	24"		AVG	14.0 15.0 13.0 14.0	22.9 24.4 21.6 23.0	96.0 94.7 94.6 95.1	N M S
Hvy Cl	<b>36"</b> .	Between Ties 116-115	AVG	12.0 2 12.0 2 13.0 2 12.3 2	22.4 24.2 21.1 22.6	95.4 93.6 96.1 95.0	n M S
Lime Stab Lean Cl	Surface	Under Tie 115	AVG	3.7 9.5 6.6 6.6	27.5 28.4 25.8 27.2	90.4 86.6* 91.3 89.4	N M - void in cylinder S
				**.*		، ، سر	

TABLE D-4 (Concluded)

\* Computed from moisture cans with nuclear density.

D-11

i i internet

,

,

5



Lime Stab Lean Cl

D-12

Surface

Under Tie 277

### TABLE D-5. KANSAS TEST TRACK SECTION 2B

.

					· · · · · · · · · · · · · · · · · · ·
		CBR 1	Data		
	CBR	<u>WC</u>	DW	WC	Remarks
AVG	25.0 9.6 12.0 15.5	34.9 33.2 29.9 32.7	79.8 82.7 83.6 82.0	35.9 32.8 29.6 32.8	N M S
AVG	4.9 2.7 4.5 4.0	26.0 27.1 29.4 27.5	93.0 89.4 87.2 89.9		n M S
AVG	7.4 5.1 7.0 6.5	24.2 31.5 23.9 26.5	94.4 83.2 90.6 89.4		n M S
AVG	12.0 12.0 7.2 10.4	24.2 24.8 23.6 24.2	90.2 92.9 93.9 92.3		N M S
AVG	8.0 6.5 10.0 8.2	27.0 29.0 26.2 27.4	89.4 87.8 90.6 89.3		N M S
AVG	4.4 8.3 9.4 7.4	33.7 33.7 30.6 32.7	83.2 79.8 83.3 82.1	34.1 34.8 30.2 33.0	N B S

.

· ....

(Continued)

	Depth			(1777)	CBR I	Data						
Material	or Elev	Location		CBR	WC	<u> </u>	WC				Remarks	
Hvy Cl	6"	Under Tie 277	۰. ب	4.6 3.5	24.9 28.8	94.2 89.6	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	5	N M			
	е		AVG	4.0 4.0	27.2 27.0	90.1 91.3		e y	<b>S</b> .			
· · · ·	12"		•	6.0 8.2	26.5 26.3	91.2 89.2		, ε	N M			
r - l			AVG	9.3 7.8	26.4 26.4	90.0 90.1			8	ч. "		
	24"			9.1 9.3 10.0	22.3 24.3 24.6	95.5 92.7 92.9		• •	N M S	-	` .	, ··
Harre Cl	36"	Under Tie	AVG	9.5	23.7	93.7			N		,	
пуу СІ		277	AVG	8.3 8.7 8.7	23.8 23.8	89.4 91.8	•	۰ . ب	M S	,		
Lime Stab Lean Cl	Surface	Between Ties 277-278	C C	6.9 9.1	24.9 33.3 28.8	79.3 83.9	33.7 29.9		N M			
<u>`</u>	· · ·		AVG	9.1 8.4	32.8 31.5	82.0 81.7	29.7 31.1	4 s * -	S			
Lime Stab Lean Cl	Surface	Under Tie 278		5.7 8.1	33.0 32.9	83.5 80.1	33.5 34.0		N M			
en de la composition de la composition La composition de la c	in the second		AVG	9.1 7.6	31.4 32.4	82.1	3⊥•4 33•0	. ,	<b>ย</b> ส.			•

. 15

n í s ركاسك Plan des te

TABLE D-5 (Concluded) .

	Depth		CBR Data					,
Material	or Elev	Location		CBR	WC	DW	<u> </u>	Remarks
Lime Stab	Surface	Under Tie		3.8	24.6	84.6	N	Pit had lavers of limestone
Lean Cl		161	· ·	10.0	31.7	85.8	М	dust throughout and rocks
				9.0	29.0	87.1	-S	
			AVG	7.6	28.4	85.8		
Hvy Cl	6"		,	7.0	22.1	95.8	Ň	
			, .	7.0	21.5	95.5	M	
	· .			7.8	25.3	93.7	• <b>S</b>	
			AVG	7.3	23.0	95.0		
1	12"			7.1	29.0	88.1	N	
-				12.0	23.9	92.8	М	
				9.0	31.5	84.4	S	
			AVG	9.4	28.1	.88.4		
-	24"			10.0	22.5	95.5	N	
ł		· .		11.0	24.8	92.1	м	
	÷.,			9.0	23.1	94.4	· S	
			AVG	10.0	23.5	94.0		· · · · · · · · · · · · · · · · · · ·
Hvy Cl	36"	Under Tie	•	11.0	25.9	92.6	N	
• .		161		10.0	25.8	88.4	M	
				8.0	24.5	94.9	S	
		х 1	AVG	9.7	25.4	92.0		
Lime Stab	Surface	Between Ties		2.5	25.5	86.2	N	_
Lèan Cl	· ·	161-162		14.0	24.6	91.1	M	•
	•	• • ,		7.0	30.0	88.6	S	· ·
•			AVG	78	26 7	88 6	· · ·	

TABLE D-6. KANSAS TEST TRACK SECTION 3A

(Continued)

1001011100



	CBR Data			· · · · · · · · · · · · · · · · · · ·
	CBR	WC	DW	Remarks
	9.0	23.1	96.5	N
	8.0	27.3	91.6	M
	9.5	22.2	96.4	S
AVG	8.8	24.2	94.8	т.
	••••			
	11.0	28.8	89.3	N
	10.0	27.1	88.7	M
	7.5	30.4	85.4	S
AVG	9.5	28.8	87.8	
		•		
	11.0	25.1	93.2	N
	11.0	23.9	94.9	M
	9.0	27.4	90.3	S
AVG	10.3	25.5	92.8	
	11.0	26.4	82.8	N
	16.0	25.5	82.5	M
	12.0	25.1	92.9	S
AVG	13.0	25.7	86.1	-
		-201		
	4.0	19.9	91.9	Ν
	4.8	18.0	92.0	М
	9.0	25.2	93.0	S
AVG	5.9	21.0	92.3	
			-	
	4.1	31.5	90.2	N
	17.0	32.8	88.0	М
	3.4	29.1	84.9	S
AVG	8.2	21.1	87.7	

.°

-

۰.

TABLE D-6 (Concluded)

يهي هذه المنصلة الامتحاص معادية المحادث



D-16

# TABLE D-7. KANSAS TEST TRACK SECTION 3B

CBR Data					<u></u>		
	CBR	WC	DW		Rema	rks	
AVG	23.0 19.0 21.0 21.0	35.0 32.4 35.7 34.4	79.7 79.6 78.7 79.3	N M S			
AVG.	28.0 20.0 20.0 22.7	30.1 28.1 32.9 <b>30.</b> 4	82.4 83.4 81.9 82.6	N M S			
AVĢ	22.0 13.0 36.0 23.7	30.3 28.2 33.6 30.7	81.8 82.4 81.3 81.8	N M S			
AVG	2.3 8.0 4.0 4.8	26.5 26.0 25.5 26.0	90.4 92.4 91.5 91.4	N M S			
AVG	3.6 3.2 3.1 3.3	28.1 26.9 29.7 28.2	85.7 86.7 86.4 86.3	n M ··· S			
AVG	11.0 10.0 13.0 11.3	23.0 22.3 23.6 23.0	95.0 95.7 94.8 95.2	N M S			
		 	· ' , i			. *	

. ^ . . .

(Continued)



D-17

# TABLE D-7 (Concluded)

CBR Data				
	CBR	WC	DW	Remarks
AVG	9.0 8.0 9.0 8.7	24.7 22.8 22.4 23.3	94.3 95.0 94.9 94.7	N M S
AVG	17.0 21.0 20.0 19.3	35.8 33.5 36.4 35.2	77.8 82.8 77.6 79.4	N M S
AVG	5.5 7.0 5.1 5.9	26.4 26.0 26.0 26.1	92.2 92.4 89.5 91.4	N M S
AVG	3.8 4.4 4.2 4.1	26.6 27.0 24.2 25.9	89.1 90.2 94.0 91.1	N M S
AVG	13.0 12.0 12.0 12.3	23.0 21.6 25.6 25.9	95.6 94.9 91.7 94.1	N M S
AVG	9.0 11.0 9.0 9.7	23.8 23.7 22.6 23,4	95.0 95.6 93.5 94.7	N M S
-			·	

.



D-18

.

# TABLE D-8. KANSAS TEST TRACK SECTION 4

			1.	
	CBF	7 DAta		<del></del>
	CBR	WC	DW	Remarks
AVG	12.0 7.6 8.0 9.2	29.3 29.5 27.6 28.8	82.4 85.9 88.7 85.7	N M S
AVG	3.8 4.1 4.2 4.0	26.5 24.0 29.4 26.6	88.2 91.0 87.6 88.9	N M S
AVG	4.6 8.0 2.6 5.1	24.8 27.1 25.1 25.7	90.4 88.9 93.4 90.9	N M S
AVG	4.4 4.9 1.8 3.7	37.4 32.0 30.8 33.4	80.5 86.2 85.9 84.2	N M S
AVG	9.7 8.8 9.0 9.2	25.3 26.1 26.2 25.9	93.1 92.3 91.6 92.3	N M S
AVG	27.0 8.5 7.4 14.3	28.6 30.0 32.7 30.4	86.8 86.2 82.1 85.0	N M S
	۰.		•	

(Continued)

· · · ·



D-19

TABLE D-8 (Concluded)

÷

۰..:

	CBR Data			میں بیٹر ہے۔ یہ میں پیشی میں بیٹر کی پر
	CBR	WC	DW	Remarks
AVG	3.6 3.4 3.8 3.6	26.5 26.2 25.8 26.2	90.4 92.2 93.2 91.9	N M S
AVG	4.6 3.8 6.0 4.8	25.0 26.2 29.2 26.8	91.0 91.0 86.4 89.5	n M S
AVG	6.0 7.8 7.4 7.1	30.2 26.7 27.5 28.1	87.3 90.1 90.5 89.3	N M S
AVG	6.1 5.8 6.6 6.2	30.2 25.9 22.9 26.3	89.4 92.3 94.9 92.2	n M S
Material	Depth or Elev	Location		
----------------------	------------------	-------------------------		
Lime Stab Lean Cl	Surface	Center Slab 121 I		
Hvy Cl	6"			
	12"			
	24"			
Hvy Cl	36"	Center Slab 121		
Lime Stab Lean Cl	Surface	Joint Slabs 121-120		
Hvy Cl	6"			
Hvy Cl	12"	Joint Slabs 121-120		

D-20

TABLE	D-9.	KANSAS	TEST	TRACK						

SECTION 5

	CB	R Data		
	CBR	WC	DW	Remarks
AVG	18.0 9.4 13.7	31.6 30.4 31.0	82.4 84.5 83.5	M S
AVG	4.3 2.0 3.2	29.8 29.8 29.8	86.7 85.1 85.9	M S
AVG	2.3 3.2 2.8	29.5 29.6 29.6	86.3 86.7 86.5	М S
AVG	5.3 5.2 5.3	27.6 27.0 27.3	84.5 88.7 86.6	M S
AVG	14.0 13.0 13.5	25.5 25.3 25.4	92.0 91.3 91.7	M S
AVG	17.0 10.0 13.5	30.3 31.8 31.1	83.7 82.4 83.1	N S
AVG	3.5 3.0 3.3	29.5 30.2 29.9	87.3 84.6 86.0	N S
AVG	2.8 2.6 2.7	29.3 35.1 32.2	87.2 83.0 85.1	N S

(Continued)

TABLE D-9 (Concluded)

	Depth	· · · · · · · · · · · · · · · · · · ·		CBI	R Data	·····
Material	or Elev	Location	. '	CBR	WC	DW
Hvy Cl	24"	Joint Slabs 121-120	AVG	6.6 5.1 5.9	27.8 26.1 27.0	85.1 89.0 87.1
Hvy Cl	36"	Joint Slabs 121-120	AVG	17.0 18.0 17.5	25.6 26.0 25.8	91.7 90.2 91.0
		ŕ				·
	ч. •				• • .•	•
-					۰ م ۱	
		· ·				
. ,		. ·				
		-	x			-
				• •		
				,	;	· ·

÷. ....

• .								
	÷.				 	_		
· ·		 · · · · · ·	Remar	ks	 			
	N S		-					
,	n S							
	. <i>.</i> .	r						
		•	-					
-								
	·							
		·						
<del>,</del>		 			 -*	<u></u>		

.

Material	Depth or Elev	Location
Cement Stab Lean Cl	Surface	Joint Beams 63-62
Hvy Cl	6"	
	12"	
	24 <b>"</b>	
HvyCl	36"	Joint Beams 63-62

Cement Stab Lean Cl

۰.

Surface

Center Beam 63

•••

	CBI	R Date		
	CBR	WC_	DW	Remarks
AVG	30.0 50.0 44.0 41.3	92.8 30.6 28.1 29.5	83.1 85.6 87.0 85.2	N M S
AVG	1.3 3.1 1.8 2.1	37.0 31.0 38.3 35.4	82.8 88.4 84.0 85.1	N M S
AVG	6.6 7.4 8.0 7.3	26.2 26.5 24.8 25.8	92.9 93.1 95.4 93.8	N M S
AVG	6.0 5.6 6.0 5.9	27.3 27.2 30.6 28.4	90.8 88.5 86.8 88.7	N M S
AVG	7.0 11.0 10.0 9.6	26.1 26.0 25.8 26.0	89.8 91.4 93.6 91.6	N M S
AVG	33.0 62.0 33.0 42.7	29.4 30.5 32.4 30.8	85.3 84.8 81.9 84.0	N M S

# TABLE D-10. KANSAS TEST TRACK SECTION 7

(Continued)



Ϋ.

TABLE D-10 (Concluded)

D-23

	Depth			CBI	R Data			
Material	or Elev	Location		CBR	WC	DW		Remarks
Lime Stab Lean Cl	Surface	Under Tie 261 Between Ties 262-263	AVG	10.0 17.0 13.0 13.3 3.3 18.0	31.5 37.0 32.4 33.6 32.3 33.8 33.2	86.4 75.6 83.5 81.8 79.8 - 79.7 82.3	N M S N M S	Free water in ballast; stab layer approx. 4-1/2" thick; soil under this appears to be saturated; this could account for the high WC in the density
	₩ ₩		AVG	12.1	33.1	80.5		
Lime <sup>®</sup> Stab Lean Cl	Surface	Between Ties 261-262	Avg	12.0 26.0 10.0 16.0	35.3 34.2 35.9 35.1	78.6 79.3 79.3 79.1	N M S	
Hvy Cl	6"		Avg	2.8 3.4 4.2 3.5	31.0 28.2 28.3 29.1	87.3 89.9 90.4 89.2	N M S	Rock and voids in samples past surface depth
	12"		AVG	6.0 7.0 8.0 7.0	26.0 26.0 25.3 25.8	94.4 92.1 94.7 93.7	N M S	
Hvy Cl	24"	♥ Between Ties 261-262	AVG	14.0 15.0 13.0 14.0	26.1 24.4 20.1 23.5	92.0 95.2 97.9 95.0	N M S	

# TABLE D-11. KANSAS TEST TRACK SECTION 8 .

.

.

· ·

....

(Continued)

۰.

(vo)

TABLE D-11 (Concluded)

	Depth			CBF	{ Data	
<u>Material</u>	or Elev	Location		CBR	WC	DW
Hvy Cl	36"	Between Ties		12.0	25.0	93.0
•	· · · ·	261-262		12.0	24.7	94.0
	· · · ·	1	1770	12.0	24.4	93.4
,		, , , , ,	AVG	15.0	24.7	93.5
Lime Stab	Surface	Under Tie		16.0	34.4	79.6
Lean Cl	• • •	262 <sup>°</sup>		18.0	35.8	75.3
	• •	4	1770	17.0	32.8	82.3
	· ·	· · · · · · · · · · · · · · · · · · ·	AVG	T1.0	34.3	19•T
Hvy Cl	6"			3.1	26.3	93.0
• 1	· · ·			3.6	28.3	89.2
			1770	3.5	20.3	90.9
		1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	AVG	3.4	21.0	90.9
	12"			6.0	27.6	90.3
		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		8.0	25.9	93.9
, <del>-</del>			AVG	10.0	27.2	94.0 02 0
	· · · · ·		AVG	0.0	20.2	92.9
	24"	and the second second		14.0	25.6	93.6
	,	, , , , , , , , , , , , , , , , , , ,		12.0	23.1	- 94.9 02 h
			AVG	13.0	24.9	9 <b>3</b> •4
	,	<b>↓</b>		T 7 6 6	67•J·	94.0
Hvy Cl	36"	Under Tie		13.0	23.1	93.9
· · · · · · · · · · · · · · · · · · ·		202	÷	1) O .	27.9	
•.		اندا این در میں ورب اور ایک	AVG	13.0	24.0	91.3
· · · ·						

D-25



	Depth				CBR 1	Data				-,,
Material	or Elev	Location		CBR	WC	DW	WC		Remarks	<del></del>
Lime Stab Lean Cl	Surface	Un <b>der</b> Tie ll	AVG	10.0 17.0 23.0 16.7		76.2 79.9 75.0 77.2	38.0 38.0 38.0 38.0	. N M S		
		Between Ties 11-12	AVG	16.0 14.0 18.0 16.0		76.3 75.3 76.9 76.1	36.0 39.0 37.0 37.3	N M S	. <i>'</i>	
Lime Stab Lean Cl	Surface	Under Tie 10	AVG	19.0 15.0 23.0 19.0	35.0 38.0 35.9 36.0	78.3 77.5 78.1 78.0	37.0 35.0 36.0 36.0	n M S		
Hvy Cl	6"		AVG	2.7 2.2 2.4 2.4		87.0 84.2 87.7 86.3	31.0 33.0 30.0 31.3	N M S		
	12"		AVG	4.0 2.8 8.0 4.9		83.3 87.7 94.8 88.6	34.0 30.0 23.0 29.0	N M S	• • • • • •	
₩vy Cl	24 <b>"</b>	Under Tie 10		12.0 6.0 19.0	* 1 <sup>-</sup>	94.9 97.2 96.8	22.0 22.0 23.0	N M S		

# TABLE D-12. KANSAS TEST TRACK SECTION 9

(Continued)

	Depth	• <u></u>								
<u>Material</u>	or Elev	Location	CBR	WC	DW	WC	Remarks			
Нуу С1	36"	Under Tie 10	9.0 11.0 16.0 AVG 12.0	8 9 9 9	87.0 94.6 98.2 93.3	23.0 23.0 24.0 23.3	N M S · `	Rocks and <b>v</b> oids in samples		
Lime Stab Lean Cl	Surface	Between Ties 10-11	1 16.0 26.0 14.0 AVG 18.7	36.0 7 37.0 7 39.0 7 37.3 7	14.7 17.5 13.4 15.2	40.0 37.0 37.0 38.0	N M S			
	6"		2.6 2.9 2.9 AVG 2.8	8 8 8 8	38.2 33.9 37.7 36.6	29.0 33.0 30.0 30.7	n M S			
	12"		3.7 3.4 5.4 AVG 4.2	8 9 9 8	31.0 90.8 95.2 89.0	35.0 26.0 24.0 28.3	N M S∢			
	24"		13.0 7.0 16.0 AVG 12.0	9 9 9 9	97.0 94.4 94.4 95.3	21.0 21.0 22.0 21.3	N M S			
↓ Lime Stab Lean Cl	36"	Between Ties 10-11	10.0 12.0 12.0 AVG 11.3	9 9 9	93.7 95.0 94.4 94.4	23.0 23.0 24.0 23.0	n M S	· · · · · · · · · · · · · · · · · · ·		

TABLE D-12 (Concluded)

D-27

St. a. a. Sec. 1

Street week

#### TABLE D-13. LABORATORY TEST RESULTS ON BALLAST SAMPLES

,		· · ·		Pe	ercent	Finer	by V	Veight			Atterb	erg Limit	s on Fines
	U. S.	Stands	rd Sie	eve On	ning	in In.	ī	J. S. Stan	dard Si	eve Numbers	Liquid	Plastic	Plasticity
Identification	2	1-1/2	1	3/4	1/2	3/8	-	4	8 •	200	Limit	Limit	Index
				<u></u>									
B-1-N-T*	100	. 100	85	63	40	26		11	6	2	NP		
B-1-M-T	1	99	87	66	41	29		14	10	4	NP		
B-1-S-T		100	. 90	70	50	39		24	20	6	NP		
B-1-N-B	· · ·	1	. 95	81	55	41		21	17	9 :	37	. 24	13
B-1-M-B		·	96	82	63	μq		29	24	บ้	41	24	17
B-1-S-B	1		97	82	60	17		31.	24	11 .	35	25	10
B-1-N-SH	1	· · ·	Ó.	73	35	ıÅ		7	1	1 1			
B-1-S-SH	1		80	57	17	8		ĩ	2	ī			
B_24_5_T		1	00	67	28	26		16	10	<u>,</u> ,		,	
B-24-N-B	1		01	77	52	11		26	26	23			
B-24-S-B			07	81	56	51		20	18	10			
B-2A-S-SH	1	<b>*</b> 8	80	57	21	27		24	17	10 ·			
B-2R-0-01		100	88	65	24	21		14	10	1 h			
B OD N D	1	100	00	. 71	50	20		14	10	10			
B 2B C D"			93	74	21	20		27	20	12			
B CAN AT			90	11	47	34		22	19	12			
D-2B-N-SH			00	24	22	.9		2	Ţ	1			
D-JA-S-T			20	22	28	17		8	6	3			
B-3A-N-B			97	81	59	48		33	28	14			
·B-3A-S-B .			96	76	52	39		26	21	12			
B-34-S-SH		1	92	77	50	31		15	12	, 6			
B-3B-N-T		÷	76	50	26	16		11	10	5			
B-3B-11-B		i.	97	86	67	54		34	29	18			
B-3B-S-B		1	94	73	-49	37		27	24	12			
B-3B-N-SF			88	57	13	3		2.	2	1			
B–4–∞M–2		:	92	74	47	32		13	9	4	29	21 <sup>,</sup>	8
B=4-MJ=T			96	· 81	57	42		24	19	6	28	21	7
B-4-NM-B		V	95	. 83	57	42		24	20	11	35	24	11
B-4-NJ-B		. 99	94	83	64	51		31	24	8	29	21	8
B-4-SM-B		1,00	96	85	67	54		31	24	8	29	22	7
B-4-SJ-B			96	84	66	53		34	26	8	26	19	7
B-4-N-SH		}	. 96	89	70	54		27	17	6			·
B-4-S-SH			90	75	44	24		6	3.	1.		'	
B-5-SJ-B			95	70	45	34		22	18	10			
B-5-NJ-B		1	96	84	65	54		35	27	12			
B-5-MM-B		ł	99	90	74	61		37	27	11			
B-5-S-SH		λ.	96	83	60	41		15	11	2	·		
B-7-MM-T			93	74	48	35		22	18	12			
B-7-NJ-B	1	1	04	74	52	38		25	21	12			·
B-7-SJ-B	1		<u>9</u> 4	75	52	30		27	23	14			
B-7-N-SH	1		93	71	46	33		16	·0	3			
B-8-S-T	4	i i	óĩ	69	32	16		-ŭ	2	· 1			
B-8-N-B			04	76	43	25		12	ā	5			
B-8-S-B		1	63	67	38	26		14	12	ó			
B-8-5-5H			82	54	28	16		<u> </u>	- 2	í			
B-9-N-T			96	78	16	31		18	16	12	42	26	16
B_Q_M_T		-	<u>01</u>	. 75	1.8	30		13	10	Ъ	35	21	14
B-Q_S_T	1		01	62	22	24		2	2	1			1-
B_Q_N_B	•	·	01	65	20	18		12	11	ō	հհ	26	18
B_Q_M_B			0)	70	57 50	27		21	21	12	1.3	26	17
B_0 S.B	1		06	95	61	31		24	24	15	27	20	12
D-J-J-D D N CU	1	1	90	70	-01	41	•	<u> </u>	20	10	21	24	13
D-9-N-5H		1.	93	(2	30	Τſ		. (	0	2			
8-9-5-58	¥	V	09	60	21	(		2	T	1			
Additions? M	+ a												
Augulional Tes	105						• .						
B-2B-AS	100	100	96	87	73	64		47	39	17			
B∸8–UT			90	61	24	12		5	4	1.		·	
B-8-AS			94	85	63	50		32	26	13			<u></u> _
B-9-UT			92	68	36	26 .		17 -	16	11	42	26	16
B-ML-5900		1	95	64	27	14		7	6	3 '			
B-ML-8526	4	4	97	89	28	16		5 .	4	2			
	•	-											

\*Legend and example of sample identification numbers is given below.



· . . .

D-28

٠,

Pit No.	Depth From Top of Subgrade	USGS Classi- fication	<u>I.L</u>	PL	PI	Percent Finer Than No. 200 Sieve	Color
1	0-12	CH	57	28.	34	93	Brown
1	24-36	CH CH	62	23	-39	91	
2A	0-12	CH	62	24	38	95	
2A	24-36	CH	61	24	37	96 `	
2B	0-12	CH	59	23	36	95	
2B	24-36	CH	63	23	40	95	
3A	0-12	CH	59 .	23	36	94	
3A	24-36	CH	60	22	38	94	;
3B	0-12	CH	53	23	30	93	
3B	24-36	CL	46	20	26.	69	
4	0-12	CH	61	24	37	94	
4	24-36	CH	66	24	42	95	
5	0-12	CH	63	20	43	89	
5	24-36	CH	59	25	34	92	
7	0-12	CH	58	24	34	91	,
7	24-36	CH	60	19	41.	91	
8	0-12	CH	56	23	33	93	
8	24-36	CH	58	19	39	90	
9	0-12	CH	62	24	38	97	Y
9	24-36	СН	55	21	34	95	Reddish- Brown

TABLE D-14. LABORATORY CLASSIFICATION TESTS ON SUBGRADE SAMPLES

D**-**29

.









FIGURE D-2. PROFILES AND CROSS SECTION OF TEST SECTIONS 2A AND 3A

Ζ.

D-31



FIGURE D-3. PROFILES AND CROSS SECTION OF TEST SECTION 2B

D-32



FIGURE D-4. PROFILES AND CROSS SECTION OF TEST SECTION 3B

• •



FIGURE D-5. PROFILES AND CROSS SECTION OF TEST SECTION 4

1





FIGURE D-6. PROFILES AND CROSS SECTION OF TEST SECTION 5





FIGURE D-7. PROFILES AND CROSS SECTION OF TEST SECTION 7



FIGURE D-8. PROFILES AND CROSS SECTION OF TEST SECTION 8





ŝ,



FIGURE D-10. TYPICAL PLATE BEARING TEST SETUP









- 0 LOCATION OF TOP (0 TO 8 IN.) BALLAST SAMPLES
  - LOCATION OF BOTTOM (8 TO 18 IN.) BALLAST SAMPLES

LOCATION OF UNDISTURBED SOIL SAMPLES

Δ

NOTE: TWO SACK SAMPLES OF SOIL WERE TAKEN FROM EACH TRENCH.

FIGURE D-12. TYPICAL LOCATIONS OF BALLAST AND UNDISTURBED SOIL SAMPLES ON TIE SECTIONS





FIGURE D-13. TYPICAL LOCATIONS OF BALLAST AND UNDISTURBED SOIL SAMPLES ON BEAM SECTIONS

. -

.





### LEGEND

- △ LOCATION OF PLATE BEARING TEST
- O LOCATION OF CBR, MOISTURE, AND DENSITY TESTS ON SUBGRADE
- LOCATION OF BALLAST SAMPLES
- O LOCATION OF UNDISTURBED SOIL SAMPLES

FIGURE D-14. LOCATIONS OF FIELD TESTS AND SAMPLES ON TRACK SECTION 5



FIGURE D-15. SUBGRADE SURFACE OF TEST PIT 1



FIGURE D-16. SOUTH WALL OF TEST PIT 2A (NOTE BALLAST SUBGRADE INTERFACE)

D-43



FIGURE D-17. CROSS SECTION OF SUBGRADE SURFACE (NOTE BEAM EDGES ARE RESTING ON SHOULDER SUBGRADE INDICATING 3-1/2- TO 4-IN. RELATIVE DEFORMATION UNDER TRACK STRUCTURE)





# LEGEND

- Δ LOCATION OF PLATE BEARING TEST ON BALLAST
- O LOCATION OF CBR, MOISTURE, AND DENSITY TEST AREAS ON SUBGRADE (SURFACE ONLY)
- O LOCATION OF CBR, MOISTURE, AND DENSITY TEST AREAS ON SUBGRADE (SURFACE, 6-, 12-, 24-, AND 36-IN. DEPTHS)

FIGURE D-18. TYPICAL LOCATIONS OF FIELD TESTS ON TIE SECTIONS





# LEGEND

LOCATION OF PLATE BEARING TEST Δ LOCATION OF CBR, MOISTURE, AND DENSITY TESTS 0

FIGURE D-19. TYPICAL LOCATIONS OF FIELD TESTS ON BEAM SECTIONS



FIGURE D-20.



CALIFORNIA BEARING RATIO (CBR)






D-49







. . .



FIGURE D-24. UNCONSOLIDATED, UNDRAINED (Q) TRIAXIAL TEST RESULTS FROM TEST PITS 1 AND 4



FIGURE D-25. UNCONSOLIDATED, UNDRAINED (Q) TRIAXIAL TEST RESULTS FROM TEST PIT 9

D-52

	_							_				
							. L	_				
	ŧĦ	┟┼┼┼╏┲┲┲		╪╪╪╪┽┥		1	PALUER SIGETOMES	III		┟╆╞╪┟┨┨┨┋	╞╪╪╪╪╪┋	
	t##	<u>   </u>	╪┇┋┇┋┋	*1******	******			ш	╞╁╞╞╉╂┤┤┤	╞╆┊┊┊┋┋╧┊╴	<u>╪╪╪┊╞╞</u> ┇╪╪	
	###	╏╪┧╡┟┟╽╽╽	<del>↓↓↓↓↓↓↓</del> ↓↓↓	<del>╪┇┋┇┇┇┋┇┇┇</del>	\$414444			<b>†</b> ‡‡	┢╬╆╞╋╉╪╁╪╧		┊╎╎┧┵┙┫╿╽┨	
	ŧĦ	*****	┊┊┋┊┊┋┋┚┊┇	<del>┇╹<u>╏</u>┇┇</del> ┇┇┇┇┇			ι Ψ 🖽	111	*****	╪╪┽┽┼┦┾┿┾	<u>    </u>	
· · · · · · · · · · · · · · · · · · ·	###	<u>                                     </u>	╞╡┽┟╎┛╎┼╎	╪╪╪┊╧╪╪╪╪			ি ব া	Ħŧ		╞╪╪╪╪╪╪╪		
	##	*****	╪┼┼┼┼┼┼┼	╡┥╻┥╡			1 (3) #	Ħŧ	╞╡╪╪╉╤╪╅	*****	╞╪╡╅╪╪╪╪╪╪	
1 5 時	###	*****	<del>┇┊╡┊┊┇┇┊┇┇</del>				L LED & HH	111		LIII Kolt		
	###	;;;;;;;;;;					l a' šĦ	###			<del>┇┋┇</del> ┇╏╏╏╏╏	
	##	*******		₽₩₽₽₽₽₽₽				Ħ	MIII ANN	<b>           </b>		
	ĦŦ	HULL	*****					И	ницн		74 - I - I - I - I - I	
	ĦŦ	Inguli	╎┼╏╎╎╏╎╎╎	*****			\.~ \$ ##	Į#‡				
	116	ri mii ii		<del>            </del>				CH.R.	ALIIII			
1 8 🖽	И						i o `≬∰7	HA				
	ИΥ							ЖI				
0.4	ĿИ	<del>                         </del>	<del>┊╒┊╛╞┫┥╽</del>	<b>····</b>				AH)	<b>HHHH</b>	<b>FFFFFFF</b>		
	ИI			<del>┨┥╿╿╽<u>╢</u>╋</del>				H	┢╋┟┫╋╋┥┚┛╿		┊┼┧┊╞╋╋╋┥	
	111	<u>↓↓</u> ╆┟╈ <u>╄</u> ╋╋		╈╋╋				Ш				
	Ш		<u><u></u></u>	<u>┼┼┠┠┟┟┨</u> ╋╋				Ш		┢╋╈╋┥╋┥╏┥		
	##	<del>┟┦<u></u>╏╎╏╎╏╎╽╽</del>	<u>ŧŧŧŧŧ</u> ŧŧ	*******				Ht			╏┵┇┟┟┟╏┨┾╞	
		min	ապա	mmu	mind			ч	<u>unn</u> un	uniter.		8
			ARIAL STRAIN, T	•						ASIAL STRAIN, S.		
		<u> </u>		<u> </u>				_				
tisi NO.			×	· · ·		1.11			1	2	3	
TITE OF SPECIMEN		Undiat.	Undist-	{	1		TYPE OF SPECIALIN		Undist.	Undist.	Undist.	
WATER CONTENT	-	27 5 %		9		1	WATE Crownel	-	28 17 5	<b>*</b>	28.) %	%
	<b>,</b> •••	e1.2	4.5	+	<u>↓</u>	۰ I		<u>۳</u>	20.7	20.0	CO.1	i
A AND BATHO	e.	0.800	0.772				3 400 8100	1	0.881	0.856	0.838	
A SATURATION	5	92.8 %	99.0 %		5		E BATHEARDH		88.0 %	88. 3 5	90.5 %	\$6
1	<u> </u>	<u></u>		<u> </u>	<u> </u>	· ·		1				<u> </u>
DRY DENGTY, LAVOU FT	10	94.7	95.1				BRY SONERY, LA/CU FF	Ľ*	89.6	90.8	91.7	
TAME TO FAILURE, MEN		9	30				TANK TO PARAME, MEN	4	2	ь	13	
Included Constanting	Ē	<u> </u>		+	<u>├───</u>		HIGCING CONSTRUCT	<u>ا</u>	<u> </u>			
STIENGTH, T/SQ FT	9	1.17	1.13	L			STAINCAL, 1/20 P	•	2.30	2,61	2.08	
UNDRABASED SHEAR STEEHOTH, 1/80 PT		0.58	0.56		1		UNBEAMED INCLUS (2304375, 1/50 FT	•	1.15	1.30	1.04	
	Ē	<u></u>		+	┼───┤			١,				<u> </u>
LENGRATHY RATIO	s.	L		L	<u> </u>			1	L			
HETAL SPECIMEN DAMETER, IN	D.	1.41	1.41		·		NARMA STREAMEN CANADISH, IM	<b>D.</b>	1.40	1.40	1.39	
· · · · · · · · · · · · · · · · · · ·	1.			+ ···	<u>                                      </u>							
INITIAL SPECIALEN NEIGHT, BA.	H,	3.00	3.00				DETAL BRICKING HERCET, BL	м.	3.00	3.00	3.00	
CLASSERIATION FLASTIC CLAY (CH), Y	ddi	sh brown;gr	avel up to	<u>1/1"</u>			CLAMPEARON PLASTIC CLAY(CH), b	row				
u <u>-</u> a -		(Pi _		0. 2.70			u 62 🛤 24	<u>`</u>	(P	38	2.70	(Fat.)
RAA/KS	1002	KT KANSAS T	TEST TRACK					FRECA	KY KANSA	S TEST TRAC	<u>x</u>	
		POST NO	RTIN INVEST	IGATION			· · · · · · · · · · · · · · · · · · ·		POST	NORTEM DIVE	STIGATION	
I			· - 1									
				AND IN THE REAL PROPERTY AND INTERPOPERTY AN	Sond -		·	1.0		h	2AT	1076
	K.	0-12"	1	ממעל כב	1710			8	0-12		23 Sept.	1710
L	KOC.	UNCON		NOR DET REPO	m(		L		6740.076			<u></u>
				•			· ·				•	
						1 4						
	-			·								
PADLES SEFTONES 4.0	n.	нннт						TT.	mm	mm	HTTTT	mm
					1			Ħ				
PADUTE SKETCHES												
PALUE SEFORES												
PALLER SEFTORS 4.0											<b>0</b>	
0 3.0											0	
											0	
											0	
									/			
									1			
									1			
									1			
MALUEI METONS         4.0           Image: state s												
ALUES METONES     4.0												
PALUEI METORIS         4.0           Ø         3.0           Ø         3.0           Ø         1.0           Ø         1.0									1			
			-9 <b>-9</b>									
ALLES METONS     4.0     0     .0     .0     .0     .0     .0     .0     .0     .0     .0     .0     .0     .0     .0												
												B
MALUEI METONES         4.0           Image: state												
PAALES METONS         4.0           Image: state s			алан ( 1997 Ф. су 1997 Ф. су 1997 Ф. су 2016 Ф. су 2016 Ф. су 1997 Ф. су 2016 Ф. су 1997 Ф. с						2 L Updiet.	And short T	<b>A</b> <b>A</b> <b>A</b> <b>A</b> <b>A</b> <b>A</b> <b>A</b> <b>A</b>	
PARLIES METORS         4.0           Image: State		The second secon	Unite:							С. С. С. С. С. С. С. С. С. С.		
MALLES METONS         4.0           ●         3.0           ●         3.0           ●         5           ●		λ υαίτε. 27.0 5	2 Updist. 27.4 %						2 1 Undist. 28.1	2 Updist. 28.0	6 3 Undist. 28.0	
PALUEI METORIS         4.0           Image: Contract of the contract		1 27.05 27.05 27.05 27.05 27.05	2 27.4 27.4 27.4 50.4 50.4 50.4 50.4 50.4 50.4 50.4 50						2 2 1 1 2 8.1 2 8.1	28.0 % 0,805	6 3 1 28,0 5,005	
PAALIES BEFORES         4.0           Image: State		1 Uadist. 2,7:05 5,7:05	2 Updist. 27.4 % 0.770 %						2 1 Undist. 28.1 5 0.805 5 2	2 Undist. 28.0 %	<b>2</b> <b>2</b> <b>2</b> <b>2</b> <b>2</b> <b>2</b> <b>2</b> <b>3</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b>	
PAALES METONS         4.0           Image: state s		1 0 0 0 0 0 0 0 0 0 0 0 0 0	2 10 10 10 10 10 10 10 10 10 10 10 10 10						2 2 1 1 0.805 94.2	C.BC5 93-94 1001101 2001101 28.0 0.805 93.9 8	6 3 0,805 93.9	
PAALUEI BEFORES         4.0           Image: State of the state		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2 Uptist. 27,1, % 0,770 97.6						2 2 1 Updiet. 28.1 9 9,2 9 3,4	2 Undist. 28.0 % 93.9 %	<b>9</b> <b>9</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b>	
PALLET METONS         4.0           Image: Angle of the state of		1 Ualist. 27.0 5 5.5 5 95.5 5	2 UDLIST. 2 UDLIST. 2 UDLIST. 2 0.770 56.1 % 92.6						2 1 Upd1st. 28.1 93.4 37	2005 2007 200 200	<b>4</b> <b>5</b> <b>6</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b> <b>1</b>	
PAALUEI METONES         4.0           Image: State of the state		1 Undist. 27.0 55.5 7	2 Upoliet. 27,4 95,6 24,				0         3           0         3           0         3           0         3           0         3           0         1		2 2 1 Updiet. 28.1 93.4 37	2 0.805 93.9 93.0 20	6 3 Updist. 28.0 93.9 93.9 93.4 26	
PAALIES METONS         4.0           Image: State		2.40	2 Updist. 27.4 5 0.770 56.4 5 25.6				0         3           0         3		2 1 Updiet. 28.1 93.2 37 3.04	ASA 1000, 1 ASA 1	93.9 93.0 3.04	
PALLES METORS         4.0           Image: Control of the second secon		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	2 Undist. 27.4 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9						2 2 1 1 1 2 2 2 37 3.0 4 3.0	2 Ubditst. 28.0 93.9 93.1 20 3.02 3.02	6 3 3.9 93.9 93.9 93.4 26 3.0 0	
PAALIES BEFORES         4.0           Image: State		1 Uadist. 27.0 5 5 5 5 5 5 5 5 5 5 5 5 5	2 99-97 97 97 97 97 97 97 97 95 95 95 95 14 2,11 1,06						2 2 1 Und1st. 28.1 99.4 37 3.04 1.52	2 Undist. 28.0 % 93.9 % 93.4 20 3.02 1.51	202 202 202 202 202 202 202 202	
PALLES BEFORES         4.0           Image: Angle of the second		1 1 1 27.0 59.5 5 7 2.40 1.20	2 10-11 27-4 10-11 27-4 10-11 27-4 27-4 50-6 14 2-11 1.06				6ALINE BUTCHE         4           0         3           0         3           0         3           0         3           0         3           0         3           0         1           0         1           0         1           0         1           0         1           0         1           0         0           0         <		2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 1 1 2 1 1 2 1 1 1 2 1	Control Contro	6 0.805 93.9 93.4 26 3.04 1.52	
PAALIES BEFORES         4.0           Image: State		1 Undist. 27.0 5 5 6.765 5 5 8 7 2.100 1.20 1.00	2 0 0 0 0 0 0 0 0 0 0 0 0 0						2 2 1 Updiet. 28.1 9 9.2 9 3.4 37 3.0 8 1.52	2 Ubdist. 28.0 % 93.0 3.02 1.51	200 3 Updist. 28.0 93.9 93.4 26 3.04 1.52 	
PAALES METCHES         4.0           0         3.0           0         3.0           0         5.0           0 <td></td> <td>1 1 1 1 1 1 1 1 1 1 1 1 1 1</td> <td>2 10 27,4 27,4 37,4 37,4 37,4 37,4 37,4 37,4 37,4 3</td> <td></td> <td></td> <th></th> <td></td> <td></td> <td>2 2 1 1 2 2 2 1 2 2 2 2 2 2 2 2 2 2 2 2</td> <td>2 2 3.02 3.02 1.51 1.40</td> <td>6 3.04 3.04 3.04 3.04 3.04 3.04 1.52 1.39</td> <td></td>		1 1 1 1 1 1 1 1 1 1 1 1 1 1	2 10 27,4 27,4 37,4 37,4 37,4 37,4 37,4 37,4 37,4 3						2 2 1 1 2 2 2 1 2 2 2 2 2 2 2 2 2 2 2 2	2 2 3.02 3.02 1.51 1.40	6 3.04 3.04 3.04 3.04 3.04 3.04 1.52 1.39	
PAALIES BEFORES         4.0           Image: State		1 1 1 1 1 1 1 1 1 1 1 1 1 1	2 Updirt. 27.4 % 95.6 14 2.11 1.40 3.00						2 2 1 Usatiet. 28.1 93.4 37 3.00 1.52 3.00	2 Updist. 28.0 3.02 1.51 1.60 3.00	0.305 93.9 93.4 3.04 1.52 1.39 3.00	
PAALES BEFORES         4.0           Image: State		1 Uatist. 27.0 5.766 55.5 7 2.40 1.20	2 Updist. 27.4 5 0.770 56.4 5 25.6 1,40 3.00						2 1 Updiet. 28.1 93.4 37 3.00 1.59 3.00 b rown -	Assume to the second se	3           Updist.           28.0           93.9           3.04           1.52           1.39           3.04	
PAALIES BEFORES         4.0           Image: State		1 Undist. 27.0 55.8 7 2.k0 1.k0 3.00	2 Upoliet. 27.4 % 95.6 14 1.40 3.00	· · · · · · · · · · · · · · · · · · ·					2 2 1 Undist. 28.1 93.4 37 3.04 1.39 3.00 h brown - [n]	2 Updist. 28.0 93.9 93.1 20 3.02 1.51	6 3 Updist. 28.0 93.9 93.4 26 3.04 1.39 3.00	
PAALIES BEFORES         4.0           Image: State		1 Uadist. 27.0 5 5.7 2.40 1.40 3.00 5 7 2.40 1.40 3.00	2 Undist. 27.4 % 5.11 1.06 1.40 3.557 TRAC						2 1 Updiet. 28,1 93,2 93,4 37 3,00 1,39 3,00 1,39 3,00 1,39 3,00	Asa REAST TAPO	93.9 3.00 1.52 2.20,0 (5 3.00 1.52 3.00 1.39 3.00	8 
PALLES METORS         4.0           Image: State S		1 Uadist. 27.0 55.5 55.8 7 2.40 1.40 3.00 	2 Undist. 27.4 95.6 14 1.40 3.000 7.770 9.5.1 1.40 3.000 7.771 1.40 3.000						2 2 1 1 1 2 2 2 1 1 2 2 1 1 2 2 1 1 2 2 1 1 2 2 2 1 1 2 2 1 1 1 2 2 1 1 1 1 2 2 1 1 1 1 1 2 2 1	2 Updits. 2 Updits. 2 2 Updits. 2 3.0 3.0 3.0 3.0 3.0 3.0 3.0 3.0 3.0 3.0	P         P           P         P	
PAALIES BEFORES         4.0           Image: State		1 1 1 1 1 1 1 1 1 1 1 1 1 1	2 2 2 2 2 2 2 2 2 2 2 2 2 2						2 2 1 Undist. 28.1 5 93.4 37 3.00 1.52 1.39 3.00 1.52 1.39 3.00 1.52 1.39 3.00 1.52	2 Undist. 28.0 93.9 93.9 93.9 93.0 1.51 1.40 3.00	3 Updist. 28,0 93,9 93,4 26 3,0% 1,52 1,39 3,300 [6, 2,70 () x	8 <b>x</b> <b>x</b>
PALLET METORS         4.0           Image: Contract of the second seco		1 1 1 1 1 1 1 1 1 1 1 1 1 1	2 Undist. 27.4 5 95.6 14 2.11 1.06 3.000				6.44.182.8:07008         4           0         3           0         3           0         3           0         3           0         3           0         3           0         3           0         3           0         1           0         1           0         1           0         1           0         1           0         1           0         1           0         1           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0         0           0		2 2 2 1 1 2 2 2 2 2 3 3 3 3 3 3 3 3 3 3	AVA EFLAN X 2 1 2 1 2 2 2 2 2 2 2 2 2 2 2 2 2	6 3.04 1.52 1.39 3.00 6 2.30 1.52 1.39 3.00 6 2.70 (f) 2.70 (f)	8 
PAALIES BEFORES         4.0           Image: State		1 1 1 1 1 1 1 1 1 1 1 1 1 1	2 Updirt. 27.4 % 95.6 14 2.11 1.06 3.00 						2 1 Usatiet. 28.1 93.4 37 3.00 1.52 1.39 3.00 1.52 1.39 3.00 1.52 1.39 3.00 1.52 1.39 3.00 1.52 1.55 1.55 1.55 1.55 1.55 1.55 1.55	2 Updist. 28.0 3.02 3.02 1.51 1.40 3.00 2 7557 TAKC 000000 DIVE	0.305 9.3.9 9.3.9 9.3.4 3.00 (a. 2.70.10 x STIGATION Market 23 23.52 25.52	8 8 9 1976
PAALES BEFORES         4.0           Image: Control of the second seco		1 Uadist. 27.0 5.766 95.5 95.8 7 2.10 1.20 1.00 1.20 1.	2 27.4 % 27.4 % 2.4				6.44.182.8:07008         4           0         3           0		2 2 2 2 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2	ANA (ELSA) X ANA (ELSA) X 2 2 2 2 2 2 2 2 2 2 3 3 20 3 3 20 3 3 20 3 3 20 3 3 20 3 3 20 3 3 20 20 3 20 20 3 20 20 3 20 20 3 20 20 3 20 20 3 20 20 20 20 20 20 20 20 20 20		8 
PAALIES BEFORES         4.0           Image: State		1 Undist. 27.0 5 5.7 5 95.6 7 2.40 1.40 3.00 (n 	2 Updiet. 27.4 % 95.6 14 1.40 3.000 						2 1 Undist. 28.1 93.4 37 3.04 1.39 3.00 b From 1.39 3.00 b Torm 1.39 3.00 b Torm 1.39 3.00 b Torm	2 Undist. 28.0 39.9 3.02 1.51 1.40 3.00 5 TEST TRAC OKITA DIVE	3           Updist.           28.0           93.9           93.4           26           3.00           1.39           3.00           (a. 2.70.10)           x           STUATION           AMM 23 Sept. VERT Card	8 8 9 1976 2776 2776

FIGURE D-26. UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 1 AND 2A



FIGURE D-27. UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 2B AND 3A

-			_				
	FAILURE SKETCHES . 8	₽					
	Θ	Ħ	H			▐▐ <u></u>	
ļ							
	Ň				•••••		
	2						
	сонтночию атлеха	Ħ					
ļ	CONTROLLED STRAIN	•		2	ATLAL STRADY, 9	. 6	
72	7 ND.			1	2	3	
m	E OF SPECIMEN			Undist.	Undist.	Undist.	
Γ	WATER CONTENT		•.	27.9	26.4 *	27.8	S
3	VDID BATTO		•	0.852	0.776	0.808	
١£.	SATURATION			88.4 *	91.8 *	92.9	- *
	DRY DEHERTY, LEVICU PT		74	91.0	94.9	93.2	
714	IE TO PAILUTE, MIN		4	10	15	12	
ų,	CONTINUED COMPRESSIVE ENGTH, 1/50 FT		•	4.59	5.47	5.57	
ų	CALANED SHILL STEINGTH, 1/10 PT		•	2.30	2.73	2.78	
st?			4				]
M	TAL BRECHICH CLAMETER, IN		Π.	1.39	1.39	1.39	
N	TAL BRECINER HERONT, IN.	_	м,	3.00	3.00	3.00	
<u></u>	53 PLASTIC CLAY(CH	/, bro 23	wn.	14	30	a 2.70/2	
-	Specimens from bott:		FROM	KT KANSA	S TEST TRAC	x =======	
3	f sample;top was too crumb	¥.		POST	NORTEN INV	STICATION	
-			100	43 HQ.		AND NO. 38	
-			<b>S</b> OM	0"-12"		4 Oct.19	76
			RE	UNCON	DARD COMPTHE	NON THAT SHO	17
_		_	_				







.

FIGURE D-28. UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 3B AND  $^{\rm L}_4$ 



FIGURE D-29. UNCONFINED COMPRESSION TEST RESULTS FROM TESTS PITS 5 AND 7



97

FIGURE D-30. UNCONFINED COMPRESSION TEST RESULTS FROM TEST PITS 8 AND 9

D-57

#### APPENDIX E: INSTRUMENTATION

#### General

There had been three major data acquisition periods in the brief life of KTT, but parts of these data, notably moisture measurements and some of the final readings of the vertical extensometers, were thought to be unreliable. The Federal Railroad Administration (FRA) desired an evaluation of the embankment instrumentation to include its design, function, calibration, and condition. This work was carried out in Phase II of the field investigations.

This section documents the investigation of instrumentation arrays installed in the Kansas Test Track (KTT) embankment by Shannon and Wilson, Inc. (S&W),\* and the data recording system owned and operated by the Portland Cement Association (PCA). The items of interest in this study are the soil pressure cells, temperature and moisture meters, vertical, partial, and total deflection meters, and the recording system. The horizontal extensometers will not be considered since they were not permanently installed and could be examined and calibrated as needed.

### Transducers

A standard Schaevitz Model 1000HR Linear Variable Differential Transformer (LVDT) was installed in the extensometers as the transducer element. The pressure cell assembly manufactured by Slope Indicator Company employed the Schaevitz Model PT-7 pressure transducer. The Soiltest, Inc., Model MC-300A soil moisture and temperature meter was used to detect the soil temperature and moisture at various locations in the embankment test sections.

<sup>\*</sup> Shannon and Wilson, Inc., "Embankment Support for a Railroad Test Track, Construction Report," Aug 1972, U. S. Department of Transportation Federal Railroad Administration, Washington, D. C.

### Dynamic Recording Equipment

The information detected by the embedded transducers was recorded with equipment housed in the PCA field recording van. Recording equipment in the van included carrier amplifiers, power supplies, oscillographs, and other equipment necessary to simultaneously record 30 channels of data.

The amplifier, which furnished a carrier (excitation voltage) to the LVDT-type transducers, has the capability of suppressing the transducer output to zero volts within the limits allowed by the amplifier gage factor setting. All cables and interconnections in the van were permanently wired including external bulkhead transducer connectors.

Provisions were also made to attenuate large, full-scale static transducer output signals to be compatible with Sanborn recording equipment.

The Sanborn "150" recording system used has a flat frequency response up to 20 Hz and is within <u>+8</u> percent up to approximately 70 Hz. Additional details concerning recording equipment are given in a report by H. C. Greer.\*

### Field Calibrations and Measurements

Extensive tests were conducted at the main arrays at Test Sections 2, 7, and 9. Readings were recorded from the embedded vertical extensometers, soil pressure cells, and the soil moisture and temperature sensors to define the final settlement and soil pressure of the embankment.

LVDT calibrations were referenced to a micrometer having a 0.0001-in. accuracy and a John Fluke digital voltmeter (DVM) as shown schematically in Figure E-1. With the LVDT core adjusted to its electrical zero, a DVM reading  $(V_{\rm o})$  was made. The Standard LVDT core was

<sup>\*</sup> H. C. Greer, Memorandum for Record, Subject: Trip to Portland Cement Association at Skokie, Illinois, May 1976, U. S. Army Engineer Waterways Experiment Station, CE, Vicksburg, Miss.

displaced exactly 1.000 in., as measured with the micrometer, and another DVM reading  $(V_1)$  was made. The excitation voltage  $(V_E)$  was also read and recorded. The sensitivity of the LVDT can be expressed as

$$\frac{V_1 - V_0}{V_E} = 0.257/0.7319 = 351 \text{ mv/v/in.}$$
(E-1)

The Schaevitz Model TR-100 indicator was calibrated to indicate l in. on its readout when the Standard LVDT was deflected l in. Therefore, by knowing that the sensitivity of the Standard LVDT is 351 mv/v/in. and that a deflection of one is indicated on the TR-100, transducers of other sensitivities can be read with the TR-100. The equation for displacement is

Displacement = 
$$\frac{S_1}{S_2}$$
 × TR-100 Indicator Reading (E-2)

where  $S_1$  equals 351 mv/v/in.,  $S_2$  is the known sensitivity of other LVDT in mv/v/in., and TR-100 reading is in inches. The equation for pressure is

Pressure = 
$$\frac{S_1}{S_2}$$
 × TR-100 Indicator Reading (E-3)

where  $S_1$  equals 351 mv/v/in.,  $S_2$  is the sensitivity of pressure transducer in mv/v/psi, and TR-100 indicator reading is in inches.

The static readings from the extensometers and soil pressure cells were made with the TR-100 using the above equations, and the final readings taken are listed in Table E-1. Readings from the soil moisture and temperature sensors were made for documentation purposes, were not converted to temperature and moisture units, and are recorded in Table E-2. Insulation to ground readings of all transducers in the main instrumentation arrays in Test Sections 2, 7, and 9 are listed in Tables E-3, E-4, and E-5, respectively.

### Field Observations

The main instrumentation arrays at Test Sections 2, 7, and 9 were excavated to a depth which included position 1 pressure transducer located approximately 3 ft below the top plate of the multiple vertical extensometer (Figures E-2 and E-3) and the extensometer locations O1 and O2.

Soil was very carefully removed from transducer areas to prevent damage to pressure cell diaphragms and cables or disturbance of interfaces between soil and transducers. Pressure cell extensometer terminal box and PCA pressure cell elevations were measured with a surveyor's level and are recorded in Figures E-4 through E-9.

Diaphragms of the soil pressure cells were depressed (in place), and indications were observed on the TR-100 LVDT, which verified that the units were operable and had the proper polarity. Pressure cells excavated had a good interface with the soil as shown in Figures E-10, E-14, E-15, and E-21. All pressure cells were operable with the exception of those located at 2201 and 2202 which had open circuits in LVDT secondary windings. Sound anchor prong-soil interfaces were found after excavation and are shown in Figures E-11 (Test Section 2), E-16 and E-17 (Test Section 7), and E-22 (Test Section 9).

Extensometer terminal boxes were opened for inspection, and loose mechanical connections were found, as shown in Figures E-12, E-13, E-18, E-19, E-24, and E-25. These loose connections may be the source of phase reversals, noisy signals, and questionable data which were encountered during the testing period. Although other main instrumentation arrays were not scheduled to be excavated, it was convenient to remove the ballast from the main arrays at Test Sections 1, 3, 6, and 8 in order that the multiple vertical extensometer terminal boxes could also be opened for inspection. Condition of the internal parts of these extensometers and appropriate photographs are tabulated in Table E-6. The presence of mud and water inside terminal boxes required further examination of extensometers in Test Section 7. This inspection revealed that pumping had occurred between the construction joints of the two

polyurethane foam lifts. Evidence of pumping is shown in Figure E-20 and can best be seen on extensometer 7401 (right side of the picture). The dark area in the cut out area long the construction joint indicates that mud had impregnated the white polyurethane foam.

Soil samples were taken beneath extensometers 2401 and 2402 where the water content was determined to be 28.4 and 29.0 percent by weight, respectively. Soil samples were also taken between pressure cells 9201 and 9202 and beneath extensometers 9401 and 9402 where the water content was found to be 28.0, 29.0, and 30.0 percent, respectively. Evidence of the high water content below 9402 is shown in Figure E-23 where water was seeping from higher elevations and pooling just below the extensometer terminal box.

LVDT's located in Test Sections 2, 7, and 9 were calibrated in place using a carpenter's rule as a standard. These values are considered as checks on the performance of the transducers after subjection to a hazardous environment for a lengthly period of time. Data from these calibrations are in Table E-7.

### Posttest Laboratory Calibration of Soil Pressure Cells

Soil pressure cells excavated from the KTT embankment were check calibrated at the WES using laboratory standards and equipment (Figure E-26). These calibrations were performed to determine after-test transducer sensitivity and linearity so that an evaluation could be made as to the validity of test data retrieved from these instruments. During the calibrations, the LVDT output voltage was recorded at several different pressure levels set by use of a laboratory test pressure gage with an accuracy of  $\pm 0.25$  percent full-scale and with the LVDT excitation voltage and frequency held constant. Linearity curves for each transducer calibrated are shown in Figures E-27 through E-32. Tabulated values of applied calibration pressures, output voltages measured at each pressure, and the error expressed in terms of percent full-scale deviation from the best straight-line fit drawn through all points is shown in Tables E-8 through E-13. The calibration history

of the pressure transducers is shown in Table E-14.

### Soil Moisture and Temperature Sensors

The temperature sensors produced reliable data, but as indicated by Shannon and Wilson\* the moisture sensor readings were erratic and undependable. Several sensors were removed from the KTT and returned to the factory in hopes of getting some indication of the cause for gross failures. Soiltest, Inc., furnished a letter report (Figure E-33) concerning their evaluation of these transducer failures.

### PCA Carlson Pressure Cells

No electrical readings were made by the WES on the PCA pressure cells, but several interesting items were noted in photographs taken at the site. The photograph in Figure E-34 shows typical settlement under the ties and the heaving between them. Figure E-35 gives an indication of the construction problem involved where the reinforcing metal was very close to the pressure cell. Figure E-36 shows where a repairman inadvertently drove a wooden wedge between one of the pressure cells and the concrete when attempting to level the slab. Figures E-37 and E-38 show the effects of pumping where the pumped lime-like materials are attached to the pressure cell. Note in E-38 that the material installed on the cells to protect the groove (pressure sensing area) from becoming contaminated with foreign particles is deteriorated and has allowed particles to contaminate the area. Information obtained from pressure cells operating in this type environment and condition would be questionable.

<sup>\*</sup> Shannon and Wilson, Inc., "Embankment Support for a Railroad Test Track, Analysis of Embankment Instrument Data," Vol 1, Jan 1976, U. S. Department of Transportation Federal Railroad Administration, Washington, D. C.

	· · · · · · · · · · · · · · · · · · ·	an a	- 1	<u></u>
Gage	TR100	Gage Sensitivity*	Deflection	
Location	Indication	<u></u>	<u> </u>	Date
2401-1	1-251**	382.3	1 151	5/20/76
201-2	1 107	378.2	1 001	5/20/76
2401-4	1.25L	372.3	1.18L	5/20/76
× , · · ·			. 3.	
2402-1	1.45L	379.2	1.34L	5/20/76
2402-2	1.40L	379.0	1.30L	5/20/76
2402-4	<b>1.30L</b>	381.2	<b>1.20</b> L	5/20/76
2403-1	0.55R <sup>†</sup>	379.3	0.51R	5/20/76
2403-2	0.00	377.5	0.00	5/20/76
2404-4	0.03R	379.0	0.028R	5/20/76
ר בטולצ	0 801	277 7	0.761	5/18/76
701-2	0.021	378 0		5/18/76
7401-L	1.201	375.8	1,121.	5/18/76
1407-4	T. COD			77207:0
7402-1	0.50R	380.0	0.46L	5/18/76
7402-2	1.50L	374.2	1.41L	5/18/76
7402-4	0.045L	377.3	0.0421	5/18/76
7403-1	0.27L	379.8	0.251	5/18/76
7403-2	0.55L	374.0	0.516	5/18/76
7404-4	1.10L	378.7	1.02L	5/18/76
ດມ∩າ⊸າ√	1 051	377 3	0.087	
9401-2 ·	1.00L 0.05T	211.2	0.97L	5/19/76
9401-3	0.557	277 2	0.577	5/19/76
9401-4	0. <u>45</u> 7.	311.5	0.107	5/19/(6
,		310.7	0.421	2/19/ (0
9402-1	1.35L	372.8	1.27L	5/19/76
9402-2	1.25L	376.3	1.17L	5/19/76
9402-3	1.30L	381.0	1.20L	5/19/76
9402-4	1.30L	374.0	1.22L	5/19/76
9403-1	0.30R	379.2	0.28R	5/19/76
9403-2	0.60R	375.8	0.56R	5/19/76
9403-3	0.90R	370.5	0.85R	5/19/76
9403-4	1.45R	378.0	1.35R	5/19/76
		а.		•

 $\dot{z}$ 

TABLE E-1. FINAL EXTENSOMETER INDICATIONS

\* From Shannon and Wilson, Inc., op. cit., p. E-1.
\*\* L - down.
† R - up.

Gage	Temperature	Moisture
2301	1251.*	-1 8 E T
2302	1 30T.	
2303	1251.	1001
230J	1301.	1851
2305	1301	2001
2306	301	200L 18u
2307	1)101	
2308	1001	1651
2300	1301	1050
2310	101**	
2311	1251	LOH
2312		
2313	1251	47L 1651
2313	7227	TOPL
7301	12L	55H
7302	128L	91L
7303	133L	76L
7304	128L	191L
7305	122L	186L
7306	118L	196L
7307	114L	200L
7308	112L	186L
7309	128L	197L
7310	184L	197L
7311	134L	194L
7312	164L	OPEN
7313	OPEN	175L
9301	130L	45H
9302	135L	30H
9303	130L	15H
9804	125L	10H
9305	190L	190L
9306	15H	15H
9307		-
<u>9</u> 308		-
9309	130L	170L
9310	140L	185L
9311	140L	_175L
9312	135L	50L
9313	125L	87L

### TABLE E-2. FINAL INDICATIONS, MOISTURE AND TEMPERATURE FROM MC300A METER

,

\* Indicates low range on MC300A meter.
\*\* Indicates high range on MC300A meter.

•

51 e P

TABLE E-3. INSULATION TO GROUND, TEST SECTION 2, 20 MAY 1976

	Gage	Α	В	C	D	Е	F	G	H	J	K	L	M	N	P	R	S	Т	U	V	W	X	<u> </u>	<u>Z</u>	<u>α</u>	Con	nector
	2401-1	>20M	>20M	>20M	>20M	>20M																					l
	2401-2				-	v	1.5M	1.5M	. 700K	700K	<u>700</u> K				۰.		10			•		• •				:	l
	2401-4			~	¢							,					100K	120K	120K	120K	285K		•	• . •			1
	2402-1	20M	7M	20M	20M	lM			-																		2
	2402-2						20M	720K	800K	800к	720K	•							,							• •	2
	2402-4		-														>20M	>20M	>20M	>20M	>20M					· .,	2
	2403-1	20M	20M	20M	20M	20M																					3
	2403-2			-			>20M	>20M	>20M	>20M	>20K							د			.•					•	3
۰.	2403-4														,	;	MI	· lM	500K	500K	230K					· ,	3
	2201	7M	5M	3M	>20M	>20M	5M								: '		ŕ									م ال	4
· .	2202	-						· 7M	· 7M	350K	720K	20M	120K				٠,										4
	2203 🚬 🖉	÷ .	· · ·	1		÷		·7		. 7	*			20M	· 20M	20M	20M	20M	20M	. •••		<u>.</u>	-				4 ·
:	2301	1,0K	5K	8к		• •			••	• *	· · ·			• "		``		.`	· - ·	· · ·		en e	<u> </u>			: {ر	5 <sup>.</sup>
•	2302				19K	15K	19K											•		.'						· · · ·	5
	2303		· •	•			-	<u>,</u> 20K	17K	19K	, ·			•								•		;			5
•^	2304					· · ·					178	14K	14K													e ing ke	5
	2305										•		. •	18k	14K	15K	,									ಎಲ್ಲಿ ಎಲ್ ಇಗ್ಗ	5.
. *	2306							,	· ·	· ·				•			70K	9ÓK	40K		. •					1 -5	5
·	2307	ı																	-	30K	26K	30K		• •		÷.	5
	2308			*				•	•	- ,					". 	*						·	30	к 13К	17K	1.1	5
	2309	15K	15K	12K.	·•									÷						-	5'					·. ,	6
	2310				80K	100K	3M													•							, 6
•	2311						• `	40K	25K	40K					-,			~ ~							,		6
÷ ,	2312				,			·. ,	•		401	25K	40K	,		`-		•	•			· .	;	• •			6
	2313	. • ×	-	•	ŗ		· . •		-	•	-			156	106	158		•						• •			6

. .

Note: K = 1,000 clims M = 1,000,000 clims

Gage	A	В	C	D	E	F	G	H	_J	К	L	M	<u>N</u> _	Р	R	S	T	U	_ <u>v</u>	W	X	_Z_	<u>α</u>	Connector
7401-1	20M	20M	20M	20M	20M																			1
7401-2						20M	20М	20M	20M	20M														1
`7401-4											,			,		20M	20M	20M	20M	20M				1
7402-1	2.5M	2.5M	1.5M	1.5M	250K																			2
7402-2						2.5M	2.5M	500K	650K	30k														2
7402-4																350K	350K	300K	300K	140K				2
7403-1	>20M	>20M	>20M	>20M	>20M												•							3
7403-2						>20M	>20M	>20M	>20M	>20M								•				•		3
7403-4																>20M	>20M	>20M	>20M	>20M				3
7201	>20M	>20M	700K	1.5M	1.5M	500K																		4
7202							lom	10M	3M	lom	10M	3M	•			,								4
7203												•				710K	710K	710K	710K	710K				4
																								,

# TABLE E-4. INSULATION TO GROUND, TEST SECTION 7, 18 MAY 1976

Note: K = 1,000 chms M = 1,000,000 chms

TABLE	E-5.	INSULATION	TO	GROUND,	TEST	SECTION	9,	
		19	MAY	1976				

Gage	A	В	C	D	E	F	G	H	J	K	L	М	N	P	R	<u>S T U V W X</u>	Y Z	α	Connector
9401-1	20M	20M	20M	20M	20M														1
9401-2						15M	15M	1.5M	1.5M	15M									1
9401-3											3M	3M	450K	450K	140K				1
9401-4											<u>``</u>					1.5M 1.5M 140K 150K 260K			l
9402-1	lM	lM	900K	900K	>20M														2
9402-2						4M	4M	1.5M	1.5M	>20M									2
9402-3											400K	400K	120K	120K	230K				2
9402-4																160K 180K 110K 110K 240K			2
9403-1	>20M	>20M	>20M	>20M	>20M														3
9403-2						20M	20M	240K	240K	>20M									3
9403-3											>20M	>20M	>20M	>20M	800K				3
9403-4																>20M >20M >20M >20M >20M			3
9401	280K	260K	300K	150K	150K	lM													4
9402							1.5M	2M	600K	600K	600K	600К							4
9403													550K	550K	450K	5M 5M 2M			4
9301	95K	105K	95K																5
9302				85K	140K	90K													5
9303							200K	300K	210K										5
9304										350K	450K	350K							5
9305													5K	18K	8K				5
9306																350K 450K 350K			5
9307																>20M >20M >2	MOM		5
9308																	>20M >20	M >20M	5
9309	20K	16K	184	2															6
9310				45K	45K	50K													6
9311							40K	45K	45K	£02									6
9312										100K	150K	100K							6
9313													45K	22K	40K				6

Note: K = 1,000 ohms M = 1,000,000 ohms

Location 1401-1 1401-2 1401-4 1402-1	Broken	Bent	Jammed	uaton nou		unpang.	core weberng
1401-1 1401-2 1401-4 1402-1	broken	Dent	Jammea	Braken	HOTOP	Mud	on Bottom
1401-2 1401-4 1402-1				Druken	Y	muu	
1401-4 1402-1					· Y		
1401-4					A V		
1402-1	v				л		
	X						
1402-2	X N						
1402-4	X		v	v		· ·	v
2401-1			X	A A			A V
2401-2	X			•			· A · V
-2401-4			77	37	v	v	<b>.</b>
2402-1			X	X	X	A V	
2402-2	Х	X	Х		X	X	
2402-4	Х	х			X	X	
3401-1					X		
3401-2	Х				X		
3401-4					х		
3402-1	Х	¢			X		
3402-2	Х				X		
3402-4	Х				Х		
3403-1							
3403-2							
3403-4							
. 6401-1							
6401-2							
6401-3							
64C1-4							
6402-1	Х				Х		
6402-2			· . · .	4 x 2	X		÷ -
6402-3	Х				Х		
6402-4	Х				Х		
7401-1				·			
7401-2							
7401-4							
7402-1					Х	X	
7402-2					X	X	
7402-4	Х		х		Х	х	
8401-1							
8401-2							
8401-4							
8402-1					Х		
8402-2					Х		· ·
8402-4					Х		
9401-1	,						
9401-2	,		Х				
9401-4							
9402-1					Х		
9402-2	X				Х		
9402-3					Х		
9402-4					Х		

TABLE E-6. CONDITION OF EXTENSOMETER LVDT ASSEMBLY

	TR-100	LVDT Sensitivity*	Displacement
Gage	Indication	mv/v/in.	<u>in.</u>
2401-1'			
2401-2	1.1R**	378.2	1.02R
2401-4	0.97R	372.3	0.91R
2402-1'			
2402-21			
2402-4	0.95R	379.0	0.83R
7401-1†			
7401-2	1.05R	378.0	0.98R
7401-4†	÷		
7402-1	0.97R	. 380.0	0.98R
7402-2	1.05R	374.0	0.98R
7402-4	1.05R	377.3	<b>0.9</b> 8R
9401-1	1.05R	377.3	0.98R
9401-2	1.05R	380.2	0.97R
9401-3	1.05R	377.3	0.98R
9401-4**	1.5R	376.5	1.4R
9402-1‡	. •		
9402-2	1.06R	376.3	0.99R
9402-3	1.05R	381.0	0.97R
9402-4	1.05R	374.0	0.99R

# TABLE E-7. INSITU CALIBRATION VALUES FOREXTENSOMETERS, 20 MAY 1976

\* From Shannon and Wilson, Inc., op. cit. p. E-1.

\*\* R = up.

- + Could not loosen LVDT core from reference assembly.
- tt Calibrated twice.
- # Rod jammed tube.

### TABLE E-8. POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 2203

### 1-FT CABLE

12-1-76

### LINEAR LEAST SQUARES CALIBRATION VOLTS / PSIG VOLTS = -.976736754479D-02 + .221103075793D-02 PSIG

RESSURE	OUTPUT	(VOLTS)	DIFFERENCE	ERROR
(PSIG)	MEASURED	PREDICTED	(VOLTS)	% FULL SCALE
10.00	.0140	.0123	00166	.85858
20.00	.0320	.0345	.00245	-1.27111
30.00	.0540	.0566	.00256	-1.32827
40.00	.0760	.0787	.00267	-1.38542
60.00	.1240	.1229	00111	.57281
80.00	.1670	.1671	.00012	05963
98.00	.2070	.2069	00009	.04474
80.00	.1680	.1671	00088	.45850
60.00	.1230	.1229	00011	.05467
49.00	.0790	.0787	00033	.16899
30.00	.0570	.0566	00044	.22614
20.00	.0360	.0345	00155	.80143
10.00	.0140	.0123	00166	.85858

### 30-FT CABLE

LINEAR LEAST SQUARES CALIBRATION VOLTS / PSIG VOLTS = -.861905800567D-02 + .228796865692D-02 PSIG

PRESSURE	OUTPUT	(VOLTS)	DIFFERENCE	ERROR	
(PSIG)	MEASURED	PREDICTED	(VOLTS)	% FULL SCALE	
10.00	.0150	.0143	00074	.36422	
20.00	.0380	.0371	00086	.42349	
30.00	.0610	.0600	00098	.48276	
40.00	.0910	.0829	.00190	93581	
60.00	.1270	.1287	.00166	81727	
80.00	.1730	.1744	.00142	69874	
98.00	.2180	.2156	00240	1.18134	

### TABLE E-9. POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 7201

# 12-1-76

### 1-FT CABLE

LINEAR LEAST	SQUARES CALIBRATION	VOLTS / PSIG	
VOLTS =	50009743563 <b>3D-03</b>	+ .307000026768D-02	PSIG

PRESSURE	OUTPUT	(VOLTS)	DIFFERENCE	ERROR
(PSIG)	MEASURED	PREDICTED	(VOLTS)	* FULL SCALE
10.00	.0300	.0302	.00020	16260
20.00	.0600	.0609	.00090	73171
30.00	.0910	.0916	.00260	48781
40.00	.1220	.1223	.00030	24391
50.00	.1530	.1530	.00000	00000
40.00	.1230	.1223	00070	.56910
30.00	.0920	.0916	00040	.32520
20.00	.0610	.0609	00010	.08130
10.00	.0310	.0302	00080	.65041

## 30-FT CABLE

LINEAR LEAST SQUARES CALIERATION VOLTS / PSIG VOLTS = .30000000000-03 + .311000000000-02 PSIG

PRESSURE (PSIG) 10.00 20.00 30.00 40.00	OUTPUT MEASURED .0320 .0620 .0930 .1250	(VOLTS) PREDICTED .0314 .0625 .0936 .1247	DIFFERENCE (VOLTS) 00060 .00050 .00060 00030	ERROR * FULL SCALE .43397 40323 48387 .24194
40.00	.1250	.1247	00030	.24194
50.00	. 1560	.1558	00020	.16129

### TABLE E-10. POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 7202

			·······	11-30-76	
		<u>1-FT</u>	CABLE	· · ·	
LINEAR LE VOLTS	AST SQUARES	6 CAL IBRATI 24589723D-	0N VOLTS / 03 + .4	/ PSIG 125428608523D-02	PSIG
PRESSURE (PSIG) 10.00 20.00 30.00 40.00 50.00 40.00 30.00 20.00 10.00	0UTPUT MEASURED .0420 .0840 .1280 .1200 .1200 .1280 .0840 .0430	(VOLTS) PREDICTED .0423 .0849 .1273 .1699 .2124 .1699 .1273 .0848 .0423	DIFFERENCE (VOLTS) .00026 .00080 00066 00011 .00043 00011 00066 .00080 00074	ERROR <b>%</b> FULL SCALE 15126 47059 .38655 .36722 25211 .06722 .38655 47059 .43698	

## 30-FT CABLE

LINEAR LEAST SQUARES CALIBRATION VOLTS / PSIG VOLTS = .225514051877D-16 + .440000000000-02 PSIG

### TABLE E-11. POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 7203

٦	2-	7_	<b>7</b>	ĥ
_	<u> </u>	<u> </u>	1	Ų.

# 1-FT CABLE

LINEAR LEAST SQUARES CALIBRATION VOLTS / PSIG VOLTS - .130417253968D-02 + .179727639617D-02 PSIG

PRESSURE	OUTPUT	(VOLTS)	DIFFERENCE	ERROR
(PSIG)	MEASURED	PREDICTED	(VOLTS)	% FULL SCALE
10 00	.0190	.0192	. 00019	- 11270
20.00	0770	0370	00005	- 03166
20.00	.0010	0010	,00000	.00100
30.00	0220	.0549	00008	.04939
40.00	.0730	.0728	00020	.13043
60.00	. 1080	.1085	.00054	34443
80.00	.1440	.1443	.00029	19235
98.00	.1760	. 1765	.00046	29125
80.00	.1450	.1443	- 00071	.45460
60.00	. 1090	.1085	- 00045	.29251
40.00	.0730	.0728	00020	.13043
30.00	.0550	.0549	00008	.04939
20.00	.0370	.0370	.00005	03166
10.00	.0190	.0192	.00019	11270

### 30-FT CABLE

LINEAR LEAST SQUARES CALIBRATION VOLTS / PSIG VOLTS = .205155237483D-02 + .183916903366D-02 PSIG

PRESSURE	DUTPUT	(VOLTS)	DIFFERENCE	ERROR
(PSIG)	MEASURED	PREDICTED	(VOLTS)	% FULL SCALE
10.00	.0200	.0204	,00044	27361
20.00	.0390	.0388	00017	. 10189
30.00	.0570	.0572	.00023	13989
40.00	.0760	.0756	00039	.23561
60.00	.1130	.1124	00060	.36932
80.00	.1490	.1492	.00019	11424
98.00	.1820	.1823	.00029	17908

## TABLE E-12. POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 9201

11-30-76

# 1-FT CABLE

LINÈAR	LEAST	SQUARES	CALIBRATION	VOLTS	
VOL	TS •	25714	438425630-82	÷	.813714

÷	.8137	14356665D-02	PSIG

PRESSURE	OUTPUT	(VOLTS)	DIFFERENCE	ERROR
(PSIG)	MEASURED	PREDICTED	(VOLTS)	% FULL SCALE
5.00	.0400	.0381	~.00169	1.15668
10.00	.0780	.0788	.00080	49030
15.00	.1180	.1195	.00149	91148
20.00	.1600	.1602	.00017	10517
25.00	.2030	.2009	00214	1.31463
20.00	.1600	.1602	.00017	10517
15.00	.1180	.1195	.00149	91148
10.00	.0790	.0799	.000990	-,49880
5.00	.0390	.0381	·00089	.54339

# <u>30-FT CABLE</u>

LINEAR LEAST	SQUARES CALIBRATION	VOLTS / PSIG	
VOLTS -	-,44000000000000-02	+ .8680000000000-02 PS	51G

PRESSURE (PSIG)	OUTPUT MEASURED	(VOLTS) PREDICTED	DIFFERENCE (VOLTS)	ERROR % FULL SCALE	
10.00 15.00	.0810 .1240	.0824	.00140	80925	
20.00 25.00	.1690	.1692	.00020 00140	11561 .80925	

### TABLE E-13. POST EXCAVATION CALIBRATION OF SOIL PRESSURE CELL 9202

12-1-76 1-FT CABLE LINEAR LEAST SQUARES CALIBRATION VOLTS / PSIG VOLTS - .157141890407D-02 .399142891945D-02 PSIG + DUTPUT (VOLTS) . MEASURED PREDICTED PRESSURE DIFFERENCE ERROR % FULL SCALE (PSIG) (VOLTS) .32143 .0420 .0415 10.00 -.00051 .00040 .0810 .0814 20.00 .1213 30.00 .1210 .00031 -. 19643 40.00 .00023 -.14286 .1610 -.00086 50.00 .2020 .2011 .53571 40.00 .1610 .1612 .00023 -.14286 -.19643 -.25000 .32143 30.00 .1210 .1213 .00031 20.00 .0910 .0814 .00040 10.00 .0420 .0415 -.00051

## 30-FT CABLE

LINEAR LEAST SQUARES CALIBRATION VOLTS / PSIG VOLTS = .500000000000-03 + .419000000000-02 PSIG

PRESSURE	OUTPUT	(VOLTS)	DIFFERENCE	ERROR
10 00	MEHSURED 0470	PREDICIED 0424	- 000C0	ZECOO
10.00	.0430	,0424	-,00000	- 770 <i>11</i>
20.00	1270	1262	- 00130	47984
40.00	1680	. 1681	.00010	- 05988
50.00	.2100	.2109	00000	.00000

		Se in	Sensitivity in mv/v/psi				
Cell	Range	Slope Indicator	WES Calibration				
Number	in psia	Company Calibration*	0 ft of cable	30 ft of cable			
2201	25	8.667	**	**			
2202	50	4.263	* *	* *			
2203	100	2.225	2.211	2,288			
7201	50	3.120	3.070	3.110			
7202	50	4.303	4.254	4.400			
7203	100	1.802	1.787	1.839			
9201	25	8.693	8.137	8.680			
9202	50	4.086	3.991	4.190			
9203	100	2.000	. †	+			

# TABLE E-14. CALIBRATION HISTORY OF MAIN INSTRUMENTATION ARRAY SLOPE INDICATOR COMPANY PRESSURE CELLS

- ---

. .

\* From Shannon and Wilson, Inc., op. cit., p. E-1.

\*\* Defective cell.

- -

· ..

† Leads and air tube cut too short for calibration vessel.



FIGURE E-1. CALIBRATION NETWORK FOR SCHAEVITZ LVDT

E-21

1



FIGURE E-2. INSTRUMENTATION LAYOUT (from Shannon and Wilson, Inc., op. cit., p. E-5)



-

FIGURE E-3. INSTRUMENT INSTALLATION DETAILS (from Shannon and Wilson, Inc., op. cit., p. E-1)





a. PCA PRESSURE TRANSDUCERS

FIGURE E-4. TEST SECTION 1, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY



### a. PCA PRESSURE TRANSDUCERS

FIGURE E-5. TEST SECTION 2, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY



a. PCA PRESSURE TRANSDUCERS

FIGURE E-6. TEST SECTION 3, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY



a. PCA PRESSURE CELLS

FIGURE E-7. TEST SECTION 7, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY




## a. PCA PRESSURE TRANSDUCERS

FIGURE E-8. TEST SECTION 8, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY



## a. PCA PRESSURE TRANSDUCERS

FIGURE E-9. TEST SECTION 9, TRANSDUCER ELEVATIONS AT MAIN INSTRUMENTATION ARRAY



FIGURE E-10. TEST SECTION 2, MAIN INSTRUMENTATION ARRAY



FIGURE E-11. TEST SECTION 2, EXCAVATED EXTENSOMETER



FIGURE E-12. TEST SECTION 2, 2402 TERMINAL BOX



FIGURE E-13. TEST SECTION 2, 2401 TERMINAL BOX



FIGURE E-14. TEST SECTION 2, EXCAVATION 2201



, FIGURE E-15. TEST SECTION 7, MAIN INSTRUMENTATION ARRAY



FIGURE E-16. ANCHOR PRONG-SOIL COMPLING FOR GAGES 7401-1 AND 7402-1, TEST SECTION 7



FIGURE E-17. ANCHOR PRONG-SOIL COMPLING FOR GAGE 7-01-1, TEST SECTION 7



FIGURE E-18. TEST SECTION 7, 7401 TERMINAL BOX



FIGURE E-19. TEST SECTION 7, 7402 TERMINAL BOX



FIGURE E-20. TEST SECTION 7, EXCAVATION OF 7401 AND 7402



FIGURE E-21. TEST SECTION 9, PRESSURE CELLS 9201 and 9202



FIGURE E-22. TEST SECTION 9, EXTENSOMETER EXCAVATION



FIGURE E-23. EXTENSOMETER TERMINAL BOX EXCAVATION SHOWING TILT AND WATER SEEPAGE, TEST SECTION 9



FIGURE E-24. TEST SECTION 6, FAILURE OF EXTENSOMETER 6402



FIGURE E-25. TEST SECTION 8,



FAILURE OF EXTENSOMETER 8402



FIGURE E-26. CALIBRATION NETWORK FOR SLOPE INDICATOR COMPANY SOIL PRESSURE CELL

E−46





## E-48

1











SOILTEST, INC.

BARABOD, WISCONSIN 53913

DIVISION OF BOILTEST, INC., EVANSTON, ILL. Bubbidiary of Cenco Incorporated

TELEPHONE 608/356 8777

TELEX 265-455

REFER TO:

June 9, 1976

Department of the Army Waterways Experiment Station, Corps of Engineers P.O. Box 631 Vicksburg, Mississippi 39180

Dear Mr. Greer

RE: WESBP 20/1982

SUBJECT: Evaluation of Failure of (5) Soil Moisture Cells Returned to Soiltest.

Upon receipt of the (5) cells, we soaked them in a solution of isopropyl alcohol and tap water mixed at a ratio of approximately 100:1.

(Note: This solution is used because it is relatively safe, readily available, doesn't leave a residue, and yield a mid-range meter reading.)

In this test aknown good cell from our stock was used as a reference.

Test Results In Alcohol-Water Solution read with a Soiltest MC-300B Soil Cell read out:

	Resistance	Temperature	
Cell #1	230K	79 <sup>0</sup> F	NOTE: Temperature readings were
Cell #2	65K	77 <sup>0</sup> F	not corrected and are not expected to be precise due to evaporation of the
Cell #3	1000K	80 <sup>0</sup> F	
Cell #4	200K	69.5 <sup>0</sup> F	
Cell #5	200K	78.5 <sup>0</sup> F	alcohol.
Known good	đ		
cell	11K	77 <sup>0</sup> F	

At this point I talked to Homer C Greer, WES on June 7, 1976, and discussed our course of action in evaluating the defective soil cells. It was decided that Soiltest, Inc. would analyze the cells free of

ENGINEERING TEST EQUIPMENT FOR SOILS, CONCRETE, BITUMINOUS PRODUCTS & CONSTRUCTION MATERIALS

FIGURE E-33. LETTER REPORT FROM SOILTEST, INC., TO WES CONCERNING DEFECTIVE SOIL MOISTURE CELLS

charge and submit a report to W.E.S. of our findings.

In a subsequent phone conversation on June 8, 1976, I was informed by Mr. Greer that the defective cells had been buried in the roadbed ballast of a railroad in Kansas.

This information, coupled with the results of Dr. Oestings report led us to the following conclusion.

The cells'outer shells were plated with copper, while the pores in the electrode spacer fabric were plugged by a non-conducting substance, probably a petroleum based substance such as diesel fuel or weed killer. Positive tests could not be conducted because of the initial alcohol bath.

Electric current for the plating could have come from several possible sources:

- 1. Galvanic currents produced by a chemical reaction between the steel rails and chemicals present in the roadbed ballast.
- 2. Current flow between the rails
  - a. Current used for signal devices.
  - b. Inter-rail current flow from the electric drive motors used in modern diesel engines.

Suggestion:

If roadbed measurements are necessary, we suggest that a representitive abandonded roadbed be choosen. Preferably one that has not been contaminated by unknown materials. Such a roadbed might be a spur line into a quarry.

Please feel free to reprint this report.

Sincerely,

In os Powe

M. B. Powell Customer Service Manager

enclosure

FIGURE E-33. (CONTINUED)

June 9, 1976

To: M. B. Powell From: R. B. Oesting Subject: Moisture Cells

I examined two moisture cell units and found copper plated on the surfaces of them. There was no evidence of corrosion or of any other deposit being present. Iron was absent from these surface deposits.

Further test on the glass cloth spacer removed from a faulty cell showed traces of an organic compound. This test was run after immersion of the cell in alcohol and no more detailed conclusion is possible. The organic compound was not isopropyl alcohol but was some high molecular weight residue.

R.B. Cesting

R. B. Oesting PhD Professor of Chemistry University of Wisconsin

FIGURE E-33. (CONCLUDED)



FIGURE E-34. DIFFERENTIAL SETTLEMENT IN PCA PRESSURE CELL ARRAY, TEST SECTION 3



FIGURE E-35. PCA PRESSURE CELL IN CLOSE PROXIMITY TO REINFORCING BAR, TEST SECTION 7



FIGURE E-36. WOODEN WEDGE DRIVEN AGAINST PCA PRESSURE CELL, TEST SECTION 7







FIGURE E-38. DAMAGE TO CORK LINER AROUND SIDES OF PCA PRESSURE CELL, TEST SECTION 7

Post Mortem Investigation of the Kansas Test Track, Part II, 1979 US DOT, FRA
U.S. DEPARTMENT OF TRANSPORTATION FEDERAL RAILROAD ADMINISTRATION

Washington, D.C. 20590

Official Business

PENALTY FOR PRIVATE USE, \$300

POSTAGE AND FEES PAID FEDERAL RAILROAD ADMINISTRATION DOT 516



.

PROPERTY OF FRA RESEARCH & DEVELOPMENT LEDSARY

.